

# HISTORIC COSTUME

LESTER













# HISTORIC COSTUME











From *Godey's Lady's Book*, 1865

# HISTORIC COSTUME

A Résumé of the Characteristic Types  
of Costume from the Most Remote  
Times to the Present Day

By

KATHERINE MORRIS LESTER

Director of Art Instruction, Public Schools,  
Peoria, Illinois

Illustrated by ILA McAFEE



THE MANUAL ARTS PRESS  
PEORIA, ILLINOIS

COPYRIGHT

1925

THE MANUAL ARTS PRESS

PEORIA, ILLINOIS

22C65



*Printed in the United States of America*





In Memory of Happy and Profitable Years of  
European Study and Travel

Dedicated  
To  
FANNIE ROUSE WINCHELL

*A little lady, rare and fine—  
A friend of mine.*





## PREFACE

**C**OSTUME has always been influenced by contemporary conditions—social, religious, and political. A knowledge of its development from the earliest beginning involves extended research, the study of history, and the translation of numerous old French texts. For this reason the author believes that a résumé of such study limited to a single volume will be helpful to the student of the subject.

The aim has been to cover the periods of costume as represented by those nations most influential in matters of dress from remote times to the present, emphasizing the most marked of these influences and touching upon minor details. The work deals primarily with the variation and development in the costume of women. Men's dress is also considered, and the most important changes noted and closely followed.

The author makes no claim to originality in presenting the illustrations of the text. They have all been gathered from the most reliable sources. Only authentic descriptions and historic representations yield trustworthy information on the costume of the past. For this reason recognized sources only have been drawn upon.

Though nothing worthy the name of costume can be considered as existing before the discovery of the arts of weaving, dyeing, tanning, and working in metal, still the faint beginnings of dress may be detected in the prehistoric decoration and ornamentation of the body.

For the earliest records of costume the interest turns to ancient Egypt. In Egypt, the cradle of civilization, were worked out many of the first problems in dress. The recovered monuments scattered throughout the world present the dress of that age-old period with all the accuracy and detail of a modern fashion plate.



Inasmuch as the civilization of Asia antedates that of Europe, a study of those Asiatic races bordering on the Mediterranean and Red Seas is a natural sequence in the history of costume.

From the marble figures in relief found in the ruins of the ancient city of Persepolis comes much of our knowledge of the dress of the Persians. Engraved gems and coins have also yielded a fund of illustrative material. On the Trajan column in Rome, the arch of Septimius Severus, and that of Constantine, are pictured the Parthians and Dacians in the characteristic costumes of their land. Moreover, sculptures and vases in the museums of Greece and throughout Europe yield authentic records of the dress of these Asiatic peoples.

In the ancient world Greece represents the zenith of achievement in arts and letters. In this wonderful land there still remains a wealth of material for the student of costume. Sculptures, mosaics, vases, and sepulchral monuments furnish an accurate and detailed record of the classic world.

Likewise the Roman world is preserved to us in sculptured monuments, portrait busts, and ancient paintings.

Passing to the Middle Ages we find the sources of information quite diverse. Sculptured tomb reliefs, stained glass windows, and wonderful old tapestries picture the men and women of the period with a truth and accuracy that make them living personages rather than musty historic figures.

From the beginning of the sixteenth century France has been the acknowledged leader in matters of fashion. For this reason the writer has considered French fashion exclusively through the period of the Renaissance (1500-1700) and the succeeding centuries. In so noting French fashion, a knowledge may be gained of fashions throughout Europe, and in the colonies of America.

American fashion has accepted the main lines of French fashion, adapting them to the needs and convenience of life in America. American colonial costume and American

dress down to the present day bear the stamp of this French origin. There may also be traced in the American dress Spanish and Italian influences, which, coming through France, made their contributions to the modern styles.

The records contained in tomb monuments, old French prints, and in the works of eminent painters and sculptors, on down to the array of modern fashion books, present a galaxy of costume bewildering in its diversity, and yet bold and direct in the leading types which stand forth as period costume.

This work is the result of extensive travel, study of the ancient monuments of Greece and Egypt, combined with much research relative to modern dress.

May it find its own peculiar niche in the world of service!

KATHERINE MORRIS LESTER.





# CONTENTS

	PAGE
From <i>Godey's Lady's Book</i> , 1865.....	<i>Frontispiece</i>
Color Notation .....	12
List of Plates.....	13
List of Drawings.....	15
CHAPTER	
I. The Beginnings of Costume.....	17
II. Egyptian Costume—Ancient Times.....	21
III. Asiatic Costume—Ancient Times.....	38
IV. Greek Costume—700 B. C.-53 B. C.....	47
V. Roman Costume—53 B. C.-476 A. D.....	67
VI. Costume of the Middle Ages—France—476-1500.	78
VII. The Renaissance in France—1500.....	108
VIII. The Renaissance in France—1600.....	122
IX. French Costume—1700 .....	139
X. Colonial Costume in America—1620-1781.....	161
XI. American Costume—1781-1900 .....	181
XII. American Costume—1900- .....	213
Bibliography .....	237
Index .....	238

## COLOR NOTATION

### THE MUNSELL SYSTEM

THE matter of exact color in early costume lies to a considerable extent in the field of conjecture. Many of the original sources of costume—sculptures, vase paintings, mosaics and prints—are either uncolored or the color is not sufficiently well preserved to furnish exact data. Further, it has been found that considerable variation in value and chroma exists among the best extant plates of costume in color.

The colors given in the accompanying notation are based upon a careful study of the most dependable sources, and in each instance the aim has been to preserve the color atmosphere of the period.

THE AUTHOR.

## LIST OF PLATES

PLATE	PAGE
✓ I. Egyptian Costume—Ancient Times.....	25
II. Egyptian Costume—Ancient Times.....	27
III. Asiatic Costume—Ancient Times.....	39
IV. Asiatic Costume—Ancient Times.....	41
V. Grecian Costume—700 B. C.-53 B. C.....	51
VI. Grecian Costume—700 B. C.-53 B. C.....	55
VII. Grecian Costume—700 B. C.-53 B. C.....	59
VIII. Roman Costume—53 B. C.-500 A. D.....	69
IX. Roman Costume—53 B. C.-500 A. D.....	71
X. Costume of the Middle Ages— 600-1100.....	81
XI. Costume of the Middle Ages—1100-1350.....	83
XII. Costume of the Middle Ages—1395-1495.....	97
XIII. Costume of the Middle Ages—1386-1498.....	101
XIV. The Renaissance in France—1500.....	111
XV. The Renaissance in France—1500.....	113
XVI. The Renaissance in France—1500.....	115
XVII. The Renaissance in France—1600.....	125
XVIII. The Renaissance in France—1600.....	127
XIX. French Costume—1700.....	141
XX. French Costume—1700.....	143
XXI. French Costume—1700.....	155

PLATE	PAGE
XXII. French Costume—1800-1814.....	159
XXIII. Colonial Costume in America—1620-1725.....	167
XXIV. Colonial Costume in America—1710-1777.....	177
XXV. American Costume—1790-1824.....	185
XXVI. American Costume—1832-1850.....	191
XXVII. American Costume—1820-1865.....	197
XXVIII. American Costume—1873-1897.....	201
XXIX. American Costume—1902-1915.....	215
XXX. American Costume—1913-1916.....	221
XXXI. American Costume—1917-1921.....	229
XXXII. American Costume—1917-1918.....	231
XXXIII. American Costume—1900-1920.....	235

## LIST OF DRAWINGS

FIG.		PAGE
1.	Tattooed head of the Maori.....	18
2.	The Princess Sedet.....	22
3.	Skirts of Egypt.....	23
4.	Head-dress of a lady.....	29
5.	Beards and crowns.....	30
6.	Egyptian sandals .....	32
7.	Egyptian ornament .....	34
8.	Lady rouging herself .....	35
9.	Egyptian kohl-pot .....	36
10.	A Phrygian .....	42
11.	Head of an Amazon.....	43
12.	Costume from a cameo.....	43
13.	A Persian .....	45
14.	The peplos .....	48
15.	Doric chiton .....	48
16.	Double girded chiton.....	49
17.	Ionic chiton .....	50
18.	Ionic chiton showing adjustment of girdle.....	52
19.	Ionic chiton showing adjustment of girdle.....	53
20.	Greek ornament .....	60
21.	Pyxis and fans.....	64
22.	Roman ornament .....	74
23.	Roman footwear .....	76
24.	Byzantine ornament .....	85
25.	Head coverings .....	86
26.	Gothic tracery .....	91
27.	Surcoats and nets.....	92
28.	The twelfth-century fitted garment.....	94
29.	Pattens .....	99



FIG.	PAGE
30. Steel corset worn by Catharine de' Medici.....	120
31. Chopines .....	128
32. <i>Paniers à coudes</i> .....	145
33. Head-dress à la Belle Poule.....	149
34. <i>Pouf au sentiment</i> .....	150
34-a. Caricature of period.....	151
35. Shoes of 1780 and 1790.....	153
36. Charlotte Corday cap.....	157
37. Titus coiffure .....	160
38. A clog .....	165
39. Wigs .....	169
40. The calash .....	178
41. Wedding dress of 1813.....	186
42. The canezou .....	195
43. The hoop .....	198
44. Coiffure of the early '70's.....	199
45. Hats of the '70's.....	202
46. Hoop, tilter, and trail.....	203
47. "Tied-back" time .....	204
48. The bustle .....	205
49. Riding habit of the '70's.....	207
50. Fashions of the '90's.....	210
51. Shirt-waist suit .....	216
52. Chanticleer .....	217
53. Dress of 1912, showing basque and tunic.....	222
54. Revival of the styles of '83.....	223
55. The peg-top silhouette.....	224
56. The Balkan blouse.....	225
57. Styles of 1916.....	226
58. Hats of 1916.....	227
59. Red Cross uniforms.....	232
60. Sport suit .....	233
61. Riding clothes of 1924.....	233

## CHAPTER I

### THE BEGINNINGS OF COSTUME

FROM the beginning the subject of costume has received a full share of the world's interest and attention. Dress in this twentieth century is so much a matter of course that we scarcely ever think of its beginnings in the remote past. And yet the impulse toward adornment was just as marked and vital in our primitive ancestor in his paint, tattoo, and human bones, as it is today expressed in milady's rouge, feathers, and fur. Looking back through eons of time we find that man, in that dim, distant age, lived in caves and under rocky cliffs. He was concerned mainly with the securing of food and the preservation of his life. Dress did not exist. However, the impulse toward dress grew out of this early life which was dedicated to the hunt and the chase. [Evidence is unmistakable that costume as we know it today emerged after a long and tedious process of evolution.] The beginnings of dress, that from which dress came to be, was in the form of body decoration. The painting, cutting, and tattooing of the skin are forms of body decoration, which were the first steps toward modern dress.]

The ambition to be distinguished from his fellows no doubt stimulated the desire toward dress. This desire grew out of certain discoveries which had been made. When this primitive hunter, stained with his own blood or that of the vanquished, returned to his tribe, he found these evidences of his might greeted with respect and admiration. Physical power in this remote day was the only standard of worth. These blood-stains were mute witnesses to a courage and might which compelled the veneration of his fellows. So gratifying was this distinction to this primordial leader that he sought for more permanent badges

of bravery. Now, the blood-marks of courage were left upon the body as long as possible. When finally they wore off, the scars remained. Out of this admiration of scars and blood-marks upon the human skin there arose a dim sense of beauty. Naturally the desire for continued notice




Fig. 1. Tattooed head of the Maori, New Zealand. The form of design is traditional; every part has a meaning

and favor gradually led these early leaders to devise new schemes of decoration. The colored clays that were so plentiful about them were the next source of inspiration. They began to daub their faces, heads, and bodies with this colored pigment. Soon these daubs were expressed at regular, measured intervals. Thus a sense of rhythm and the idea of pattern began.

The days of crude face painting, however, do not belong alone to the primitive past.<sup>1</sup> The present-day savage of Australia carries with him a supply of white earth and red and yellow ochres.

Daily he touches up his face with spots of color, and on festive occasions he carefully paints his entire body in pattern. The Adamese, who live in the Adaman Islands of the Indian Ocean, and are the lowest order of savages, paint the entire body with a pale green when in mourning, with white for decorative purposes, and with yellow ochre, mixed with fat, for facial decoration. Even as late as the last century, the American Indian when about to go on the war-path covered his face with rhythmic patches of yellow, red and blue. The modern rouge and the patch, which had such a wide-spread vogue in the eighteenth century, are only later refinements of this same age-old body painting.

Soon another form of body decoration found expression. The cutting edge had been discovered. Knife blades

<sup>1</sup>*Color News*, June, 1924. Munsell.

were made of bone, horn, flint, and other stones and finished with a fine point and edges. With these new tools the primitive fashion leader amused himself by cutting and slashing his skin in forms of pattern. This was followed by tattooing, a method of marking the skin with slight incisions and adding coloring material. This form of decoration expressed itself in elaborate pattern. (Fig. 1.) Even today this custom is wide-spread, being found among the South Sea Islanders, the Burmese, the Chinese, and Japanese. Among the recovered relics of the ancient cave men, remnants of ground ochre and other colors used in painting and tattooing have been found.

The second impulse toward dress took the form of body ornamentation. Now the coveted marks of distinction were ornaments added to the body. Various peoples in many parts of the world have worn a bit of bone, wood, or stone run through a hole in the lip, nose, or ears.

Both he and his people were black as sloes,  
For the region they lived in was torrid;  
And their principal clothes were a ring through the nose  
And a patch of red paint on the forehead.

—THOMAS HOOD, THE YOUNGER.

Bye and bye these bits of facial ornamentation were supplemented by the trophies of war and the chase. The leader now wore his necklace of teeth, bone, or polished stones, and his waist-belt of skin. It is this same necklace of teeth, bone and, in time, beads, hanging about the neck, that later, after the discovery of the art of weaving, developed into the tunic, waist, and jacket. In like manner it is the waist-belt of feathers, bones and other trophies that gradually became the apron, and later was transformed into the modern skirt.

The protective dress, namely, the wearing of skins, furs, and bark for protection, came after ages of decoration and ornamentation.

The first problems in costume proper were worked out by those early peoples living along the shores of the Mediterranean.

It was here after the art of weaving was discovered that we find the necklace of beads, teeth, and fringe developed into the tunic and mantle, and the primitive waist-belt lengthened into the skirt.

[The ancient records that have been preserved picture the king and men of wealth wearing the long skirt dependent from the waist and the mantle hanging from the shoulders. Soon woman adopted the long robes of her lord. There was no need for the short skirt for the woman of that day. Her life was restricted to home and home duties. Her sphere was purely domestic. Within doors the long tunic and skirt were worn with ease and comfort. This long skirt finally became an established type of conventionality in woman's dress upon which the world of fashion has since continued to play but never completely changed. The long skirt and mantle are distinctly the dress of antiquity.]

Modern dress, that is, the fitted dress or costume as we know it today emerged during the Middle Ages, when Frank, Gaul, and Latin mingled. The impulse that shaped modern dress came from the North. There, climatic conditions necessitated a more clinging garment. The long, loose tunic and mantle were not sufficient to sustain the warmth of the body, so these men of the North wrapped their legs in cloth or skins. They were looked upon and ridiculed by the Romans as "trouserred barbarians." As the Romans, however, pushed their conquests farther north they were compelled to adopt the same costume. Though trousers are undoubtedly of oriental origin, it is in this period of the Middle Ages during the fusion of the races that trousers became the established type of men's dress, while the skirt remained the conventional dress of women.



## CHAPTER II

### EGYPTIAN COSTUME

(ANCIENT TIMES)

**A**MONG the great civilizations of the past, that of Egypt opens the first record of costume. This record is clearly and unmistakably written in temple, tomb, and mummy-case, in statue, design, and colored hieroglyphics. The Egyptians were the first to leave their records of costume in a form so durable that they could not be easily destroyed. The development of dress in that distant corner of Africa takes on a peculiar interest as we see not a few of our more modern types dating back two or three thousand years before Christ. Our sources of information concerning this remote period are quite as realistic as a modern fashion plate, for they are none other than the pictures of Egyptian life painted upon the walls of tomb and temple. Today these drawings are quite as distinct, and in many instances the coloring quite as fresh and bright as when left by the hand of the primitive artist. Here we may see the laborer, the merchant, the king, the rich, the poor, each clad in the garments of his class.

These ancient records show that the lower classes of this country, especially in the earliest periods (2900 B. C.-2350 B. C.), wore no clothing whatever, and the upper classes very little. Gradually clothing became more general, and in the Fifth Dynasty (2700 B. C.-2500 B. C.), the loin cloth had long become the dress of the peasants and a short skirt or apron was adopted by the higher classes. The materials were very thick and coarse, and in all probability made of flax, which was abundantly cultivated in Egypt. A kind of matting is also known to have been worn by the lower classes.

Though on the whole there is greater variety in the early costume of men, yet the tendencies in the general development of the costume of the two sexes are quite similar. During the early dynasties (2550 B. C.-1530 B. C.) there is a sameness in the costumes of the women of all classes. This characteristic dress consisted of a long, straight tunic, reaching from the bust to the ankles. The shoulders and breast were uncovered, and the tunic kept in place by straps over the shoulders. (Fig. 2.) These tunics were extremely scant, and drawn so closely about the figure that not even the suggestion of a fold appears. A small number of sculptured figures of this type have



Fig. 2. The Princess Sedet

been found, and the only possible means of telling that the figures were intended to be covered is the almost imperceptible edge about the neck and ankles. Recently, while in Egypt, a number of American women secured photographs of this most ancient type, and delighted in sending them home to their American tailors, declaring, "Now we have found the original of the hobble-skirt." Other records show the woman of Egypt clad in a short, scant tunic of one piece of material, with a jeweled belt connected by straps with a jeweled collar. Sometimes a piece of material was thrown about the shoulders and fastened to the collar at either side of the front. Innumerable rows of rich beads were worn about the neck, forming a mass of color reaching to the waist.

From the earliest times the men of the higher classes wore a short simple skirt which became the foundation for all later developments. The skirt was usually a straight piece of some white material, and was wrapped about the body from right to left so that the edge came in the middle of the front. (Fig. 3, a.) This skirt later became longer and wider, reaching sometimes to the

ankles. Among the higher classes the form gradually changed, and it was arranged with a triangular fold at the front, which was so elaborated at times that it extended at the lower edge from one side of the figure to the other. (Fig. 3, b.) As the coarser materials were given up, finer and



Fig. 3. Skirts of Egypt. a, ancient skirt; b, later skirt; c, the two skirts; d, e, f, draped skirts; g, skirt with the golden border; h, oldest form of royal skirt

more transparent materials were used. It was then necessary to wear a second skirt under the first. (Fig. 3, c.) Originally these two skirts were very similar, but as time went on the outer skirt was gradually shortened in front and lengthened at the back. At the close of the Eighteenth Dynasty (1350 B. C.) the underskirt became longer and wider and the outer one looped in puffs over it, giving the first suggestion of drapery. (Fig. 3, d.) Gradually these two skirts underwent another change; the under one became full and plaited, and the upper one evolved into a strip or sash of linen folded about the hips and tied in front. The manner of adjusting the sash varied; sometimes it reached down over the back of the legs, and was gathered up short in front, and sometimes it was wrapped twice around the body. (Figs. 3, e and f.)

For festive occasions the great lords of Egypt wore a short skirt similar to the oldest types, made more elegant with trimmings of gold and a golden clasp at the girdle.

The front of these skirts was rounded off, and from the center back to the front ornamented with a plaited piece of gold material, which gave an added touch of elegance to the costume. (Fig. 3, g.) The king's skirt was similar in form—that is, with the rounded edges—but with an added strip of material which, hanging from the girdle under the skirt, could be seen below. The addition of a lion's tail at the back completed this most ancient form of royal skirt. (Fig. 3, h.) In later times it became the proud privilege of others besides the king to wear the shend'ot, the royal skirt. Many of the ancient monuments show the same skirt minus the lion's tail worn by kings, priests, and other dignitaries.

The one badge of royalty in the king's dress which was reserved for him alone was the king's apron, which no doubt succeeded the earlier type. This apron hung from the girdle in front, and was richly ornamented with colored feathers, lion heads, and other devices. Usually a row of asps, always the royal insignia, bordered the apron. (C, Plate I.)

With the Eighteenth Dynasty (1545 B. C.-1350 B. C.) there were many changes in dress, due in great measure

#### COLOR NOTATION—PLATE I

- A*—Tunic, white; stripes, Y  $\frac{3}{8}$ ; border, Y  $\frac{3}{8}$ , Y  $\frac{7}{8}$ , Y R  $\frac{3}{8}$  (probably some gold). Girdle, R  $\frac{3}{8}$ . Collar, white, R  $\frac{7}{8}$ , B  $\frac{1}{8}$ . Hat, Y  $\frac{7}{8}$ , flower, R  $\frac{3}{8}$ , G Y  $\frac{3}{8}$ . Head-dress, Y  $\frac{3}{8}$  (probably gold). Ribbon, R  $\frac{3}{8}$ . Bracelets, Y  $\frac{3}{8}$  (probably gold).
- B*—Tunic and mantle, white. Collar, Y  $\frac{3}{8}$ , B G  $\frac{3}{8}$ . Armlets, R  $\frac{1}{8}$ ; banding, white. Head-dress, Y  $\frac{3}{8}$ ; ribbon, white. Sandals, Y  $\frac{5}{8}$ .
- C*—Skirt, white. Apron, center Y  $\frac{7}{8}$ ; spots R  $\frac{1}{8}$ ; colors to side of center, B G  $\frac{3}{8}$ , R  $\frac{1}{8}$ , B G  $\frac{3}{8}$ . Girdle, Y  $\frac{7}{8}$ , R  $\frac{1}{8}$ , B G  $\frac{3}{8}$ . Chest covering, G  $\frac{3}{8}$ ; border, Y  $\frac{7}{8}$ , Y  $\frac{3}{8}$ . Sleeves, Y  $\frac{3}{8}$ ; bands, G  $\frac{3}{8}$ . Collar (1), R  $\frac{1}{8}$ ; dots, Y  $\frac{7}{8}$ ; (2), white; points, B G  $\frac{3}{8}$ ; (3), R  $\frac{1}{8}$ ; dots, white. Head-dress, Y  $\frac{7}{8}$ , B G  $\frac{3}{8}$ ; band and ornament Y  $\frac{3}{8}$ .
- D*—Tunic, white. Girdle, R  $\frac{1}{8}$ . Collar, R  $\frac{7}{8}$ , G Y  $\frac{7}{8}$ , B  $\frac{1}{8}$ . Head-dress, Y  $\frac{3}{8}$ , Y R  $\frac{3}{8}$ . Bracelets, white, R  $\frac{7}{8}$ , B  $\frac{1}{8}$ . Sandals, Y  $\frac{5}{8}$ . Ring, Y  $\frac{3}{8}$ , B  $\frac{1}{8}$ .
- E*—Tunic, G Y  $\frac{3}{8}$ ; border,  $\frac{3}{8}$ ; spots, Y  $\frac{5}{8}$  (probably metal discs). Girdle, R  $\frac{1}{8}$ . Armlets, B  $\frac{1}{8}$ ; bands, R  $\frac{1}{8}$ . Anklets, B  $\frac{1}{8}$ ; banding, white. Shoulder straps, Y  $\frac{3}{8}$ , Y R  $\frac{7}{8}$ . Collar, Y  $\frac{3}{8}$ , R  $\frac{3}{8}$ . Head-dress, white, G Y  $\frac{3}{8}$ ; ribbon, R  $\frac{3}{8}$ .
- F*—Tunic, white. Mantle, white. Collar, white, Y  $\frac{3}{8}$ , R  $\frac{1}{8}$ , B G  $\frac{3}{8}$ . Head-dress, Y  $\frac{3}{8}$ , Y R  $\frac{7}{8}$ , B G  $\frac{3}{8}$ ; ribbon, R  $\frac{1}{8}$ .





A B C D E F

PLATE I—EGYPTIAN COSTUME—ANCIENT TIMES

- A*—The dress of an Egyptian princess. The bell-shaped tunic fitting at the shoulders and flaring toward the lower edge is a type of dress worn only in the royal household. The head-dress is an ornamented wig of the period.
- B*—A simple white tunic worn with the mantle which in later days developed into the modern shawl.
- C*—A king of Egypt. The badge of royalty is seen in the king's apron, which hangs from the girdle, and in the head-dress, or pschent, ornamented with the royal asp.
- D*—A queen of Egypt with the sacred bird, the vulture, as a head-dress.
- E*—A lady of rank wearing the straight tunic, armlets and ankle rings.
- F*—An Egyptian prince. The distinguishing mark of a prince was the badge at the side of the head, descending to the shoulders.



to the new relations with Western Asia and the far reaching commercial interests of the country. It was during this period that the coarser materials gave way to the finer, and cotton and linen began to be extensively used. At this time the value of dyes seems to have been well known. This period witnessed the entrance of a new fashion—that of covering the upper part of the body and adopting a short shirt as an article of dress. These shirts were usually open on the right side, while the arm passed through a short sleeve on the left. This garment gradually evolved into a robe with sleeves covering the entire figure, and has been frequently pictured as the robe of the priest-ess. (*D*, and *G*, Plate II.)

The women's dress of this period resembled that of the men in possessing a sleeve for the left arm, leaving the right arm free. It is also to this later period, no doubt, that the bell-shaped tunic belongs—fitting close at the shoulders and flaring toward the lower edge. (*A*, Plate I.)

During the Nineteenth and Twentieth Dynasties (1350 B. C.-1090 B. C.) the wearing of a long mantle became fashionable. (*B*, Plate I.) This was draped sometimes under one arm and over the other; sometimes over both shoulders and fastened in front over the breast. Later this mantle became a short mantilla, which was often edged with fringe. (*D*, Plate I.) This type of wrap was no doubt the forerunner of our modern shawl. The fringes were made by the projecting threads of the warp, twisted together and tied at the end in one or more knots to prevent their unraveling. Herodotus says that they had the

---

#### COLOR NOTATION—PLATE II

*A*—Head-dress and loincloth, white.

*B*—Head-dress, white; stripe, R  $\frac{5}{8}$ . Tunic, white.

*C*—Tunic, white. Wig, Y R  $\frac{3}{4}$ .

*D*—Tunic, white. Collar, white, R  $\frac{5}{8}$ , B G  $\frac{5}{8}$ , Y  $\frac{7}{8}$ . Head-dress, white.

*E*—Head-dress and skirt, white; stripe, R  $\frac{5}{8}$ . Collar, white, B G  $\frac{5}{8}$ , R  $\frac{5}{8}$ , G Y  $\frac{7}{8}$ .

*F*—Skirt, white; stripe, G  $\frac{7}{8}$ . Collar, white, R  $\frac{5}{8}$ , B G  $\frac{5}{8}$ , Y  $\frac{7}{8}$ . Head-dress, white, G  $\frac{7}{8}$ .

*G*—Tunic, white; stripe, R  $\frac{5}{8}$ . Head-dress, white.



*A B C D E F G*

PLATE II—EGYPTIAN COSTUME—ANCIENT TIMES

*A, B, E, F*—A group showing the simple forms of skirt worn in the earliest periods of Egyptian history. The caps and head-dresses were a protection from the rays of the sun.

*C*—A peasant woman wearing the long straight scant tunic.

*D*—A priestess wearing the simple tunic, the embroidered collar, the head-dress, and carrying the key of life.

*G*—A priestess in robe of striped material and wearing the usual head covering.

custom of leaving a fringe to their pieces of linen, which, when the dresses were made, formed a border round the legs. This kind of dress was called a calasaris, but was not universally worn. The dresses in the peasant classes followed in the main the general tendencies of the upper classes—the women wearing the long straight tunics with or without sleeves (*C*, Plate II.), and the men clinging to the simple skirt and shirt.

In the oldest period, that of the Old Empire, the dresses of women were more often colored than white. Later, during the Middle Empire, various colors were worn, especially green. The use of color in dress, however, largely gave way among the upper classes to the finest and whitest of linen, the merit of the clothing consisting in its absolute purity and its fineness of texture.

The fashionable coiffure of five thousand years ago reveals a marvel of the wig-maker's art. (Fig. 4.) It may appear singular that so warm a covering for the head should have been adopted by both the men and women of Egypt. These coverings, however, were devised especially to keep the head cool, serving the same purpose as the modern turban. The women of Egypt often kept the hair short, and the men always shaved the head. The wig, built upon a netlike surface, allowed the heat of the head to escape, and at the same time served to protect the head itself. The fashion in women's coiffure varied according to the period. Under the Old Empire the fashion tended toward huge constructions reaching to the shoulders. (Fig. 2.) This style continued general, the only change being fringe-like arrangement of the ends. The Eighteenth Dynasty, which wrought so many changes in fashionable attire, also introduced a greater variety in the styles of hair dressing. The women of this period seemed to get away from the stiff conventional form of the past, and adopted a more graceful natural arrangement—the hair falling in soft curls without concealing the contour of the head. Later the styles reverted to the past, and the woman of the Twentieth Dy-

nasty allowed her wig to fall in a heavy mass over each shoulder to the waist.

Styles in men's wigs followed the dictates of fashion as did those of the women. Originally short hair arranged in little curls seems to have been the fashion. This wig



Fig. 4. Head-dress of a lady, from a mummy-case  
(After Wilkinson)

was set low on the forehead and covered the ears. The second type was the long-haired wig, the hair falling thick from the crown of the head to the shoulders. Variations of these two forms of coiffure succeeded each other, until in the Twentieth Dynasty we find long freely waving hair.

We in our day have grown rather accustomed to the popular use of artificial hair, and in view of the modern weakness in that direction cannot judge severely our sister of antiquity. Another custom, however, closely allied to this, which the men of Egypt adopted, we cannot view with quite the same leniency—that of wearing an artificial beard. The Egyptian regard for absolute cleanliness led them to discard the natural beard. From the most primitive times



the beard had been regarded as a badge of manly dignity. Consequently, in order to command respect from the populace, the dignitaries of the country, on certain occasions, appeared with artificial beards fastened beneath the chin. The style of the beard was determined by the importance



Fig. 5. Beards and crowns. a, beard of Osiris; b, crown of Lower Egypt; c, artificial beard and crown of Upper Egypt; d, king's beard and the pshent

of the person wearing it. Private citizens usually wore a small beard, probably two inches in length. (Fig. 5, c.) That of the king was of considerable length (Fig. 5, d), and that of the gods turned up at the end. (Fig. 5, a.)

Aside from the wigs proper, members of the royal family wore a covering for the head which was especially symbolic of office and rank. The state head-dress of the Egyptian king, the pshent (Fig. 5, d—b and c combined), symbolized the union of Upper and Lower Egypt. A helmet-like cap, probably derived from the Persians, was also worn, made of thick stuff with a nap and ornamented with the royal asp. The distinguishing mark of a prince was the badge at the side of the head, descending to the shoulders and edged with gold fringe. (*I*, Plate I.) The vulture, the sacred bird, protector of the king in battle, appears upon the head-dress of the queen. (*D*, Plate I.) This was a very elaborate arrangement, the plumage entirely covering the head. Besides these royal head-dresses, wreaths, colored ribbon, and the lotus flower were often twined round the hair.

In many works of art of the early Egyptian period the men in everyday life are pictured wearing close-fitting caps and hoods. In many cases the hood hangs down over the shoulders in two broad bands or sometimes plaited lappets. (*B* and *E*, Plate II.) This type of head-dress is also part of the kingly attire in the most ancient period.

The heads of female figures are frequently covered with a hood, which is often close-fitting and again often laid in a number of folds. The usual form of head-dress was made of one piece of linen or striped material, cut in semi-circular fashion with a band for the head left in the center of the straight edge.

✓With peculiar interest we have seen many of the Egyptian costumes revived down through the centuries, and we note that even the very modern fashion of carrying a walking-stick dates back to remote antiquity. (*D*, Plate I.) The Egyptian canes were usually four to six feet in length and surmounted by a flower or some similar ornament. Many were decorated with gilding and color, and were frequently inscribed with the owner's name.

Though we find that the earliest form of protection for the feet partook of the nature of sandals, it is perhaps true that shoes or low boots, many of which have been found in Thebes, were not in general use in Egypt until after the conquest of Greece. The warmth and mildness of the East rendered a close warm shoe unnecessary; and indeed at the present day they have much of the character of slippers. The foot thus unconfined by tight shoes retained its natural shape and freedom of motion.

Again we may go to the records written upon the walls of a temple at Thebes, and gaze upon the ancient shoemaker at his work in the early days of Thothmes III, who ascended the throne about 1495 B. C. and during whose reign the exodus of the Israelites occurred. The shoemakers are both seated upon low stools (real specimens of such stools may be seen in the British Museum), and are both busily engaged in shaping the sandals then worn in Egypt. The first workman is piercing with his awl the leather thong

at the side of the sole through which the straps were passed which secured the sandal to the foot. His fellow-workman is equally busy sewing a shoe and tightening the thong with his teeth.

The higher classes paid a great deal of attention to the beauty of their sandals. Those worn by men and women of the upper classes were usually pointed and turned up at the end. Some had a sharp flat point; others were nearly round. (Fig. 6, a, c, d.) Many were made of a woven or




Fig. 6. Egyptian sandals.

interlaced work of palm leaves and papyrus, frequently lined with cloth. Sandals have been recovered which show the painted figure of a captive upon the inside lining of the sole. (Fig. 6, b.) This humiliating position was considered as one befitting the enemies of the country.

Among the Egyptians, ornament and design as well as color were of serious moment. Color and pattern had real significance to these people of long ago. Down through the centuries these same designs have continued, and though their early significance is often unappreciated today, the inspiration which made them possible at this remote period found its source in the deep and sincere religious life of the people.

The winged globe (Fig. 5) is one of the best known of the Egyptian ornaments; it was the emblem of the great sun-god, Ra, who took precedence over all other gods. The sun symbolized life, power and eternity. The winged globe represented the sun being carried on wings through the heavens. The wings suggested the protection the sun-god assured to his people in life and in death. For this reason it was placed over the entrance to temples and tombs, and

used as a decoration upon garments, head-dress and jewelry. It also ornamented the ruler's throne and his chariot. Further, a body was never placed in a mummy-case that did not have a winged globe as part of its decoration. The conventional form of the cobra, representing the generative power of the sun, is often seen on either side of the center.

"As Ra and his descendants are rulers of earth and heaven, all must be submissive to the great rising sun, or there will be no peace on earth or in the hereafter." This hymn, written to the rulers, was preserved on an old piece of parchment.

The scarabæus, or sacred beetle of the Egyptian, was the emblem of immortality and, according to Pliny, was worshipped as one of the gods of the country. (Fig. 7, a.) The designs inspired by this sacred beetle were used generally in decoration. When cut in stone they were used for rings, necklaces and other trinkets.

The lotus and papyrus furnished the inspiration for the more delicate patterns. (Fig. 7, b and c.) These were conventionalized in various ways. Many of the newly opened tombs disclose a wealth of design. Beautiful decorations in color not only embellish the interesting contents of the tombs but likewise enrich the walls of corridors and tomb chambers.

By its annual inundations the Nile fertilized the valley, giving life to the various crops. Hence the great water-god received the reverence of the people whom he protected. A simple wave-like design, symbolic of the life-renewing stream, is seen over and over again. The soft green color in which this has been worked out is known as "Nile green." (Fig. 7, d.)

The colors most generally used in fabrics and design appear to be green, yellow, red, light blue, tan and black. These colors are believed to have been produced by wonderful dyes. Many of the tombs have yielded cakes of color which indicate that mineral dyes and later vegetable dyes were used.



The Egyptian woman, as the women of other and later civilizations, had her jewels and ornaments, especially earrings, armlets, and ankle-rings. At all periods both men and women wore colored embroidery necklets, bracelets for the upper and lower arm, and anklets of the same material. Of course these were not confined to embroidered materials, but were of gold and silver as well. Many of the necklaces were made with pendants in the form of figures of the gods or of animals sacred to them, or of amulets to which magical powers were attributed. The rings were made of gold, silver, bronze, and faience. Sometimes the bezels were solid and immovable; sometimes they were inlaid with scarabs inscribed with various devices or the name of the wearer, and, as they revolved, were used as a personal seal. The red carnelian, carved in the design of a scarabæus, was the stone most used in the Pharaoh's ring, as his official seal. The seal was of great importance, for it took the place of a key in protecting treasure, at a time when keys were seldom if ever used. The door of the treasure house or treasure chest was secured by wooden bolts, set in mud and stamped with a seal. To break




Fig. 7. Egyptian ornament. a, scarabæus; b, lotus pattern; c, papyrus pattern; d, Nile pattern; e, f, Egyptian fans



a seal, particularly a royal seal, was considered a crime, and the offender was severely punished. The seal ring carried with it all the power and prestige of the owner. The bracelets were often inlaid with precious stones or colored paste. After the Twenty-sixth Dynasty, the ends, owing to Phœnician influence, often terminated in lions' heads.

Beads were used in great profusion by both men and women, and were evidently considered quite choice as an ornament. They have been found cut into various shapes, round, rectangular, oval, and ob-

long; and made of emerald, agate, carnelian, lapis lazuli, amethyst, rock crystal, onyx, jasper, garnet, gold, silver, glass, faience, clay, and straw. Several painted figures show rows of beads about the neck, with pendants of beads hanging over the breast like a mantilla.

In accessories of the toilette the Egyptian lady was by no means behind her modern sister. Fig. 8, from the Papyrus of Turin, shows a lady rouging herself. Oils, unguents, and perfumes were in common use. Many of the tombs have yielded beautiful vases and jars of the finest alabaster and porphyry; filled with various oils and scents, they were placed in the tombs at the time of burial. Chief among all the devices which made for feminine beauty was that of the application of stibium to the eyes. The ladies were wont to stain the eyes and eyebrows with this mixture, making the eye appear larger and adding to its beauty. This custom still exists in Egypt. The same properties are also ascribed to kohl, which is a mixture of various ingredients. The kohl was kept in curious little "kohl-pots," many of which have been recovered. These are of various forms and made of alabaster, steatite (soap-stone),



Fig. 8. Lady rouging herself  
(From the Papyrus of Turin)

glass, ivory, or wood. Usually they are from three to six inches high. (Fig. 9.) The stick with which the kôhl was applied to the eyes was made of wood, bronze, or glass, and was thicker at one end than at the other. The thick




Fig. 9. Egyptian  
kohl-pot

end was moistened, dipped into the powder, and then drawn along the eye-brow. The custom of painting the eyelids or the parts immediately under them is contemporary with the earliest dynasties, and seems to have been common all over the East. In II Kings 9:30 we read that Jezebel "put her eyes in stibium"; and in Jeremiah 4:30 the daughter of Zion is told that her lovers would seek her life even though "she rent her eyes with stibium"—referring to the wide-open appearance the use of stibium gives to the eyes of the women of the East.

Combs and hairpins alike were made of wood or ivory. The date of the appearance of combs in the East is unknown, but it is believed they were not introduced until a comparatively late period. Some combs had but a single row of teeth; others had two rows, one thicker and longer than the other.

The use of mirrors seems to be of great antiquity. They were frequently made of bronze, and were usually round, oval, or pear-shaped. The handles were of ivory, wood, bronze, or faience, and of beautiful design, usually suggesting the lotus plant and flower in form and color. They were also given the form of figures—one of the favorite types, judging from the number found, being that of a woman with arms raised supporting the mirror.

Of all toilette requisites, the fan is one of the most ancient, and its popularity has waxed and waned for something like three thousand years. The Egyptian fan is the original of all the later styles. (Figs. 7, e and f.) In that

day the fan was not the "toy of the fashionable lady," as it was in the eighteenth century. The ancient fan was large, with flexible handles five to seven feet in length. The fan proper was usually made of leaves, and of feathers cleverly dyed and arranged in effective pattern. The support was ornamented with jewels or painted in color. A special attendant, usually a slave, carried the fan, holding it to shield the owner from the rays of the sun, or moving it back and forth to cool milady and keep the insects and flies away.

Gradually the articles of toilette as well as the garments of Egypt influenced those with whom she shared her commercial life. That which was distinctly Egyptian was borrowed by other nations, and variously modified to meet local need and environment. The influence of ancient Egypt is recognized again and again in the costumes of modern designers. Her contribution in design and ornament has lived through the centuries, and continues to be the inspiration of ever new arrangements and combinations that still hold the interest of humanity.

## CHAPTER III

### ASIATIC COSTUME (ANCIENT TIMES)

ASIA MINOR plays a significant part in history as it became the channel through which the civilization and culture of Asia were transmitted to Greece and Europe. In matters of dress these less distant Asiatics, under the names of Phrygians, Persians, Medes, Syrians, Parthians, and Amazons, have passed on to the western world many types of costume which, though modified, have been preserved to the present day. Judging from the recovered coins, monuments, and engraved gems of this remote period, there seems to have been much similarity of costume among these near-Asiatic peoples. Though the monuments picture the costume of men far more frequently than that of women, we may be able to glean the general types of women's costume from the few instances left to us upon bronze, marble, and fictile vase.

The characteristic type of dress throughout the region is distinctly that of the Orient, whose one contribution to the world of dress has been that of pantaloons and sleeves. Invariably these figures of Asia Minor wear the vest with long sleeves reaching to the wrist, and the pantaloons descending to the ankle. (*A* and *B*, Plate III.) The pantaloons were frequently close-fitting, and perhaps just as often very ample, falling in great folds and caught in the shoes or sandals. (*A* and *B*, Plate IV.) The vest was always of the same material as the pantaloons, and was closed either in the front or back by means of clasps or studs. Over the vest was worn a sleeveless tunic of another material. (*A*, Plate IV.) This was girded at the waist, and if too long, was girded a second time lower down.





A

B

C

## PLATE III—ASIATIC COSTUME—ANCIENT TIMES

- A—An Amazon. The vest with long sleeves and the pantaloons reaching to the ankles are the characteristic dress of the East. Over this the short tunic is worn. The tunics were frequently richly embroidered or painted in design. Studs or coins sometimes ornamented the belt. The voluminous mantle and the little Phrygian cap are often pictured as part of the Amazon costume.
- B—Amazon dress—pantaloons, sleeves and tunic made from leopard's skin. The Phrygian helmet and the half-boots with flying flaps also suggest the skins of animals.
- C—An Amazon from a vase painting (Hope). This figure is sometimes classified as Greek. The tunic is short, girded at the waist. The designs are probably painted.



To this dress the dignitaries of the East added a voluminous mantle, which was distinct from that of other nations in that it was edged with fringe. (*B*, Plate IV.) This fringe was not a part of the woven material, but was added as an enrichment. Though this mantle was worn by Grecian ladies of later days it was never adorned with fringe. This style of decoration is frequently referred to by Greek writers as being particularly characteristic of barbaric and Asiatic races.

The foot covering of the Asiatic is quite distinct from that of Egypt and Greece. The ancient records always picture these people in laced half-boots or sandals covering the foot. (*A*, *B*, and *E*, Plate IV.) They were made of skins and frequently ornamented with long flaps suggesting the legs of the animal.

The arts of dyeing, weaving, and embroidering were well known to these people of Asia Minor. Tyre and Sidon, the great commercial cities of antiquity, in course of time became celebrated for their splendid dyes of scarlet and purple, for their manufacture of fine linens and perfumes, and for their skill in metallic work.

Phrygia, a rather ill-defined portion of Asia Minor, probably occupying the central plateau of Anatolia and extending as far east as the river Halys, was wonderfully

---

#### COLOR NOTATION—PLATE IV

- A*—Pantaloons and sleeves, R  $\frac{5}{8}$ ; dots, white. Tunic, white. Hoods, R  $\frac{5}{8}$ . Shoes, Y  $\frac{7}{8}$ , Y  $\frac{4}{8}$ .
- B*—Pantaloons, B G  $\frac{5}{8}$ . Tunic, white; banding, Y  $\frac{7}{8}$ . Mantle, R  $\frac{5}{8}$ ; fringe, Y, Y R  $\frac{7}{8}$ . Shoes, Y  $\frac{7}{8}$ . Headband, Y, Y R  $\frac{7}{8}$ .
- C*—Undertunic, white. Overtunic, B G  $\frac{7}{8}$ ; banding, neck, sleeve and belt, R  $\frac{4}{8}$ . Head-dress, white.
- D*—Tunic, white; border, B G  $\frac{5}{8}$ ; painted border, R  $\frac{3}{8}$ . Girdle, B G  $\frac{5}{8}$ ; points, R  $\frac{3}{8}$ . Studs, probably gold. Mantle, R  $\frac{5}{8}$ ; border check, black and white. Head-dress, probably gold.
- E*—Tunic, white; banding and girdle, Y  $\frac{7}{8}$ . Head-dress, white; banding, Y  $\frac{7}{8}$ . Mantle, white.
- F*—Colors not verified. Colors of the time would indicate: Tunic, probably white; border, Y  $\frac{8}{8}$ , P B  $\frac{5}{8}$ . Neckband, P B  $\frac{5}{8}$ ; design, Y  $\frac{7}{8}$ . Girdle, Y  $\frac{7}{8}$ . Head-dress, wreath, G  $\frac{5}{8}$ ; circlet and lappets, Y R  $\frac{8}{8}$ , B G  $\frac{5}{8}$ . Shoes, Y R  $\frac{7}{8}$ , Y R  $\frac{5}{8}$ .



A

B

C

D

E

F

PLATE IV—ASIATIC COSTUME—ANCIENT TIMES

*A*—A Phrygian nobleman. The long sleeves reaching to the wrist and the pantaloons terminating at the ankles were characteristic of the costume of eastern peoples.

*B*—Costume of a Dacian king. The mantle edged with fringe distinguished persons of eminence.

*C*—A Dacian woman wearing the flowing skirt and long overtunic with a suggestion of sleeve.

*D*—A Phrygian lady of rank. The long flowing tunic and mantle of rich material, the head-dress, and casket of jewels suggest the wealth of the East.

*E*—A Phrygian lady of rank.

*F*—Figure attired for religious rites. (From a Greek vase, sometimes classified as Greek.)

rich in gold. The great quantities of this precious metal found in that region no doubt helped to frame the myth of King Midas, who was one of the Phrygian rulers. With this knowledge it is not surprising to read of the "purple and fine linen" of these ancient peoples, to note the beautiful designs which edge the costumes and mantles, and the silver and gold of their ornaments and arms.



Fig. 10. A  
Phrygian (After  
Montfaucon)

Among the Phrygians the dress consisted of two tunics. (Fig. 10.) The under one was longer and terminated at or above the knees, the sleeves were wrist-length. Over this was worn a second tunic reaching to the hip. This was without sleeves and usually worn without a girdle. Sometimes this second tunic was quite full, girded at the hips, and fell to the knee. Often with this the sleeves of the under tunic were also full, turned and fastened very high with a hook.

The ancient records show the women of Phrygia wearing the long straight tunic, close fitting, with sleeves reaching to the wrist or elbow. This was of fine texture, many times embroidered in threads of harmonizing color. Over this characteristic dress was worn the mantle of rich material, with woven borders and all-over patterns. (*D* and *F*, Plate IV.) The short skirted tunic is also pictured as a favorite costume of Phrygian women. (*E*, Plate IV.)

The little cap worn by the Phrygians, and termed the "Phrygian bonnet," traveled as far westward as Venice, and the Doge continued to wear it to the last day of Venetian independence. The characteristic features of the Phrygian cap are its point or top bent forward, and its long flaps descending to the shoulders. Sometimes the cap was of soft pliant material and, unable to support itself, hung in folds. Again, when made in a more durable mate-

rial such as leather or metal, it took on the appearance of a helmet, so well did it keep its erect shape. Often these were richly ornamented. Usually two or four flaps descended to the shoulder, and these were probably the legs of the animals whose skins furnished the body of the casque or cap.



Fig. 11. Head of an Amazon  
(After Hope)

of their helmets terminate in the bill of a griffin, and the back of the casque takes on the jagged crest of that ancient animal of mythology. (Fig. 11.) Minerva sometimes appears in a Phrygian helmet. On many Roman coins Roma is pictured wearing the same type of helmet. Fig. 12, from a cameo, shows Paris wearing the Phrygian cap and the long sleeves and pantaloons of Asia. Many of the officers of the Byzantine emperors wore the same head-dress. Later it was borrowed by the Turks and Greeks, and even in our day the children still cling to their "stocking-cap."

The costume of the Amazon women was quite similar to the usual Asiatic dress. When at home and following peaceful pursuits they are pictured as wearing short skirts of fine material, richly embroidered or painted in spots,

Among the statues and paintings of the Amazons, women celebrated for their courage and daring, variations of the Phrygian cap may be seen. Many




Fig. 12. Costume from a cameo  
(After Hope)



zigzags, checks, or stripes. The skirts were worn over the long pantaloons, which were very loose, hanging in numerous folds and caught in with the tops of the shoes. When engaged in war, they are often represented as wearing the long pantaloons of skins. A little vest closed in front was usually the upper part of the pantaloon costume, and was always of the same material. (Plate III.) Over this a wide sleeveless tunic of another material was sometimes worn. This was clasped at the shoulders, girded at the waist, and, if very long, girded a second time by means of a second belt about the hip, thus making the tunic reach about the middle of the thigh. Many of the ancient vases show a voluminous mantle added to this usual costume of the warring Amazons.

Among the Persians it was never the custom to go without clothing as it was among the Greeks; consequently the arrangement of dress among these people became of much importance. The vest and pantaloons, as with other Asiatic nations, were usually of linen, and the tunic also of linen. Later Cyrus (about 559 B. C.) brought the long robe or sleeved tunic of the Medes, and persuaded the people to adopt it. They found it of great advantage, not only in covering the defects of the body but in adding to the majesty of the figure. (Fig. 13.) These sleeved tunics were worn both long and short, depending upon the rank and power of the wearer. The dignitaries of Persia wore the purple robe lined with white. It was usually long, and shortened by means of horizontal folds arranged like steps.

On many ancient coins the kings of Persia may be seen wearing long beards and enormous wigs of curled hair. Sometimes the hair is arranged in long braids which fall over the shoulder. Bonnets, crowns, and diadems were worn, and it was also a common custom to bind a fine cloth about the head—a custom which has been perpetuated in the turban of the East.

Among the Persians the same garments were worn by both men and women. The latter, however, girded themselves with sashes made with fringes. Necklaces, ear-rings,



bracelets, and rings on the fingers and joints, contributed not a little to the Persian costume.

Display and luxury characterized the Medes. Painted eyes, eyelids, and eyebrows gave an expression of power to the countenance. False hair in enormous quantities was worn by both men and women, and the latter added the further ornamentation, the aigrette. Long tunics descending to the feet were the fashion. These were of many brilliant colors and often embroidered. The successors of Cyrus wore a robe usually purple in color, without sleeves and richly embroidered. Subjects were compelled to wear the long sleeves, for they were not permitted to show the arm.

The Syrians wore narrow, close-fitting, plain clothes, in which dark blue threads alternated with red, frequently adorned with rich embroidery.

The Parthians, who inhabited a part of the Persian kingdom, were noted for their beauty. Their dress in the main followed the tendencies of that of Persia. A few of the rare

coins collected from this country show the heads of the Parthians with their long hair and elaborately curled beards. Often they wear a cylindrical cap rather wider at the top than at the bottom, and called by the Greeks "mitre." (Fig. 13.) Sometimes this cap was enriched by a diadem, and often loaded with different emblematic ornaments. Its shape is to this day preserved in the head-dress of the Armenian priests.

The Dacians, though living on the European side of the Euxine, were of Asiatic origin, and seem to have adopted the same costume with but few changes. Their shoes or soles were fastened with long strings wound several times



Fig. 13. A Persian  
(After Hope)

around the ankle, and their pantaloons were extremely wide. (*B*, Plate IV.) The dress of the Dacian women was equally voluminous and very long. The second tunic, which frequently descended to the foot, is often represented drawn up in numerous folds under the girdle. (*C*, Plate IV.)

Gradually through the extensive commercial relations existing between these countries bordering on the Red Sea and Mediterranean Sea, much of the dress which was purely local in character became more widely diffused. Types of costume which were characteristic of one country and appealed to the people of another were adopted by them, adjusted to the new conditions, and became a part of the national costume.



## CHAPTER IV

### GRECIAN COSTUME

(700 B. C.-53 B. C.)

THE civilization of ancient Greece has left a rich heritage to posterity in her chaste and refined simplicity of dress. The saneness maintained in the matter of costume throughout the development of Greek national life is unequaled. Those excesses and barbaric splendors which so often appear in dress during a nation's most luxurious days were never seen in Greece. On the contrary, throughout her progress from primitive conditions to the highest point of refinement, dress remained exceedingly simple. It is to the costume of Greece of twenty-five hundred years ago that we turn for grace, beauty of line, refinement of detail, and unity of composition.

In approaching the study of Grecian costume one naturally recalls the many lines of Homer which sing of the beauty of Greek women—of the beautiful hair ornaments, veils, and diadems. The familiar sculptures of Greece and the realistic representations of costume seen in Greek vase paintings come to mind. However, it is not in any one of these sources alone that the wealth and variety characteristic of the dress of the classic world is found. It is only in study that combines all three sources—literature, painting, and sculpture—that one may develop an appreciation of the entire field of Greek costume.

It is in Greek literature particularly that we find reference again and again to the charming diversity in materials, ornament, and detail. It is in Greek literature combined with the expression of Greek life in sculpture and painting that we have an authentic and complete background for our study of classic costume.

The two garments always associated with Greek life and worn alike by men and women were the chiton and the himation. Today they are frequently called "tunic" and "mantle." The chiton was a form of tunic which was doubtless of Asiatic origin. Many of the oldest bas-reliefs show the




Fig. 14. The peplos




Fig. 15. Doric chiton, showing "apotygma" and "kolpos"

Assyrians wearing both long and short chitons. The earliest form of Greek chiton was called the peplos. This was in use during the period 1200 B. C.-600 B. C., and the later forms of chiton, notably the Doric and Ionic, superseded it.

The peplos was a rectangular piece of woolen material sufficiently large to wrap about the body. In adjusting it the upper long edge of the material was first folded over (Fig. 14), and the whole adjusted about the body, beginning at the left. Then the front and back of the folded edge were pulled up and fastened on the shoulder with clasps or brooches, points *A* and *AA* meeting over the right shoulder, *B* and *BB* over the left. It was then girded at the waist. The right side of the peplos remained open, and the over-fold covered the chest and the back. Since the material was heavy and closely wrapped the figure, the beautiful folds which distinguished the fifth-century chiton were absent.

The Doric chiton resembled the peplos. It was, however, more ample, of softer and finer material, and fell in numerous folds. It was girded at the waist and the superfluous length, pulled up through the girdle, fell in a baggy effect called the "kolpos." (Fig. 15.) The folded upper portion was known as the "apotygma." Great variety was introduced into the Doric chiton by making the apotygma long or short. When short, the garment was longer and consequently the kolpos was larger. With the longer apotygma, the length of the chiton was necessarily shortened, and the girdle was worn over two thicknesses of material. (D, Plate V.)

Among the women of Greece, the Dorians, particularly those dwelling about Sparta, were the conspicuous athletes. Superfluous length of dress hindered the graceful freedom of the body, consequently the Spartan women often wore the double girdled chiton. This second girdle was adjusted about the hips and the material pulled up through this and the girdle encircling the waist. (Fig. 16.)

The names Doric and Ionic, given to the two types of chiton, correspond to those of the well-known columns of Greek architecture. The Dorians were soldiers and practical men of affairs. These qualities were expressed in both the simplicity and strength of the architectural column, and the practicality of the Doric chiton. The Ionians were the artists, poets, and philosophers of Greece. Their every effort was marked by a fine feeling for grace and beauty. Thus every nation expresses its characteristics in each field of activity which it enters, whether it be dress, architecture or political or commercial life.



Fig. 16. The double girdled chiton (After Hope)



The Ionic chiton in its simplest form was an oblong piece of linen, twice the span of the arms in width. The



Fig. 17. Ionic chiton

length, from shoulder to feet, was always greater than the wearer was tall. In adjusting this chiton the front and back edges were caught over the shoulders and arms and held by means of clasps and brooches. The hand passed through the open spaces at the corners. (Fig. 17.) The front edge, spaced with two or three more inches than the back, gave the easy fall to the front which is characteristic of Greek dress. The girdle was added and the material

#### COLOR NOTATION—PLATE V

- A*—Chiton, white; design, Y  $\frac{5}{8}$ . Head-dress, white.  
*B*—Chiton, Y R  $\frac{5}{8}$ . Head-dress, Y  $\frac{5}{8}$ ; bands, R  $\frac{5}{8}$ .  
*C*—Chiton, white; design, Y  $\frac{5}{8}$ . Girdle, Y  $\frac{5}{8}$ . Himation, Y R  $\frac{6}{7}$ ; design, Y  $\frac{5}{8}$ . Head-dress, B  $\frac{1}{2}$ , Y  $\frac{5}{8}$ .  
*D*—Chiton, white; design, R  $\frac{9}{8}$ . Headband, cord, Y  $\frac{7}{8}$ . Collar, Y  $\frac{7}{8}$ , Y R  $\frac{7}{8}$ .  
*E*—Chiton, white. Himation, R  $\frac{7}{4}$ ; border, Y R  $\frac{7}{4}$ . Headband, R  $\frac{5}{8}$ .  
*F*—Chiton, white; design, B G  $\frac{7}{8}$ .  
*G*—Chiton, white; design, Y  $\frac{5}{8}$ . Head-dress, white; border, Y  $\frac{5}{8}$ .



PLATE V—GRECIAN COSTUME—700. B. C.-53 B. C.

- A*—The Greek tunic with the added upper garment resembling the “bib” of the Ionic chiton and called the diploidion.
- B*—The long straight tunic girded about the waist and hips, with the folds pulled up through the two girdles, making the tunic a convenient length.
- C*—The twice-girded Doric chiton. The little Phrygian cap became a favored head-dress of Greek women.
- D*—The Doric chiton girded over two thicknesses of material.
- E*—A flute player, wearing the chiton and himation.
- F, G*—Examples of Doric chiton showing borders and patterns found in vase paintings.

adjusted, forming the kolpos. The curved kolpos, or line about the hip, was secured by drawing the material deeper at the sides, making the skirt of equal length. There were two other styles of girding the chiton. A band or ribbon to be used as a girdle was first let down over the shoulders to the waistline at the back, the ends of the ribbon passing



Fig. 18. Ionic chiton, showing adjustment of girdle

under the arms were put through this loop, brought to the front of the waist and tied. This gave the effect of straps over the shoulders. (Fig. 18.) The second style shows the ribbon let down over the back, but the ends were first crossed over the chest before passing under the arms. They are then caught through the ribbon at the back, brought to the front and tied. (Fig. 19.) When it was desired to shorten the chiton still more to give freer action in walking, the hip-girdle was added. This was made by carrying the ends of the ribbon down and around the hips.

At a later date the chiton was fashioned of two strips of material, frequently sewn together at the sides to within a few inches of the top. The loose upper edges were then caught over the shoulders. It was without sleeves and resembled a simple tunic. (*B* and *E*, Plate V.)

In many statues of Greek maidens, which have been recovered, a kind of knitted chiton is seen. The knitted

effect has been given by means of minute lines seaming the figure. This suggests worsted work. As Greek women were accomplished in the arts of spinning and weaving, it is not unlikely that the art of knitting was known to them.

In earliest times wool was used for the Greek dress; then flax, then flax and silk, and lastly, pure silk. Silk in both the woven and raw state was introduced into Greece from Asia Minor. That which came in the raw state was woven into a fine transparent silk gauze which was frequently used in later times for the chiton and other parts of the Greek dress.

The outer garment worn by the Greeks was the himation. This was worn by both men and women, and seems to have been indispensable with the Ionic chiton. It was an oblong piece of linen or woolen material measuring about fifteen feet long by six feet wide. This particular garment was never fastened by clasps or brooches, but was wrapped or draped about the figure in ways so intricate that it was impossible for it to slip out of place. There seems to have been an endless variety in the arrangement of the himation, each indicative of the fancy of the wearer. As today one's dress is the expression of his taste,

so in ancient Greece the arrangement of the himation was an index to the character and culture of the wearer. When this garment was long and roomy it was wound twice around the body; first under the arms, and next over the shoulders. (*E*, Plate VI.) Another style which left the right arm free is seen in the painting and sculpture of the period. (*A*, Plate VI.) One end was drawn over the left shoulder from the back, and hung almost to the lower edge of the chiton. Then



Fig. 19. Ionic chiton showing adjustment of girdle



the material was passed across the back, under the right arm, and the remaining end thrown over the left shoulder. In still another style, one end was drawn from the back over the left shoulder, the material passed across the back and under the right arm as before, but instead of throwing the end over the left shoulder it was carried on the forearm. With the Greeks the himation never had, as among the barbarians, the outer edge adorned with separate fringe. In order to preserve the folds and assist in keeping the robe in place, small weights were often sewed into the corners. In rainy or cold weather, the mantle was drawn over the head, serving as a head covering and cloak combined.

A second garment which afforded an additional covering to the upper part of the body, and resembled the folded hanging part, or apotygma, of the chiton was often worn. This seems to have been a square or oblong piece of material of various sizes, resembling our shawls, and called a diploidion. It was folded double, the folded edge being upward and the bordered edge reaching down to or beyond the girdle. This was placed around the figure so that the center of the material came under the left arm. It was then secured by clasps which held the front and back edges together on the shoulders. If the material happened to be square, the ends would probably reach to the waist (*C*, Plate V); if long, they fell to the ankles. (*A*, Plate V.) The shape of the garment was considerably modified by

---

COLOR NOTATION—PLATE VI

*A*—Chiton, white. Himation, B  $G \frac{5}{4}$ ; border, R  $\frac{1}{2}$ ; lining, R  $\frac{1}{2}$ . Head-dress, Y  $\frac{3}{8}$ , R  $\frac{5}{8}$ .

*B*—Chiton, G  $\frac{1}{4}$ . Himation, P  $\frac{1}{4}$ .

*C*—Chiton, black; borders and design, Y  $\frac{5}{8}$ . Himation, P  $\frac{1}{4}$ .

*D*—Tunic, white. Upper garment, white; embroidery, B  $\frac{1}{4}$ , R  $\frac{1}{8}$ . Head-dress, Y  $\frac{3}{8}$ ; front, B  $\frac{1}{4}$ .

*E*—Chiton, white.

*F*—Himation, B G  $\frac{5}{4}$ ; border, R  $\frac{1}{2}$ ; lining, R  $\frac{1}{2}$ . Chiton, white. Head-dress, Y  $\frac{3}{8}$ , R  $\frac{5}{8}$ .

*G*—Chiton, Y R  $\frac{3}{8}$ ; design, Y R  $\frac{1}{4}$ . Headband, Y  $\frac{3}{8}$ , R  $\frac{5}{8}$ .





A                  B                  C                  D                  E                  F                  G

PLATE VI—GRECIAN COSTUME—700 B. C.-53 B. C.

- A—The himation, or shawl-shaped drapery, worn over the chiton. This was the garment that expressed through its style of arrangement the refinement and rank of the wearer.
- B, C—Two mourning figures in robes of purple, dark green and black. The hair was frequently cut as a sign of sorrow.
- D—A short, ungirded upper garment.
- E—A peasant girl.
- F—A Grecian woman wearing the himation draped over the left shoulder.
- G—A Grecian costume with sleeves. The free edges of the folds of the chiton hanging from the shoulder are here held together by clasps or studs, thus forming a sleeve.

fashion, in later times it became a narrow slip hanging from the shoulders and resembled a semi-fitting jacket. (*D*, Plate VI.)

The *chlamys* was a cloak worn by men. It resembled the *himation* in shape but was much smaller, measuring about seven feet by three and a half. When folded in two it formed a square. It was worn covering the left arm and side. The top edges were caught over the right shoulder and fastened with a brooch. The right side was open and the right arm free. This was the garment worn by men when riding. It was also used as a military cloak.

Veils were a charming note in the costume of Grecian women of rank: they were chiefly worn as a sign of modesty. Penelope when urged to say whether she preferred to stay with her father or to follow her husband, is represented as expressing her preference for the latter by drawing her veil over her blushing features.

A veil of richest texture wrought she wears;  
—*Odyssey*, xviii.

And again:

A veil translucent, o'er her brow displayed.  
—*Odyssey*, xviii.

At the adornment of Pandora we read that the goddess, Athene,

held with her hands a curiously embroidered veil, a marvel to  
look upon. —*HESIOD, The Theogony*.

Many references to veils appear all through the *Iliad* and the *Odyssey*. Of Helen we read:

O'er her fair face a snowy veil she threw,  
And softly sighing from the loom withdrew.  
—*Iliad*, iii.

Embroidery distinguishes the veil of Athene:

Pallas disrobes; her radiant veil untied,  
With flowers adorned, with art diversified.  
—*Iliad*, v.

The beauty and arrangement of the hair was given the greatest possible attention by these ladies of classic Greece. Since the general coloring of the southern races is dark, the lighter colorings, which were unusual, were considered more beautiful. The goddesses are often described as golden, red, or auburn haired. Paris has yellow hair; Achilles has ruddy hair; and Adonis wears a ruddy beard. In ancient painting and sculpture, red is often used for the color of the hair and beard.

Quite contrary to the custom among the Egyptians, the hair of both men and women was permitted to grow. The gods themselves rejoiced in the possession of long and abundant hair; Zeus, the king of gods, and men, is always pictured with "ambrosial locks" falling to the shoulders.

The young women often wore the hair falling loose in natural curls, or straight to the shoulders. (*A, C, F, G*, Plate V.) Others twisted or plaited their hair in various ways, sometimes confining it in a net spoken of as the caul. (*G*, Plate VI.) As a final touch the crown, wreath, or ornamental head-dress was frequently added. The head-band was probably a cord carried around the head and tied at the back with ribbons. In the following lines referring to Andromache's despair at the death of Hector, the head-dress is suggested; also the words band, net, and veil are used.

. . . The ornaments

Dropped from her brow,—the wreath, the woven band,  
The net, the veil, which Venus gave . . .

The ladies of fashion also adopted the mitre, the bushel-shaped crown worn by the goddess Ceres, and the tiara, the crescent-shaped diadem of Juno and Venus. Besides these, rows of beads, wreaths of flowers, nettings, fillets, and ornaments innumerable were worn by all the fashionable ladies of the period.

The wearing of hats seems to have been reserved for the women of later days. The men of Greece, however,

protected their heads while traveling by wearing a broad-brimmed hat, petasos, which was tied under the chin with strings. (B, Plate VII.)

Though the Grecian dress when compared with that of contemporary peoples is always simple, there is a distinct difference in costume between the Homeric period and the later centuries. The distinguishing marks of the earlier period were the quality and rarity of the cloth, the expense of the dye, and the richness of the embroidery, which often covered the entire surface of the dress. When a greater refinement of feeling developed, wealth, rank, and social prominence were no longer indicated by lavish display, but it was the cut of the garment, the manner of wearing the chiton and the himation, and the more subtle distinctions at which the Greek leaders aimed. In these later times the early display was stigmatized by Euripides as "barbaric finery."

In early times cloth of gold tissue was not uncommon; it is believed that ornamental discs of pure gold were sometimes glued to the surface of the cloth, thus adding to the glitter of the apparel. The golden embroideries were very elegant; the making of these was the popular occupation of ladies of the highest rank. In the *Iliad*, we read of Helen weaving her story:

Here in her palace at her loom she found;  
The golden web her own sad story crown'd,  
The Trojan wars she weaved (herself the prize)  
And the dire triumph of her fatal eyes.

—*Iliad*, iii.

#### COLOR NOTATION—PLATE VII

- A—Cloak, Y R  $\frac{1}{2}$ ; border, B G  $\frac{1}{4}$ . Hat, Y R  $\frac{1}{2}$ . Sandals, Y R  $\frac{1}{4}$ .  
 B—Cloak, Y R  $\frac{1}{4}$ ; border, Y R  $\frac{1}{2}$ . Chiton, B G  $\frac{1}{2}$ . Hat, Y R  $\frac{1}{4}$ .  
 C—Undertunic, white; border, R  $\frac{1}{2}$ . Armour, helmet, Y  $\frac{1}{2}$ , Y  $\frac{1}{4}$ , Y R  $\frac{1}{4}$ .  
 Crest, R  $\frac{1}{2}$ . Greaves, Y  $\frac{1}{2}$ , G Y  $\frac{1}{4}$ . Sandals, Y R  $\frac{1}{4}$ .  
 D—Undertunic, white; border, B G  $\frac{1}{4}$ ; design, Y R  $\frac{1}{4}$ . Overtunic,  
 Y R  $\frac{1}{4}$ ; spots, B G. Belt, Y R  $\frac{1}{4}$ ; spots, Y (probably metal discs).  
 Helmet, Y  $\frac{1}{2}$ , Y  $\frac{1}{4}$ . Crest, B G  $\frac{1}{4}$ . Shoes, Y R  $\frac{1}{4}$ ; straps, Y R  $\frac{1}{4}$ .  
 E—Peplum, Y R  $\frac{1}{4}$ . Sandals, Y R  $\frac{1}{4}$ .  
 F—Chiton, B G  $\frac{1}{2}$ . Shoes and leggings, Y R  $\frac{1}{2}$ . Hat, Y R  $\frac{1}{2}$ .




*A**B**C**D**E**F*

PLATE VII—GRECIAN COSTUME—700 B. C.-53 B. C.

*A, B*—The traveling cloaks and petasos, or broad brimmed hat, worn by the men of Greece.

*C, D*—Soldiers of Greece.

*E*—A Greek philosopher.

*F*—A peasant.



Of the wife of Alcinous we read:

Her royal hand a wondrous work designs;  
Around a circle of bright damsels shine,  
Part twist the threads, and part the wool dispose,  
Whilst with the purple orb the spindle grows.

—*Odyssey*, vi.

And Penelope says:

The vest much envied on your native coast,  
And regal robe with figured gild embossed  
In happier hours my artful hand employ'd,  
When my loved lord this blissful bower enjoy'd.

—*Odyssey*, xix.




Fig. 20. Greek ornament. a, b, frets; c, guilloche; d, e, anthemion

In many recovered statues of draped figures, painted borders and beautiful designs in color still remain, suggesting the borders woven into the garments by these women of Greece. Among these are the characteristic Greek patterns, the frets, or meanders, which were doubtless of textile origin. (Fig. 20, a and b. See also designs upon garments shown in plates.) The guilloche is another form of meander with the corners rounded, and suggests the Nile pattern. (Fig. 20, c.) The name “meander” is derived from the river Maiandros in Asia Minor, which flows in sinuous curves. All Greek ornament shows a great refinement of feeling for the abstract principles of design, rhythm, balance, subtle proportion, and spacing. The most notable feature of Greek ornament is the anthemion, or “honey-

suckle ornament." (Fig. 20, d and e.) The beautiful large leaves, sharply toothed, of the acanthus tree and the laurel, the leaf of the bay tree, appear many times in jewelry, dress fabrics, and other decorative art. These plant decorations imitated nature in neither color nor form, but furnished the inspiration to creative design.

In early times white and gold seem to have been a favorite combination for feminine dress; this is referred to in the description of Nausica:

The nymph's fair head a veil transparent graced;  
Her swelling loins a radiant zone embraced  
With flowers of gold; an under robe, unbound,  
In snowy waves flowed glittering to the ground.

—*Odyssey*, v.

And again the white dresses belonging to the household of King Alcinous are mentioned:

Then emulous the royal robes they lave,  
And plunge the vestures in the cleansing wave.  
The vestures cleaned o'erspread the shelly sand;  
Their snowy lustre whitens all the strand.

—*Odyssey*, vi.

Penelope clothed herself in white when praying for the return of her husband:

She bathed and robed in white with all her train.

—*Odyssey*, vi.

This choice of white garment, however, does not preclude the use of colors. Among the colors in general use, occasionally one, no doubt, became the fad. At least we may presume as much from the many references to the "saffron colored robe." These saffron colored robes are referred to constantly in the comedies of Aristophanes. In the *Ecclesiazusæ* of Aristophanes an old woman says: "For I am standing idle, painted over with white lead and clad in a saffron colored robe and humming a tune to myself." In another part of the same play a young man describes

an old woman as "clothed in a bloody blister," alluding to the flame or saffron color. The *Agamemnon* of Æschylus says in the chorus referring to Iphigenia: "And pouring to the ground her garments of saffron dye." Purple, usually suggestive of kingly or military rank, is referred to frequently in Greek literature. Though it is usually worn by men, it is occasionally mentioned as worn by women.

Her purple garments veiled the falling tear.

—*Odyssey*, iv.

Purple as well as black and other dark colors were worn as a mark of grief or mourning. In fact, black was never worn by the Grecian women on any other occasion than that of misfortune or sorrow. When so robed, the head was often covered with the himation. (B and C, Plate VI.)

The face wrapped in a veil, declared her woes.

The closely cut hair completed the outward signs of mourning:

Will any means of grace appear or must I cut my locks,  
And clothe me even now in black array of garments?

The ancient form of stay, to which the modern corset may be traced, was a very necessary part of the costume of both Grecian and Roman women. These stays consisted of supporting bands of linen, wool, or soft skin worn round the body in a manner similar to the way in which putties are worn round the legs of the present-day soldiery. There were usually three supporting bands; the zone or loin band, the thoracic band or strophion, intended to support the breasts and conserve the figure, and lastly, the waist band, which filled the space between the other two. It was, no doubt, from the combination of these three bands that the modern corset evolved.

The Grecian women gave a great deal of attention to the beauty of their sandals. These were often one of the

most costly articles of feminine dress. The earliest form of sandal for both sexes was only a wooden or leather sole with thongs attached to tie over the foot. Later a piece of leather covering the toes was added and the thongs or straps were given a variety of beautiful arrangement over the instep and about the ankle. Many times rich embroidery was added as a decorative feature to the strap and the leather which covered the toes. Shoes or half-boots were also worn by the women of Greece; these were laced in front and lined with the fur of the cat tribe. The muzzle or claws often hang from the top of the boot as an ornament similar to those worn by Asiatic women. (E, Plate IV.)

The men of rank and fashion seemed to be quite as fastidious about the beauty of their sandals as were the women. Often those worn displayed the finest workmanship. (A, C, and D, Plate VII.) The philosophers did not appropriate this fashionable foot-gear, but preferred to go about in very simple shoes or sandals. (E, Plate VII.)

It is in the comedies of Aristophanes that we find the vanities of the Grecian women exploited. Referring to the painting of the face with white lead by elderly women who wished to appear youthful, we read the words of a young man to an old woman:

Are you an ape covered with white lead or are you an old woman sent up from the dead?

—ARISTOPHANES, *Ecclesiazusæ*.

Again, a young man holds a torch high and looks into the face of an old woman, saying:

O see, Poseidon and ye elderly gods, how many wrinkles she has in her face. Upon my word you'd be the better for it if one were to wash you clean.

—*Plutus*.

Referring to the use of artificial hair we read:

If thee doesn't make haste to get away from this with prodigious speed, I'll forthwith be separating, even from thy brains, those falsified dandily arranged corkscrew curls of thine, with all their grease as well.

—*Truculentus*.

The following lines are an interesting example of similar character:

You have bought hair, paint, honey, wax, teeth, at the same cost  
you could have bought a face.  
—PALLADAS.

You dye your hair; but you will not dye your old age, nor will  
you stretch out the wrinkles of your cheeks. Do not then plaster  
the whole of your face with paint, so that you have a mask, not  
a face, for it is of no use. Why, are you mad? A paint and  
wash will never make a Hecuba a Helen.  
—LUCIAN.

The desire to be admired evidently led the woman of Greece to adopt all the artifice that could be devised at that period. In this respect she is decidedly human and no doubt would be quite at ease before a modern toilette table.




Fig. 21. Pyxis and fans

Along with all the toilette accessories were the ornaments—the ear-rings, necklaces, bracelets, rings and beautiful pins for the hair. The recent discoveries of Dr. Heinrich Schliemann at Mycenæ prove that the wealth and beauty of jewels and decorative work, to which frequent reference is made in the Homeric poems, is not an exaggeration, but a description of the ornament of the period.

What a quantity of gold she wears, like a virgin!

—ARISTOPHANES, *The Birds*.

Chains, bracelets, pendants, all their toys I wrought,

—*Iliad*, xxii.

Her soft white neck, rich earcanets embraced,

Bright, and with gold in all variety graced,

—HOMER, *Hymn to Aphrodite*.



All of these ornaments were kept in a small box or casket called pyxis (Fig. 21), which was the name of the wood from which the jewel boxes were made. Often on the vases and occasionally on the tomb monuments the Grecian lady is pictured holding this dainty casket from which she is selecting her ornaments.

The fan and sunshade were well known in Athens. Both had been used by Assyrians, Egyptians, and Persians. Grecian women adopted the fan soon after the fifth century B. C. The fans of this early day were made of leaves and feathers attached to a rigid handle. In the later centuries they were made by stretching linen or silk over a frame shaped like a leaf. In Greece, as in Egypt, the large fans with long handles were commonly used by slaves in the service of their masters. The sunshades resembled the Japanese parasol, being somewhat flat. They were made on a framework similar to the umbrella of today, and covered with linen or silk. Out-of-doors, the women were protected from the sun by the long handled sunshade carried by a slave.

The following lines from the *Iliad* picture in a poetic phrasing the fastidious toilette of the early ages of Greece:

Swift to her bright apartments she repairs,  
Sacred to dress and beauty's pleasing cares;  
With skill divine has Vulcan form'd the bower  
Safe from access of each intruding power.  
Touch'd with her secret key, the doors unfold,  
Self closed, behind her shut the valves of gold,  
Here first she bathes; and round her body pours  
Soft oils of fragrance, and ambrosial showers:  
The winds, perfumed, the balmy gale convey  
Through heaven, through earth, and all th' aerial way  
Spirit divine, whose exhalation greets  
The sense of gods with more than mortal sweets.  
Thus while she breath'd of heaven, with decent pride  
Her artful hands the radiant tresses tied;  
Part o'er her head in shining ringlets roll'd  
Part o'er her shoulders rolled like melted gold;  
Around her next a heavenly mantle flow'd,  
That rich with Pallas' labour'd colors glow'd;  
Large clasps of gold the foldings gather'd round,

A golden zone her swelling bosom bound.  
Far beaming pendants tremble in her ears  
Each gem illumined with a triple star.  
Then o'er her head she cast a veil more white  
Than new fallen snow, and dazzling as the light.  
Last, her fair feet celestial sandals grace.  
Forth from the dome the imperial goddess moves,  
And calls the mother of the smiles and loves.

—*Iliad*, xiv.



## CHAPTER V

### ROMAN COSTUME

(53 B. C.-500 A. D.)

**T**HE life of the Roman Empire is commonly reckoned from 53 B. C. to 500 A. D. During this long period Rome exerted a dominant influence on the manners and customs of practically the entire known world. The Romans borrowed much from the Greeks in matters of dress, but the distinguishing feature of the Roman costume was different from that of all other nations. The toga may properly be called the Roman's national dress. (*B* and *C*, Plate VIII.)

In early days it seems to have been worn by both men and women over the long tunic or stola, which was similar to the Greek chiton. The exact form of the ancient Roman toga has long been a subject of controversy. Some contend it was a piece of square or oblong material, and resembled the Greek himation; others that it was circular in form. Be that as it may, the toga of Rome's imperial day was semi-circular in form, and measured from tip to tip about three times the height of the wearer. Though in this form it somewhat resembles the Greek himation it is without the four corners or points. It was sufficiently ample to envelope the whole figure, and could be so arranged as to allow a portion of it to be pulled over the head for protection. The arrangement of the toga was a matter of personal pride to the Roman.

It was usually draped on the figure by starting at the left foot. The straight edge was taken over the shoulder and arm, passed across the back, and under the right arm. It was then carried across the chest, over the left shoulder, and the remaining portion was left hanging down the back. The width of material under the right arm was often turned

over, giving the effect of a second drapery. The material of the straight edge of the first section, which passed over the left shoulder, was given a draped effect by being pulled out and adjusted loosely over the top part. The loose portion at the back of the right shoulder was sometimes fastened at the belt, forming a sleeve.

If the ends were too long, they could be shortened by tying knots in the cloth near the ends. There were times, however, when the ends were allowed to sweep the ground. This was always looked upon as a sign of the great dignity and high rank of the wearer.

Soft wool, silk and fine linen were used for the toga. Undyed wool of a yellowish hue was favored by the higher classes. In lieu of the toga, the lower classes wore a hooded cloak of coarse gray or tan material.

The materials commonly used in Rome were woolen, linen, and silk. Woolen was most generally used in the earlier days. Augustus is said to have worn in winter no less than four tunics beside the under one, and all of them woolen. It is believed that linen was in common use for women's garments long before it was adopted for those of men. Some authorities state that it was not in use for men's garments until a late period of the Roman Empire. Silk seems to have been unknown to the Romans during the Republic. In the time of the Emperor Aurelian, 161 A. D., a robe of pure silk was so expensive that he refused to permit his empress to wear it. Heliogabalus, 213-222, is said to

---

#### COLOR NOTATION—PLATE VIII

- A*—Costume from Trojan column. Colors of period would indicate: Tunic, white. Trousers, R P  $\frac{3}{4}$ . Paludamentum, R P  $\frac{3}{4}$ .  
*B*—Toga, Y  $\frac{3}{4}$ . Tunic, B G  $\frac{3}{4}$ , Y  $\frac{3}{4}$ .  
*C*—Toga, Y  $\frac{3}{4}$ . Shoes, Y R  $\frac{3}{4}$ .  
*D*—Undertunic, white. Overtunic, sleeves, B G  $\frac{7}{8}$ ; banding, Y Y R  $\frac{7}{8}$ . Belt, B G  $\frac{7}{8}$ . Armour, Y Y R  $\frac{7}{8}$ ; design at lower edge, Y  $\frac{7}{8}$ . Crest, B G  $\frac{3}{4}$ . Banding at neck, B G  $\frac{3}{4}$ . Mantle,  $\frac{3}{4}$ . Shoes,  $\frac{7}{8}$ ; underlaces and top, Y R  $\frac{3}{4}$ .  
*E*—Tunic, trousers, Y R  $\frac{3}{4}$ . Armour, B G  $\frac{3}{4}$ . Helmet, B G  $\frac{3}{4}$ . Crest, Y R  $\frac{3}{4}$ . Shoes, Y  $\frac{3}{4}$ ; fur,  $\frac{3}{4}$ .  
*F*—Helmet, Y Y R  $\frac{7}{8}$ , R  $\frac{3}{4}$ .  
*G*—Tunic, B G  $\frac{3}{4}$ . Upper tunic, Y Y R  $\frac{3}{4}$ . Skin, Y R  $\frac{3}{4}$ . Sandals, Y Y R  $\frac{3}{4}$ .



A B C D E F G

PLATE VIII—ROMAN COSTUME—53 B. C.-500 A. D.

A—Roman emperor in military tunic and paludamentum. This mantle, being less trailing and cumbersome than the toga, was frequently worn. It was fastened on the right shoulder by a clasp or button.

B, C—Roman citizens wearing the toga.

D—Military tunic of Roman emperor.

E, F, G—A group showing various types of dress worn by the Roman soldiery.



be the first emperor who wore a robe of pure silk. The Romans considered the silk imported from India too thick and closely woven; consequently it was unraveled and re-woven with linen or wool, and made so thin as to be transparent. Later, however, the silkworm was introduced from the East, and the Roman manufactures soon equaled those of India.

With materials of the finest texture, color began to play an important role in the Roman world. As colors became more numerous, they were used as badges for distinguishing classes. Purple and gold were reserved for those of noble birth; a purple striped toga was worn by men of rank; a purple silk toga embroidered in gold was the badge of a victorious general. Among the professions, blue was the color for philosophy; black, for theology; and green, for medicine. The costume of the soothsayer was white, with no ornament; that of the lower classes of a somber hue. The peasantry were permitted one color only; officers, garments of two colors; commanders of clans, garments of three colors; and on up to the royal household, where seven colors were permissible.

Though the toga was worn by both men and women in the earlier times, it was first laid aside by women, who adopted the palla, which corresponded to the himation of the Greeks. (*B, C, D, E, F*, Plate IX.) This garment was oblong in shape; the four points or corners quite distinguished it from the toga. The palla was distinctly a woman's garment, never adopted by the men of Rome. It was worn over the long tunic or stola which resembled the Greek chiton, and fell in numerous folds about the feet.

---

#### COLOR NOTATION—PLATE IX

*B*—Stola or tunic, white; banding, R  $\frac{6}{8}$ . Palliolum, Y  $\frac{8}{8}$ , Y R  $\frac{6}{8}$ .

*C*—Stola, white. Palla, R  $\frac{6}{8}$ ; design, Y  $\frac{8}{8}$ . Head-dress, Y  $\frac{8}{8}$ . Veil, white.

*D*—Undertunic with sleeves, white. Stola, R  $\frac{8}{8}$ . Palla, B G  $\frac{7}{8}$ . Head-dress, Y  $\frac{8}{8}$ , Y R  $\frac{7}{8}$ . Sandals, Y  $\frac{7}{8}$ .

*E*—Stola, Y R  $\frac{8}{8}$ . Palliolum, Y  $\frac{8}{8}$ . Sandals, Y  $\frac{7}{8}$ .

*F*—Stola, white. Palla, B G  $\frac{5}{8}$ ; border, B  $\frac{6}{8}$ , B  $\frac{3}{8}$ . Head-dress and bracelets, Y  $\frac{8}{8}$ , Y R  $\frac{7}{8}$ . Sandals, Y  $\frac{7}{8}$ .



A B C D E F

PLATE IX—ROMAN COSTUME—53 B. C.-500 A. D.

- A—The Roman military tunic, from a statue of Minerva.
- B—A figure wearing the simple tunic with long sleeves and the palliolum with the flowing ends wrapped about the figure.
- C—A Roman lady enveloped in the palla, the mantle worn by all Roman women. The style of hairdress is seen in many of the portrait busts of the Vatican Gallery.
- D—A seated figure in tunic and palla. The sleeves are linked. The hairdress, the ear-rings and sandals are typically Roman.
- E—The palliolum, or veil, is draped about the head and shoulders. In warm weather a transparent mantle replaced the veil.
- F—A lady of rank wearing the ample palla wrapped about the figure in intricate fashion. The head-dress is distinctly Roman.

Originally it had sleeves reaching to the elbow, and later extending to the wrist; often the lower edge of the palla was trimmed with a border or fringe. (*E, F*, Plate IX.) Though the stola over which the palla was worn resembled the chiton of the Greeks, Greek simplicity was not in evidence in the Roman dress. The luxurious taste of the Roman women required several tunics worn one over the other, and each of a different color. The tunics usually varied in length; the topmost was looped up at the waist, displaying the several colors beneath; the sleeves, also, were made of varying length, thus giving the same color effects over the arm. With materials of finest texture and an almost unlimited range of colors, the Roman matron was free to indulge her every whim for display and luxury in dress.

The veil of exquisite quality, called palliolum by the Romans, was a favorite head-dress. It was arranged over the hair, held in place by bands or wreaths, and fell to the shoulders. There are numerous references in Roman literature to the theristrion which was a transparent mantle sometimes taking the place of the veil.

The belt or girdle was an indispensable article of dress. It was made of various materials, suited to the rank or wealth of the wearer. Often the girdle was hidden by the upper part of the stola falling over it.

Most of the early Romans were peasants. The farmer, clad simply in his tunic, a loose woolen garment which reached the knee, and resembled the chiton, followed his bronze-shod plow drawn by a yoke of cattle. His narrow mind held only sober, practical ideas; for he saw nothing of the world beyond the mountains bordering the plain of the Tiber—mountains which inspired him with no love of the beautiful and the grand, but rather with a feeling of hatred for the enemies who were wont to sweep down from them upon his little field.<sup>1</sup>

He cherished no dreams of military glory or world conquest; only when an enemy attacked did he seize his weapons and join his neighbors to defend his home and

---

<sup>1</sup>George Willis Botsford, *History of the Ancient World* (New York: The Macmillan Company, 1911), p. 328.

fields. Cincinnatus, called from the plow to the dictatorship of the republic, is a typical Roman character. It was in the early days of hardy, rugged life that the ideals—social, economic, governmental—which dominated Rome through her long history, were formed. In her later centuries, every reform in morals or politics was a harking back to these ancient standards. As the great families became powerful and wealthy, they acquired vast estates, cultivated by armies of slaves; but the ancestral virtues of simplicity, industry, and homely integrity were studiously maintained. The increasing wealth and luxury incident to world dominion severely tested and finally destroyed the old system based on the homely ideals of the farmer-soldiers of ancient Latium; but the best representatives of the old Roman families, true to family tradition, fought to the end the vices and corruptions of the East.

One of the noblest and most interesting representatives of the traditional Roman ideals is the wife of the Emperor Augustus, Livia, descended from two of the most illustrious Roman families. As Ferrero says:

In Livia was concentrated the quintessence of the Roman aristocracy. In the palace of Augustus she preserved the beautiful traditions of simplicity and industry. Augustus never wore any other togas than those woven by Livia; woven not indeed and altogether by Livia's hands—though she did not disdain, now and then, to work the loom—but by her slaves and freedwomen. Faithful to the traditions of the aristocracy, Livia counted it among her duties personally to direct the weaving rooms which were in the house. As she carefully parceled out the wool to the slaves, watching over them lest they waste or steal it, and frequently taking her place among them while they were at work, she felt that she too contributed to the prosperity and glory of the empire.<sup>2</sup>

Skill in the arts of spinning, weaving, and embroidery was especially desired by the young Roman matron. It was with great pride that she wrought out a length of embroidery or a bit of design upon tunic, veil, or palla.

Many of the designs seen in Roman costume are easily recognized as Greek in feeling. Rome derived her art

---

<sup>2</sup>*The Women of the Cæsars* (New York: The Century Co., 1912), pp. 52, 58, 61.



directly from Greece, and shows individuality only in an elaboration of the original. The honeysuckle, acanthus, and laurel of Greek days are constantly used in the Roman scroll patterns. Beautiful rosette designs, inspired by the rose, are combined with the scroll patterns seen in the borders of costumes, Roman jewelry, and other decorated




Fig. 22. Roman ornament

forms. (Fig. 22.) This artistic influence touched Roman life after Greece had come under Roman rule. It was at this time that Greek artists were employed in the Roman households as teachers and designers. Wishing to please their luxury-loving masters, they elaborated the simple forms of Greek design until they took on the extravagant qualities always associated with Roman taste.

The Romans, like the Greeks, gave much attention to the hair. The ladies of the Empire frizzled and curled their hair in most elaborate fashion, adorning it with garlands of flowers, fillets, and ribbons of various colors, besides ornaments of gold, pearl, and precious stones. (Plate IX.)

In perfect view their hair with fillets tied.

—*Æneid*.

Arranging the hair was a matter of grave importance; it was usually frizzled and adjusted by the slaves of the household.

His frizzled hair to coil,  
Hot with the vexing iron and smeared  
With fragrant oil.

—*Æneid*.

Sometimes women learned in the art of the coiffure attended to the proper arrangement of the locks, while the



fair lady watched the growing edifice of curls in a mirror made of polished steel or brass, tin or silver. Ancient writers say that the lofty pile of false hair worn upon the head resembled a building. Even so, it was one of only moderate height as compared with the head-gear of later days. The back hair was often enclosed in a caul, or net, after the Greek fashion.

Her head with ringlets of her hair is crowned,  
And in a golden caul the curls are bound.

Indeed, so important was her coiffure to the Roman matron that her care extended even to the sculptured portrait. These, it is said, were ordered with adjustable wigs, in order that with the varying style in coiffure the head-dresses might be changed and thus the portrait always kept in fashion.

The men of Rome usually wore the hair long, and gave it great care. The philosophers permitted the hair and beard to grow, to give them an air of gravity. Lack of hair among the Romans was considered a deformity. It is said that Julius Cæsar wore a laurel wreath to conceal his baldness. Later, those who were bald wore a kind of peruke made of false hair, called *capillamentum*.

It was customary for both the Greeks and the Romans to go about bareheaded, but there were two kinds of head coverings which were quite common; the *petasus*, similar to the Greek hat of the same name, and the *pileus*, a closely woven cap worn generally at public games and festivals.

Of sandals and shoes the Romans had a great variety, adopted from Greece and from the far east. The Roman shoes had various names, and were distinct badges of the position held in society by the wearer. The *baxea*, *solea*, *crepida*, *soccus*, and *corthurnus* were the names of the leading types. The *baxea* were vegetable sandals, similar in construction, no doubt, to the palm leaf sandals of the Egyptians. They were worn largely by the peasant classes, and by the philosophers and priests as indicative of humility. The *solea* and *crepida* were worn indoors, being a

species of sandal fastened about the foot or ankle by a fillet or thongs. The *soccus* was an intermediate covering for the foot; it resembled the modern slipper and could be cast off at pleasure, as it did not fit closely and was not secured by thong or tie. (Fig. 23, b, d.)




Fig. 23. Roman footwear. a, sandal; b, d, *soccus*; c, *corthurnus* (buskin)

The *corthurnus* (buskin) was anciently worn by the Phrygians, and was later introduced to the stage by Sophocles in his tragedies. (Fig. 23, c.) Hence the term applied to the theatrical performers, "brethren of the sock and buskin." This particular kind of covering was a very high boot, reaching above the calf of the leg and sometimes to the knee. It was laced very closely down the front. Sometimes they were dyed purple and other gay colors; very frequently the head and paws of wild animals ornamented the top of the boot. If height of figure were desired, the ordinary thickness of the sole was increased by the insertion of pieces of cork. The shoes of the wealthy were made of fine leather, and were handsomely decorated. (Fig. 23, a, e.) They were often painted with various colors, and ornamented with gold, silver, and precious stones. It was the Emperor Aurelian who forbade men to wear red, yellow, white, or green shoes. These colors were reserved for women only. The Emperor Heliogabalus had his shoes set with diamonds and other stones, but prohibited the use of such ornaments to the women of the empire. Sometimes the shoes had turned up toes, a fashion un-


doubtedly of eastern origin, and which was carried to such extravagant lengths during the Middle Ages. The Roman senators wore black shoes or buskins reaching to the calf of the leg, usually ornamented on the top of the foot with a gold or silver crescent.

Cosmetics, washes, paint, and perfumes were lavishly used by the Roman women. White lead to soften the skin and vermilion to tint it were constantly employed by both sexes. The wife of Nero is said to have invented a pomatum which preserved her beauty. Not content with paint and powder, the women also stained their eyebrows and eyelids with black powder or soot, and added to this the popular vanity of later days, the patch.

The extravagance of the Roman ladies in their taste for luxuries and costly ornament is commented upon by contemporary writers with a severity equal to that of the Quaker. Pliny says: "They seek for pearls at the bottom of the Red Sea, and search the bowels of the earth for emeralds to decorate their ears." Seneca tells us "a single pair was worth the revenue of a large estate," and that some women would wear in their the ears the price of two or three patrimonies.

Some of the young men of the time adopted ear-rings, bracelets, and finger rings.

In classical and oriental costume the easy flowing line is the distinctive characteristic in the attire of both men and women. Aside from the influence of climate, the leisurely life of the classical world undoubtedly prolonged the fashion of the flowing dress. The citizens were practically nobles, and were not urged by the necessities of life to great activity. The menial work was done by slaves. After Charlemagne (800) the distinctly Roman costume disappeared, although this type of dress still continued to be seen in countries under Roman influence.



## CHAPTER VI

### THE COSTUME OF THE MIDDLE AGES—FRANCE (476 A. D.-1500 A. D.)

THE period connecting ancient and modern history is vaguely designated as the Middle Ages. It is commonly supposed to begin with the fall of the western Roman Empire, 476 A. D., and to extend to the revival of letters in Europe, about the year 1500. These intervening centuries, often called the Dark Ages, represent a combination of pagan civilization, Germanic barbarism, and Christianity. It was during this period, when Frank, Gaul, and Roman mingled, that costume as we know it today evolved.

When the barbaric hordes of the North began to invade the South, and the Romans began to carry their conquests northward, a revolution in dress, as well as in the political and social condition of the people, followed.

The Northern peoples had learned to protect themselves against the severity of their climate by adopting a close-fitting garment which preserved the heat of the body, and by wrapping their legs in skins. The Romans ridiculed the men of the North as "trouserred barbarians," but as the Romans pushed their conquests farther north we find a blending of the Roman and the barbaric custom.

After the conquest of Gaul by Julius Cæsar, Roman civilization was introduced into France. The natural consequence of gradual annexation to the Roman Empire of the various nations subjugated by Roman arms was an assimilation of Roman costume. It is especially interesting, however, to study its development in France, as this country was destined to become the fashion leader for the western world.

There were many conflicting influences in the dress of the people inhabiting this corner of Europe at this early



period. The Roman occupation was followed by the invasion of the Franks (428 A. D.-752 A.D.), which caused another change in the style of dress. Under Charlemagne (752-987), still other changes took place, though not so marked. Later, with the accession of the Capet family (987-1328), until the time of the Renaissance a greater variety in dress developed, especially in the details of the costume.

It is quite natural that the Gallic women, becoming Gallo-Roman, desired to follow the fashion set by the ladies of the more influential Roman families. They adopted the palla and the stola, and gathered it in at the waist by a girdle. Thus the girdle became a part of the costume, and by its adjustment a long or short waist could be attained, according to the requirements of fashion. The garments fell in numerous folds about the feet, allowing only the tips of the shoes to be seen. (*B*, Plate X.) Often several tunics were worn one over the other, and frequently the sleeves of the under tunic, which were of a different color, extended to the wrist, while those of the upper one came only to the elbow. Beneath the tunic a close-fitting boneless waist was worn, which was no doubt the progenitrix of that more modern instrument of torture—the corset. The mantle which took the place of the Roman palla was draped about the figure. Gold tissue was a favorite material for this mantle; when occasion demanded, however, heavier stuffs were doubtless used. The mantle frequently took the form of a full cloak, opened in front and secured by a large clasp or brooch. Sometimes it was thrown across the left shoulder, leaving the right arm free. Squares of white linen or colored stuffs were draped over the head, falling to the shoulder. These were bound about the head by circlets of various design, ornamented with jewels. (*C*, Plate X; *C*, Plate XI.) The Phrygian and other little caps frequently covered the head, and, being small, permitted the beautiful hair to be seen. (*F*, Plate X.) Auburn and yellow were particularly admired by these women of Gaul, and if they were unfortunate enough to



have dark locks, these were frequently dyed or concealed under artificial hair of a more fashionable hue.

In the museum collections of France one may see the exact type of house-shoe worn by these women of long ago. They were very long and pointed and without heels. The soles were of cork and the toes turned up. On going out-of-doors the women exchanged these light slippers for sandals, or the walking-boot, *corthurnus*.

The wardrobe of the Gallo-Roman woman was rich and varied. There were tunics of linen, cotton, and silk; violet colored mantles; veils, scarves, ribbons, various kinds of shoes, sandals, gold and silver ornaments, perfumes and scents. Parasols, mirrors of steel, and fans were well known to these women of Gaul. The sudarium, or handkerchief, plain or embroidered, was usually carried in the hand.

The ancient Egyptian custom of carrying crystal and amber balls for cooling the hands, a custom adopted by the Romans, was evidently passed on to the women of Gaul. It was a fashionable caprice to carry little gold and silver nets containing the balls to the theater or festival, and when the hands became heated the warmth was allayed by pressing and twisting first the crystal ball and then the amber, which on being warmed gave forth a most delightful odor.

The extravagant love of the Gallo-Roman woman for jewels and ornamentation rivaled even that of the Roman

---

#### COLOR NOTATION—PLATE X

- A*—Tunic, R  $\frac{5}{7}$ ; border, Y  $\frac{7}{7}$ . Mantle, P B  $\frac{3}{8}$ ; border, gold. Shoes, G  $\frac{5}{6}$ .  
*B*—Tunic, Y  $\frac{5}{6}$ . Mantle, R  $\frac{4}{6}$ . Sleeves, P B  $\frac{7}{8}$ . Shoes, P B  $\frac{4}{6}$ . Belt, P B  $\frac{4}{6}$ , gold studs. Buckle, gold with center, R  $\frac{4}{6}$ . Cap, white.  
*C*—Tunic, R P  $\frac{7}{8}$ . Mantle, P B  $\frac{4}{8}$ ; lining, B  $\frac{7}{8}$ . Veil, white. Circlet, gold. Shoes, G  $\frac{5}{6}$ .  
*D*—Tunic, B G  $\frac{6}{8}$ ; border, Y  $\frac{5}{6}$ . Leggings, Y  $\frac{5}{6}$ . Shoes, B G  $\frac{4}{6}$ . Hat, B G  $\frac{5}{10}$ . Mantle, R  $\frac{5}{10}$ .  
*E*—Undertunic, Y  $\frac{7}{6}$ . Overtunic, Y G  $\frac{7}{6}$ ; bands, R  $\frac{6}{6}$ ; spots, Y G  $\frac{7}{6}$ . Leggings, B G  $\frac{6}{6}$ . Shoes, B G  $\frac{4}{6}$ . Hat, R  $\frac{6}{6}$ , metal.  
*F*—Tunic, white. Overtunic, R P  $\frac{7}{8}$ . Border, Y  $\frac{7}{8}$ , G  $\frac{4}{8}$ . Mantle, P  $\frac{3}{8}$ ; lining, P  $\frac{3}{8}$ , white. Sleeves, B G  $\frac{8}{8}$ . Cap, white.



A                      B                      C                      D                      E                      F

PLATE X—COSTUME OF THE MIDDLE AGES—600-1100

- A*—752—A Merovingian woman wearing the long, simple garment with the fitted neckline.
- B*—600—A Gallo-Roman woman. The women of Gaul adopted the dress of the influential Roman women—the stola, girded at the waist, and the palla.
- C*—1000—A type of costume worn by Carlovingian women. The girdle of this day was a luxury, studded with jewels and gold.
- D*—1000—The costume of a man of rank showing the lingering influence of Roman dress.
- E*—1100—A nobleman wearing the embroidered tunic over an undertunic with long sleeves.
- F*—1100—Capetian woman wearing the long flowing tunic over an under-tunic of contrasting color.

matrons. Necklaces, rings, bracelets, and ear-rings of emerald, amethyst, sapphire, and engraved stones, all of great value, were profusely used. An ornamented anklet or garter was also worn about the leg to confine a sort of trouser of fine linen. Cosmetics and drugs of all sorts were lavishly used, and the eyelids were stained to give brilliancy to the eyes.

There were also dentists in these remote days who manufactured marvelous false teeth, and thus combatted the ravages of time.

After the invasion of the Franks under the young Prince Merowig, other changes in costume took place. This period of Frankish rule is known as the Merovingian period (428 A. D.-752 A. D.)

The Frankish women were large and coarsely built, and their taste in dress was of a corresponding character. During the earlier period of the Merovingian monarchy both men and women wore garments of felt, and of a coarse cloth made of camel's hair and called camlet. Later this was woven with a silk warp. Narrow silk mantles of red and scarlet were also favored in these early centuries. As the Franks became firmly established their rusticity began to blend with Latin refinement and produce a new type. The Merovingian women, no doubt, appropriated many of the features they admired in the Gallo-Roman dress. They, too, wore the long flowing garment and the mantle. Queen Clotilde is frequently represented as wearing a tunic confined about the waist by a band of some precious material, and a mantle laced across the breast, over which fell her

---

#### COLOR NOTATION—PLATE XI

- A*—Surcoat, Y  $\frac{3}{4}$ ; design, Y  $\frac{1}{2}$ ; lining, white. Girdle, R  $\frac{5}{10}$ . Spur straps, R  $\frac{5}{10}$ . Armour, chain.
- B*—Tunic, P B  $\frac{1}{2}$ . Mantle, R  $\frac{5}{10}$ , R  $\frac{3}{4}$ ; lining, white. Cap, R  $\frac{5}{10}$ , gold. Chin-cloth, white. Shoes, black. *Amônière*, Y R  $\frac{1}{4}$ .
- C*—Tunic, R  $\frac{1}{10}$ . Overtunic, R P  $\frac{1}{4}$ . Banding, Y  $\frac{7}{8}$ , G  $\frac{1}{4}$ . Mantle, P B  $\frac{1}{2}$ ; lining, B  $\frac{3}{8}$ , white. Veil, white. Circlet, gold. Shoes, G  $\frac{5}{10}$ .
- D*—Armour, chain. Belt, Y  $\frac{7}{8}$ . Cuff, R  $\frac{5}{10}$ .
- E*—Trunk-hose, B G  $\frac{1}{2}$ . Doublet, R  $\frac{1}{4}$ ; banding and collar, white. Hat with hood, R  $\frac{1}{4}$ ; chin-cloth, white. Feather, B  $\frac{1}{4}$ . Spur straps, R  $\frac{1}{4}$ .



A                      B                      C                      D                      E

PLATE XI—COSTUME OF THE MIDDLE AGES—1100-1350

- A—A knight wearing the chain armor with surcoat emblazoned with heraldic device.
- B—A costume showing the influence of the Crusades upon dress. The simple, straight tunic and the mantle hanging straight from the shoulder together with the little chin-banded cap produced a marked severity in the trend of costume at this time.
- C—A Capetian lady wearing the two-tunic dress with the mantle fastened with a jeweled clasp.
- D—A knight of the First Crusade wearing the chain coat of mail.
- E—A gentleman of rank wearing the long, tight hose and doublet which succeeded the loose robes of earlier times.



long plaits of hair. The Merovingians favored many-colored tunics, and bright and showy colors. Gregory of Tours, bishop and historian, who from his position was well acquainted with the customs of the Merovingian court, speaks of the "silken robes," which he describes as "splendid." There were tunics, gowns with long trains, mantles, hoods, and veils.

The Merovingians were forbidden to cut their hair, and consequently it often grew to great length. They usually arranged it in two thick plaits, intertwined with ribbon and flowers; falling over the shoulders it often reached to the knees. (*A*, Plate X.)

As usual, every woman of wealth loaded herself with jewels, necklaces, bracelets, and rings. Costumes worn on festive occasions sparkled with gold and jewels. This love for ornament, for girdles of gold, and gilded embroideries with which they later enriched the borders of tunics and cloaks, savors of the East; it attests the influence of the Imperial Court, which had been removed in the third century from Rome to Byzantium, later called Constantinople in honor of the Emperor Constantine. It was here at the court of Constantine that a new influence was developed, which was to play a mighty part in the shaping of costumes during the succeeding centuries. Here the Emperor gradually gathered artisans from the centers of Europe, and under the zeal of the new religious awakening they produced designs which expressed in many ways the early Christian ideas. The new emblems of Christianity were combined with the traditional form of the Greek and Roman period, producing a type of design and ornament characteristic of the age, and known as Byzantine. The geometric form of this design was combined with the pictorial. For instance, an entire surface of cloth was laid out in connected squares or circles, and within these were pictured scenes and figures from the Gospels. Those of beasts, inclosed in geometric form were also frequent. Many times all manner of conventional floral patterns were used in this geometric background. Rare tapestries were



made with inwoven design. Sometimes the warp and woof were both of linen, again of linen and wool, and still again of silk. These were used as hangings in the churches. The designs used in dresses and mantles were similar. The entire surface of fabrics was covered with conventional




Fig. 24. Byzantine ornament

floral patterns. These were inwoven, printed, and embroidered. Both the men and women of the Franks adopted these rich materials from the Eastern Roman Empire into their costume.

The Christian symbols used in Byzantine design were full of peculiar significance. The cross, the vine, the lamb, the dove, the square, and the circle was each a reminder to the early Christian of his new faith. The circle was the emblem of eternity; the square, of the city that "lieth four-square." The lamb was a symbol of the Christ; the dove suggested the Holy Spirit; and the cross, though used in the classic period, changed under the Byzantine influence, and was the distinct symbol of Christianity. As in the familiar Latin cross, the lower limb is the longest, but the top and arms expand rather than continue straight. (Fig. 24.)

Not only did the design assume and express the mind of the period, but soon the colors in use took on a religious significance. White was the symbol of purity; blue, of heavenly trust and sanctification; red, the love of God; purple, of dignity; green, of eternal youth; gold, of virtue; bright yellow, of fertility; violet, of humility. The Byzantine contribution to costume, combining pagan and Christian

elements, produced a magnificence in dress rivaling that of any later period.

Under the reign of Charlemagne there was no marked difference in the fashionable costume. The rich stuffs from the East still continued to furnish materials for costume,



Fig. 25. Head coverings

even after the art of embroidery, tapestry weaving, and appliqué work was carried on in Europe. It is recorded that the daughters of Charlemagne did silk weaving in 800 A. D., but the trade in fine fabrics was practically monopolized by the East. The long tunic still continued the vogue. The most elegant ladies of the period inclined toward two close-fitting tunics of different colors. (*F*, Plate X; *C*, Plate XI.) The neck, sleeve, the lower edge of the tunics, and the mantles were often trimmed with wide bands of embroidery. Transparent and somewhat clinging materials, which revealed the lines of the figure, were frequently used for the tunics. Later, however, the delicate tissues were replaced by heavier materials, and the dresses became much more ample. The girdle was placed just above the hips, and was often of great value, being ornamented with jewels and gold studs. Splendidly embroidered veils were worn upon the head, and frequently secured by a diadem or band. The ladies of noble birth continued to wear their hair long, plaited, and intertwined with ribbons and purple bands, and reaching below the waist. About the eighth century the fashion of concealing the hair, which was in marked contrast to the earlier styles, began to have a following among

the leaders of fashion. Squares of white linen and colored stuffs over white linen, which were formerly used to drape the head and shoulders, were now used for framing in the face and hiding the hair. Various kinds of hoods were also worn, known as *chaperon* or *amusse*. (Fig. 25.) The drapery covering the hair and neck is frequently referred to as the *couvrechef* (head covering.) The walking-stick was a fashionable caprice among the Carlovingian women. (C, Plate X.) These were usually cut from apple wood, and ornamented with a bird, flower or other device at the top. Gold was lavishly used both in jewels and in ornamentation; jewels were much appreciated, and were worn fastened to the costume of which they seemed to be a part. "Among the admirable miniatures in the Mazarine Library, one shows a queen wearing an under tunic of black, and the upper one in the style of a mantle is purple. Both are edged with bands of yellow, which probably is gold. The shoes also are yellow, with gold ornamentation."<sup>1</sup>

We know much more about the costumes of ladies of rank than about those of the great mass of people. History is almost silent on this point, telling us only that they wore their skirts extremely long, and that their veils were quite thick and almost enveloped the figure.

Like the Greek and Roman women, those of the early Middle Ages were skilled in the art of embroidering. In this way each was able to supply herself with beautiful bits of trimming and ornamentation. Bags, scarves, sleeves, and belts were among the articles of dress favored with the personal touch. It is said that Empress Judith, mother of Charles the Bold, who was unusually skilled in the art of embroidering, presented to the Queen of Denmark a gown richly ornamented with gems and gold, which was the work of her own hands.

The usual mourning costume of the early Middle Ages was quite different from that of the classic world, and resembled somewhat the nun's dress of today. A mantle

---

<sup>1</sup>Augustin Challamel, *History of Fashion in France* (translation, New York, 1882), p. 26.

was worn over a wide-sleeved tunic; under the tunic was a second gown with long close-fitting sleeves buttoning at the wrist. A guimpe of fine material covered the upper part of the bust, encircled the throat, and then joined the veil, which was banded across the forehead and arranged in two large folds over the ears. It was also customary to have the instep of the hose cut open as a sign of mourning.

With the accession of the Capet family (987-1328), the nationality of France became gradually more pronounced. The Gallo-Roman, Frankish, and German women merged into the French women of feudal times. Though the mediæval period is commonly called the "Dark Ages," it is one of the most interesting periods in the world's history. During this stretch of time the foundations were laid for the great forward movements in religion and social life, and for the advancement of the arts, of music, and of literature.

It was an age of adventure and romance—of noble ladies and knights in armour. The life of the young woman of this day was one of freedom when compared with the restricted existence of earlier times. She roamed at will about the castle of her father, sat in the great banqueting hall, took part in the merry conversation and listened to the tales of adventure related by the knights. Her serious moments were spent in religious study under the guidance of the nuns. Together with other young girls of her class she was taught to embroider, and later spent much of her time embroidering the family coat of arms, or in weaving fine silken trophies for a gift to her favorite knight. To be skilled in horsemanship was an ambitious accomplishment of the period. Having attained this, her pet diversion was to join a company of noble knights and ladies as they went hawking.

The crusaders exerted a marked influence on dress for a brief time, and a tendency toward severity set in. In the eleventh century men and women both adopted the *bliand*—a long straight garment with large loose sleeves,



resembling the present-day kimono sleeve. The knights frequently wore this over their armor, and since women's costume was influenced by that of the crusaders, it is not surprising that they adopted the same garment. The modern blouse has preserved the name of this early *bliand*. It is this garment, no doubt, which in the thirteenth century changed into the surcoat. One of the quaint customs introduced by the crusaders was the fashion of wearing purses attached to the girdle. They were called *amônières sarasinoises*, or Saracen almsbags, but usually carried other things besides coin for the poor. The little purse, or *amônière*, remained in fashion all through the Middle Ages, and reappeared throughout the century as one of the indispensable adjuncts of costume. (B, Plate XI; A, Plate XIV.) In this early period they were remarkable either for the material or for the needlework bestowed upon them.

The simple and severe costume effects which came in during the period of the Crusades proved to be only temporary. (B, Plate XI.) Soon the Crusaders were returning from the East, bringing with them the habits they had acquired there; before long the mass of the people were vying with one another in imitating the rich and powerful nobles and their consorts. Further, the extensive commercial relations existing between France and the East did much to refine French taste in matters of dress, and from the eleventh century on, the expression became more artistic. Greater attention was given to dress by both men and women. The Roman influence was still seen in the costumes of men as late as the eleventh century, but the knight in armor is the outstanding personage of the Middle Ages. And what a statuesque figure he is! He wore no loose folds of costume as in the classic days but instead, the metal armor, highly polished, which defined the figure and gave an impression of great strength. Under the armor a padded garment was worn to protect the body. In warm weather when the armour became unbearably hot, the silken robe (*bliand* or surcoat), with heraldic designs, was worn over it. A similar cover was used over the shield

when not in use. This decoration was the beginning of heraldry, which played so important a part in the art of the Middle Ages, and greatly influenced architectural ornament, furniture, and interior decorations.

Heraldry is a science. It treats of blazoning or describing armorial bearings in which every line or part has a specific meaning. The use of these designs no doubt originated with those who took part in the tournaments, and they were worn as marks of distinction. In no other way could the Lady of the Tournament recognize her knight, for his features were concealed by the helmet.

The armored knight occupies the stage of the Middle Ages, but the long easy tunic of the earlier period lingered, gradually becoming shortened to the knees. This was girded at the belt, and the long sleeve closed at the wrist. Over this was worn the very ample cape or mantle. (*D*, Plate X.)

It was following the Crusades that the demands of fashion were so exacting that great numbers of artisans and working women found profitable employment in producing all kinds of luxurious wearing apparel. There were innumerable makers of head-dresses, trimmers, dress cutters and makers, ribbon makers, dyers, makers of buckles and delicate clasps, furriers who possessed the most delicate and costly furs, makers of brass, copper, and wire buttons, hosiers, shoemakers, glove makers, and hosts of others.

This age is memorable for a new division of the people, and the appearance of the "middle class." Heretofore there had been but two classes, the rich and the poor, the lord and the serf. The coming of the craftsmen created an entirely new order of society. This class did the work which required both a high order of intelligence and manual skill. These qualities, developed at this time, brought forward in the next century the great artists and men of letters of the Renaissance.

Soon the great trade fraternities and trade guilds sprang up, and became a very positive influence in the life

of the time. Great credit came to the tradesman who made an article of such refined and superior workmanship that it brought recognition. To influence, in even a small way, the design or decoration of objects in common use brought an added dignity to the craft worker. The carving of a



Fig. 26. Gothic tracery

piece of wood, the fashioning of a bit of gold or silver, or the weaving of a length of embroidery were not looked upon as tasks, but as real opportunities to excel in intelligent design and finished execution. Sincere pride and pleasure in one's work was the key-note of craftsmanship.

The dress of the craftsman was a combination of smock, the regulation dress of the poor, with the richer dress of the nobles. While these garments were simple and practical, their artistic color and touches of added ornament made them distinctive.

The return of the Crusaders also marks a period of pronounced departure in architecture and ornament. These early Christians saw many beautiful temples in the East, and returned with unbounded enthusiasm to erect houses of worship. Not wishing to imitate the heathen nations, they evolved and in less than a hundred years perfected a type of architecture different from anything that had existed before—the Gothic cathedral. All classes helped to build the churches; nobles and peasants worked side by side, such service being regarded as a form of religious worship. The Gothic lines are "infinitely perpendicular." The vertical masses and the leading lines of windows, arches, and

towers "lift the thought and feeling ever and ever upward." (Fig. 26.) Before the close of the fourteenth century the towering spires of the cathedrals had contributed their influence to the fashion of the day.



Fig. 27. Surcoats and nets

The twelfth century is a period which defines many changes in the dress and customs of the people. At this time the beard appeared in France. It passed through various degrees of change. First, there was the full beard; then the little pointed beard covering only the point of the chin; and by and by it became the fashion to wear it to join the mustaches. At the close of the century, all chins were shaven.

This same period marks an interesting departure in the coiffure of women. Up to this time the hair had been covered by various hoods which concealed it. Even when visible, it was without ornamentation of any kind. Consequently the history of head-dressing proper may be said to begin with the late twelfth century. Now the rolls of hair, sometimes plaited, are arranged at the sides of the head over the ears, and confined in a net called a crestine, crepine, or crespINETTE. Among women of wealth these were of gold thread enriched by a band or coronet of gold and jewels. (Fig. 27.) The veil and wimple were frequently worn over this head-dress (Fig. 25, c and e); this style endured for something like three hundred years. The wimple was used to encircle the face, neck, and head. (Fig. 25, e.)



A kerchief of linen was brought up tightly around the face and caught at the top of the head, while another piece was pinned close to the brows and fell loose to the shoulders (1000-1200). A hundred years later came the fashion of the chinband and the headstrap (1100-1300). (Fig. 25, b.) A century later the *gorget* found its way to popularity. This was a piece of linen wrapped about the head and neck, half way framing the face (1200). Later came the head-dresses of the fifteenth century (1400).

Gloves made their appearance as part of the costume about the twelfth century, and naturally were worn only by ladies of the highest rank. During the preceding century there are rare instances of persons of the most exalted rank wearing gloves. One old manuscript of the tenth century pictures a lady wearing something like a glove. It has a thumb but no fingers, resembling the modern mitten. It was during the twelfth century, however, that gloves as we know them were accepted as fashion. It was not long before glove makers were meeting all the demands of the trade. There were long buttoned and scented gloves, "gloves made of kid and prepared with violet powder." Sheepskin, doeskin, and hareskin were much in favor.

Some of chicken skin for night,  
To keep her hands plump, soft, and white.

Silk and linen gloves, beautifully embroidered, were also made. Frequently the very long sleeves of the gown, falling over the hand, supplied the place of gloves, (*E*, Plate XII), and at times the long mantle served the same purpose. In this day it was not enough to be able to buy gloves, but a lady was supposed to display her taste by knowing just how and when to wear her gloves.

In woman's costume, the twelfth century is designated as that of the "fitted garment." (Fig. 28.) At this time lacing was introduced. This practice reached its most outrageous form during the following centuries. As early as the thirteenth and fourteenth centuries, however, the wasp-like waist of the ladies was admired. Romances of

this early period teem with allusions to and praise of the diminutive waist. Chaucer, describing the Carpenter's wife, says her body was "gentyll and small as a weasel." In Calthrop's history of English Costumes we read, "Not that the lacing was very tight, but it commenced the habit, and the habit begat the harm, and the thing grew until it arrived finally at the buckram, square-built, cardboard and

tissue figure which titters and totters thru the Elizabethan era."

Though the twelfth-century dress does not go to the extreme of the later centuries, it shows the long waist defining the figure. The skirt gathered full hangs from the hips. The sleeves are large and flowing, disclosing the fitted sleeve of the undertunic. A large mantle, and a little veil, confined with a circlet or crown, complete the costume.



Fig. 28. The twelfth-century fitted garment (After Viollet-le-Duc)

During the following century the fitted tunic continued to be worn over the undertunic. This fitted tunic was called a *cote* or *cotta*, and was held by a girdle placed just above the hips. A sleeveless garment either long or short, called the *surcot*, or *sur-*

*coa.*, was worn over the fitted *cotta*. (Fig. 27.) Many have been the transformations of the *cote* and the surcoat through the succeeding centuries. The *cote* became the *cottahardie*—a tunic either long or short, fitting the figure closely, the lower part, if long, made voluminous by gores (*E*, Plate XII); the surcoat merged into the jacket (*B*, Plate XII.) The dress of this period is an important departure in clothes. The surcoat was sleeveless; the arm's eye was so large that the front and back of the surcoat proper were reduced to a few inches. (Fig. 27.) With

these large openings at the side, the girdle worn below the waist and the tunic or cotta were easily seen. The surcoat and cotta were of contrasting material and color,—an important feature of costume at this time. The coat was the richest part of the attire, being made of velvets and silks, elaborately trimmed with ermine. Frequently in walking, the ladies, when wearing long-skirted surcoats, held them up showing the cotta beneath. This was the same color as the sleeves, and made a pleasing contrast with the surcoat.

The thirteenth and fourteenth centuries witnessed a great increase in materials appropriate for garments. There was *samite*, a thick silk in white, green, and red; *cendal*, resembling our silk of the present day; *pers*, a blue cloth; *camelin*, a fabric made from camel's hair; *isambrun*, a cloth dyed brown; "moleskin," a linen cloth; *fustaine*, a strong stuff manufactured from cotton; and finally *serge*, woven of wool, and occasionally mixed with thread. The progress of the arts of weaving and dyeing was extraordinary, and the great supply of fine materials developed a taste for the beautiful in all ranks of society.

Mantles of silk, edged or lined with ermine, surcoats richly embroidered in gold, and jewels of exquisite workmanship, were the common extravagances of the day. Not only was the lady of rank privileged to wear this finery, but the wealthy *bourgeoises* as well adopted the latest decrees of fashion. All ranks affected the leading styles, until it was impossible to distinguish the classes by their dress. Men were arrayed in scarlet, and women in cloth of gold. The limit of income was the only check on the follies of fashion.

The preachers of the day attacked these extravagances. One, Maillard, sketched the portrait of a lawyer's wife dressed like a princess, and others drew comparisons between the poverty of the masses and the indulgence of the wealthy. "The poor," said one of them "are dying of cold, while you, Madame Pompous, Madame Boastful, you have seven or eight gowns in your coffer that you do not

put on thrice in a year." In fact, luxury knew no bounds. Fortunes were consumed in the desire for finery. Louis IX, known as Saint Louis, admonished his courtiers: "You should dress yourselves well and neatly in order that your wives may love you more, and your people will also esteem you the higher for it." It was forbidden for barons' wives to wear gowns of a higher value than twenty-five sous by the yard; the wives of lords were restricted to materials at eighteen sous; the gowns of the *bourgeoises* might cost sixteen sous, nine deniers by the yard. Notwithstanding all these laws, extravagance continued as before. Woman remained the arbiter of her own fashions.

During the fourteenth century the women of the nobility found a way to distinguish themselves from the lesser folk. They began to emblazon the family coat of arms upon their gowns, that all might know their rank. The arms of the husband's family were embroidered on the right side, and on the left that of the lady's own family. The fashion became very popular, and soon heraldic designs, including fleur-de-lis, birds, fishes, ramping lions and leopards, were embroidered on the costume. The ladies employed their leisure hours embroidering not only their dresses, but their belts, bags, gloves, and shoes as well. Out of the taste for heraldic display, grew the fashion of parti-colored robes. (*B*, Plate XII.) One noble lady of Provence is described as wearing a gown, the left side and left sleeve of the bodice being white, while the other side was blue. All through the

---

#### COLOR NOTATION—PLATE XII

- A*—Tunic, B  $\frac{5}{8}$ , B  $\frac{3}{4}$ . Sleeves, uppers, R  $\frac{5}{8}$ ; cuffs, Y  $\frac{5}{8}$ ; puffs, white. Girdle, R  $\frac{5}{8}$ . Head-dress, white.
- B*—Tunic, left, R  $\frac{5}{8}$ ; right, upper, Y  $\frac{7}{8}$ , white figures; lower, P  $\frac{5}{8}$ . Surcoat, G  $\frac{5}{8}$ , edged with gold. Mantle and hood, R  $\frac{5}{8}$ , ermine.
- C*—Tunic, P B  $\frac{5}{8}$ . Gore, R  $\frac{7}{8}$ , R  $\frac{5}{8}$ , gold. Bands of sleeve, R  $\frac{5}{8}$ ; puffs, white; strips, Y  $\frac{5}{8}$ . Girdle, gold; fringe, R  $\frac{5}{8}$ . Hood, black; banding, Y  $\frac{7}{8}$ .
- D*—Houppelande, Y  $\frac{5}{8}$ , R  $\frac{7}{8}$ , ermine. Sash, G  $\frac{5}{8}$ . Vest, black. Head-dress, black, white with gold ornamentation. Veil, white. Gloves, ermine.
- E*—Tunic, G  $\frac{5}{8}$ , black. Cuffs, ermine; ruffs, R  $\frac{4}{10}$ . Girdle, Y  $\frac{7}{8}$ , Y R  $\frac{7}{8}$ , gold. Head-dress, Y  $\frac{5}{8}$ ; banding, G  $\frac{5}{8}$ . Veil, white. Shoes, B  $\frac{4}{10}$ . Roots, Y  $\frac{7}{8}$ , Y R  $\frac{5}{8}$ .





A

B

C

D

E

## PLATE XII—COSTUME OF THE MIDDLE AGES—1395-1495

- A—1495—A lady of rank wearing the fitted garment and the two-horned head-dress of starched lawn.
- B—1395—A parti-colored dress. This fashion followed the vogue for heraldic designs in dress. The close-fitting, long-sleeved jacket is the late development of the surcoat.
- C—1483—A lady of rank wearing a fitted costume.
- D—1422—A lady of rank wearing the great hennin. The collar effect of revers passing from the center of the waistline in front to the center of waistline in the back succeeded the surcoat.
- E—1495—A fashionable costume of this period—the voluminous skirt, flowing fur-edged sleeves, close bodice and the escoffion, or two-horned head-dress, which vied with the hennin for first place.

century wealth and display marked the costume. Gold, silver, and rich materials were worn. The large pattern brocades were much in favor, and the gowns continued to be very long. One side of the skirt was often held up by a clasp attached to a chain which hung from the girdle. This clasp and chain served as an ornament, and was known as the tussoire. Often as a finishing touch to the costume the rosary or paternoster of coral or gold was added. Ornament was added to ornament to attract attention. Finally handsome prayerbooks became a part of the general costume. These were often of artistic workmanship, and were carried in cases which hung from the girdle.

My book of hours, those of Notre Dame, I must have;  
And it should be, as becometh noble dame of high lineage,  
Of subtle workmanship, gold and azure, rich and rare,  
Well ordered and well shapen;  
Covered in fine cloth or in wrought gold;  
And when it is opened to be closed again  
With two golden clasps.

—*From the French of Augustin Challamel.*

During the latter half of the century a new style in dress was born. The voluminous houppelande became the fashion. This was a one-piece dress in which women are said to have discovered the normal waistline. (*D*, Plate XII.) The bodice was tight-fitting, with a deep V-shaped neck and large revers very wide at the shoulders; the sleeves were long and close, and the skirt enormous. It was usually made of material resembling tapestry in design. The skirt was frequently carried in huge folds over the arm. (See dedication page.) Isabelle of Bavaria, queen of Charles VI, set the fashion of having the long trail carried by a lady's maid or pages—a custom much in vogue in court circles during the following centuries. The treasured tapestries of the fifteenth century picture the ladies of this day in voluminous houppelande and towering head-dress. It was at this period, when the bodice was very tightly laced, that the extreme décolleté became fashionable. Isabelle was, moreover, the first to wear linen undergarments. This

fashion was also readily adopted by the ladies of the period. The linen chemise was regarded as a luxury, and called *robe-linge*. In order to allow a glimpse of the underlinens, the ladies of the court cut slashes in the sleeves of their gowns and also in the hips of their skirts. This vanity finally led to a deception. Only that part of the chemise which could be seen was made of linen, and the remainder of the old-time woolen material.




Fig. 29. Pattens

In men's clothes the long tight hose and doublet were adopted, and being such a decided change after centuries of long robes which concealed the figure, they were stigmatized for their "horrible inordinate scantiness." (*A, C*, Plate XIII.) The long tight hose were made of rich materials, and were often parti-colored. Frequently one hose was decorated in a style quite different from the other, rendering "uncertain the fellowship of the legs." The long hose was connected with the doublet by means of points, which were ties or laces with a metal tag at the end, and used to fasten garments together. They were in general use until the seventeenth century both for armor and for civilian dress.

Their points being broken, down fell their hose.

—SHAKESPEARE.

Buttons are believed to have been used in a very limited way in the late thirteenth century, and during the vogue of the tight-fitting gown of the fourteenth century. Laces and points seem to have superseded buttons in the fourteenth

and fifteenth centuries, but in the sixteenth they came again into their kingdom, and great was their variety and magnificence. Buttons of diamonds and other precious stones are mentioned; buttons of gold, silver, brass, and other metals; of horn, mother-of-pearl, ivory, bone, jet, glass, and wood covered with silk and velvet. Paste buttons which rived in brilliancy the finest precious-stones were also made. At this time (1600-1700) thousands of men, women and children were employed in the making of buttons.

The curious shoes of the period, called *à la poulaine*, were made very long and turned up, resembling the prow of a ship. (*D*, Plate XIII.) The fashion was adopted from Cracow, in Poland; in England shoes of this type were termed "Crackowes." Shoes were a mark of distinction, the various types indicating the wealth and dignity of the wearer. Later the points were exaggerated and twisted to resemble a ram's horn. During inclement weather, pattens, a kind of overshoe with cork or wooden soles, were adjusted to the foot, serving as a protection from the dampness. (Fig. 29.)

It is a curious fact that the most depressing period of French life, the Hundred Years War (1400-1450), has become known historically for the remarkable splendor of its fashions. This period is famed for its unusual head-

---

#### COLOR NOTATION—PLATE XIII

- A*—Trunk-hose, N 6; design, Y 8%. Doublet, G 4%; fur, black; belt, black; neckband, Y 8%. Sleeves, R 8%. Shoes, Y 4%; fur, white. Hat, Y 4%; feather, white.
- B*—Skirt, R 4/10. Banding, Y 7/8, Y R 7/8, gold. Front of bodice, Y 7/8, Y R 7/8, gold. Sleeves, alternate, R 4/10, Y 7/8, Y R 7/8; puffs, white; flowing cuffs, white. Head-dress, Y 7/8, Y R 7/8, gold.
- C*—Trunk-hose, G 4%; design, Y 8%. Sleeves and doublet, Y 8%; spots, R 8%. Over-doublet, black; lining, B 8%; edge, Y 8%. Hat, G 4%, Y 8%. Shoes, Y 8/10. Insignia, Y 8%.
- D*—Cotta, B 4/10, B 3/4, black. Cuffs, shoes, R 4/10. Coverchef, R 4/10; lining, white. Collar, ermine. Facing of cotta, ermine. Girdle, Y 7/8, Y R 7/8, gold.
- E*—Cottahardie, R 4/10. Mantle, P B 4%; lining, white. Hood, R 4/10; facing, white. Gloves, G 8%. Girdle, white.





A

B

C

D

E

PLATE XIII—COSTUME OF THE MIDDLE AGES—1386-1498

- A—1498—A man of rank wearing the long, tight hose and the doublet. The hose were often in gay color and frequently each of a different color.
- B—1498—A lady of rank wearing an elaborate gown. The bodice is snug and the skirt voluminous.
- C—1498—A man of rank wearing parti-colored trunk-hose. Insignia—Order of the Golden Fleece.
- D—1395—The short-waisted garment followed the long-waisted costume. The hood, in stiffened form, was made of parchment and covered with silk or cloth.
- E—1386—A lady of rank wearing the fitted tunic. The hood is a variation of the Phrygian bonnet. Gloves were more generally worn at this time than in the earlier centuries.

dressess, which grew to such an exaggerated height that the ceilings in the castle of Vincennes were raised to permit the ladies of the court to move about in comfort.

It is to the rich tapestries produced by our mediaeval ancestors that we turn to find these dames of high degree pictured in all the splendor of their rich materials and towering head-dresses. These woven chronicles invite us to study not only the costume of the period, but the love of color and color harmony which these ladies of the long-ago carried into their gowns and all their belongings. "Never perhaps," writes Viollet-le-Duc, "did extravagance in head gear reach such a pitch with the fair sex as during those melancholy days from 1400 to 1450. The hair itself formed but a small part of the head-dress; hoods, covrecheufs, chapels, fremillets, and chains were built up into the most extraordinary edifices."

The styles of head-dresses were various, but the hennin took the lead, and became the *ne plus ultra* of fashion. (*D*, Plate XII.) This particular type of head-dress was a tall conical cap, probably a yard high, fitting close to the head. From the peak of this towering edifice a veil of finest texture fell over the shoulders. This style was termed the great hennin; of course there were various heights, each woman adopting that which appealed to her.

The escoffion was a second distinct type which is believed to have been introduced into France by Isabelle of Bavaria. Naturally all the ladies were anxious to copy the fashion. (*E*, Plate XII.) Thus the new head-dress vied with the hennin for first place. The escoffion was a two-horned arrangement, being about a yard high, made of fine lawn, and stiffly starched and wired to keep its horns in place. From the tips of the horns flags, fringes, and other materials fell to the shoulders. Besides these two distinct types there were others: the turban, the heart-shaped cap, and the little hennin.

Again the philosophers and moralists organized a deadly warfare against these extravagances of fashion. They com-

pared the women who wore these head-dresses to horned beasts and to pictures of Satan. The cry was: "War to the hennins! War to the hennins!" One Carmelite monk, Brother Thomas Connecte, traveled from place to place denouncing the extravagances of dress, and hurling all sorts of invectives against the women who desired to be fashionable, even threatening them with the divine wrath. Not only did he preach against these whims, but he fared forth one day and massacred without mercy all the hennins he encountered. All the preaching against the style, however, only stimulated the taste for hennins, and they continued as high as ever. "The ladies," wrote Guillaume Paradin, the historian, "imitate the snails, who draw in their horns, and when danger is over peep them out farther than ever; in like manner the hennins were never more extravagant than after the departure of Brother Connecte." The head-dress continued, and was given up only when a caprice for change decided it.

As we of today read of the attacks of the church fathers upon the extravagances of dress, we are inclined to be amused. We should not forget, however, that it was the church, the religious life of the period, that gave to the world the beautiful in art and ornament,—gave it permanence and bequeathed it to the coming ages. The great cathedrals scattered over the land, with their colored glass windows, mosaics, and rich tapestries are among the world's greatest treasures. The most beautiful embroideries and tapestries of any age were made by the nuns of the church. In these are recognized all the stitches in popular use today; the chain stitch, the tapestry stitch, cross stitch, couching stitch, appliqué, and the origin of crochet. The monks lettered and illuminated books, tooled and embossed the leather covers, and finished them with delicately wrought clasps.

The influence of the East is felt in the early designs and ornament of the Middle Ages; the originality, however, which developed through the years is remarkable. Heraldic designs, decorative lettering, and Gothic tracery are the



types of ornament always associated with the period. The thought of the designer combined with the spirit of the craftsman made the art of the period an inspiration for all future time.

The relation existing between fashion and architecture is keenly appreciated at this period of the Middle Ages, when the Gothic turrets of castle and cathedral echoed the towering head-dress of the lady of fashion. The bright coloring of the Gothic period is seen alike in cathedral and in milady's trailing and emblazoned gowns. Looking back to the Egyptian days the same similarity exists between the massive and heavy temples and the simple and severe costumes of the Egyptian people. The love of color is seen alike in the dresses of these primitive artists, and upon the walls of their marvelous temples. Simplicity and grace were the distinguishing charm of Greek dress and Greek architecture. The Roman Empire appropriated much of Greek refinement in both building and dress; in the later period, however, the decline in taste is suggested by many of the portraits—figures ornamented "from head to foot with pearls and precious stones intermixed with cameos."

It was in the closing years of the fourteenth century that beautiful dolls dressed in the very latest mode were used as models of fashion, being passed from France to other European countries. The charming Isabelle is said to have sent a number of dolls, dressed in the very latest French fashion, as a gift to the Queen of England. Venice annually imported a French doll, which was exhibited on Ascension Day in the Piazza of St. Mark, the fashionable quarter of the city, as "the toilette of the year." During the seventeenth and eighteenth centuries these fashion dolls became more and more indispensable for supplying the latest word in French fashion.

The depressing period toward the close of the reign of Charles VI caused a lull in the fashion world. This, however, was only temporary. When Charles VII ascended the throne he set an example of such luxury to his people,



that the devotee of fashion again plunged into the greatest extravagance of dress.

Agnes Sorel, famous both for her wit and beauty, now takes the place of Isabelle of Bavaria as the fashion leader of the court. She was dubbed "the Lady of Beauty" of the period, and the fashion world eagerly awaited her every decree. The fashions set by this fair creature, no matter how extreme or indecorous, became the rage. She introduced the fashion of leaving the bosom uncovered to the waist, and was the first to wear diamonds in her hair. Her portrait, painted by an artist of the period, hangs in the famous gallery at Versailles. Trailing gowns, high head-dresses, laces, gloves, mittens, rings, and necklaces were the order of the day. Walking-sticks made of valuable wood with ornamented tops again came into vogue. Toward the end of the fifteenth century (1495) gold and silver embroidery was added to the backs of gloves, which still continued to be violet scented. Fans, usually made of feathers, were carried to church by these ladies, and used to disperse the flies.

On one point, that of the color of the hair, the taste of the Middle Ages was similar to that of the classical world. Fair hair was still considered the most beautiful. The French maidens who were not fortunate enough to be fair-haired by nature became so in spite of nature's edict. This preference for light hair led to the manufacture of great quantities of false hair.

Toward the dawn of the Renaissance a sudden change took place in the whole character of costume.

When Charles VIII and his army made their famous expedition into Italy they incidentally captured lords and ladies alike by their agreeable manners and French finery. The Italians made haste to adopt many details of the French costume; likewise many pleasing features in the dress of Italy were appropriated by the French nobles. Later when the King of France and his retinue returned to his court, the French ladies in turn were fascinated by the Italian coloring, materials, and many of the styles which

were entirely new. This enthusiasm was expressed in the fashions of the day, and many Italian ideas were assimilated in French dress. Tight-fitting bodices, many colored fringes trimming the gown, and a black veil, were especially novel. Bright colors were the vogue, and the great demand led to the importation of rich Milanese and Venetian merchandise.

The hennin was at last declared passé, and the long-toed shoes became a matter of history. The round toes called *sollerets*, such as were worn by Italian women, and which fitted the foot, were substituted. High heels were as yet unknown, but they gradually grew out of a kind of slipper with several soles placed one above the other. Hose or stockings were made of pieces of material sewed together. The word "stocking" as applied to hose does not appear until the fifteenth century.

Later in the period, sleeves became a curious novelty. In the outside garment they remained long and flowing, while those of the underdress were frequently made of different colors fastened together by ribbons. Sleeves were large, long, wide, or close-fitting; sometimes they were buttoned from the shoulder to the wrist; sometimes puffs were worn at the shoulder and elbow. (Plate XII.) Sleeves which took the form of mittens were called *mitons*; then there were the sleeves like wings, with edges cut like oak leaves and edged with fur. The poet and chronicler of the fifteenth century, Olivier de la Marche in his *Le Parchement des Dames* speaks of slippers, shoes, boots, hose, garters, stomachers, stay laces, chemises, pin holders, *amônières*, mirrors, coifs, combs, and ribbons, all of which were to be found in the wardrobe of these women of the long ago.

With the beginning of the Renaissance (1500), foreign materials of the finest manufacture began to pour into France. The linen from Holland was especially fine; Bourges was famous also for its rare cloth. French gentlemen usually stipulated that the tailor use "fine Bourges

cloth.” Fine wools came from Spain; gold and silver from Italy.

Although the fashions of the Middle Ages reached an extreme which was considered excessive for that period, it is in the following century that the most luxurious extravagance finds expression.



## CHAPTER VII

### THE RENAISSANCE IN FRANCE

(1500)

THE Renaissance opened under the dazzling splendor of the court of Francis I. The king was always in elegant attire, and set the fashions for the gentlemen of the period, which were no less magnificent than those of the ladies.

It is interesting to note that the decided change in costume, which set in during the previous century and which marked the break between the costumes of the ancients and those of the modern world, continued to grow and become more general. The long tight-fitting hose extending from the waist to the foot became known as the "trunk-hose"; the doublets began to have close-fitting and large sleeves; hats with brims, and shoes and boots were adopted. Women too had everywhere adopted the tight-fitting gown, an entirely different type of dress from that of antiquity, and the common type upon which fashion has played in varying strains ever since.

In the earliest years of the Renaissance the general style of costume continued similar to that of the previous century, at least, until that great innovation of the Renaissance—the farthingale (*vertugale*, *vertugade*, *vertugadin*.) This new feature in dress, which was destined to play a role so important, was ushered into France from Spain in 1530. It was a contrivance unheard of before, and upset and changed all the lines of costume. The farthingale remained the vogue for about three hundred years under various names,—the hoop, crinoline, panier, pouf, and bustle.

The initial appearance of the farthingale was the stiffened pad stretched upon wire frame. This was attached to the waist giving width to the hips. It was then known as the "shakefold." The name, shakefold, grew out of the



appearance of the skirt as it fell in great flute-like folds over the extension and swayed gently to and fro as milady moved about. Later the stiffened pad was made of whalebone or cane and bell-shaped in form, suggesting a cage-like petticoat. Afterward the name farthingale was applied to petticoats mounted on hoop, iron, wood, cane, or bone. As usual, women vied with one another in the width of their hips and fullness of their skirts, until, forsooth, again came the edicts against the new mode. These were many and severe, but the more numerous the edicts, the more general and daring the fashion. In the *Discours sur la Mode*, published in 1613, we read as follows:

The large vertugadin is common to all French women;  
The bourgeoises wear it freely now,  
Just the same as the great ladies, if it be not  
That the bourgeoisie is content with a smaller one;  
For the great ladies are not satisfied  
With a vertugadin less than five yards round.

It is recorded that a young widow wearing a hoop of extraordinary width was accused before the court. There she gave her word of honor to the counselors that the "exaggerated size of her hips, which was the cause of the complaint, was simply a gift of nature." The judges, of course, acquitted the widow.

The boned bodice, called the basquine, and resembling a corset, also made its appearance during the reign of Francis I. This was usually worn over a chemise of fine material.

The materials in use were very elegant—silk, satin, damask, serge, camlot, and velvets of blue, crimson, violet, green, grey, and orange. In winter the gowns were often lined with the richest of furs.

The style of dress varied but little as the years passed by. The costume *la mode* was made with a deep-pointed bodice, to which was attached the skirt, which opened all the way down the front, showing a handsome underskirt harmonizing in color and material with the gown. (*D*, *E*, Plate XV; *A*, Plate XVI.) The sleeves were often narrow to the elbow, where they widened into great hanging cuffs

bordered with fur, silk, or lace. (*D*, Plate XIV; *F*, Plate XV.) Sometimes they were raised over the shoulder in enormous puffs, and formed a succession of puffs down to the waist. (*E*, Plate XV.) Again they were slashed, showing puffings of different colored silk. (*C*, *D*, Plate XVI.) The leg-mutton sleeve which was formerly worn was revived for a short time at this period. (*B*, Plate XV.)

There was little change in shoes. They were still worn of silk and satin and often slashed several times over the instep. Occasionally they were cut very open on the instep, a style not lending any particular beauty to the foot. These shoes, however, were especially adapted for indoor wear. For outdoor wear pattens were adjusted over the shoe or slipper. About 1550 the narrow toes, which had become rounder during the introduction of Italian ideas into France, now grew apace, indeed to an excessive degree, for no one was considered fashionable whose shoes did not measure at least a foot across the toes. (*A*, *B*, Plate XV.) These shoes were generally made of leather, though frequently they were of silk and velvet, and various colors were exhibited in the slashes at the toe.

The huge head-dresses of the preceding period were succeeded by small caps of velvet or silk, and graceful turbans. Rosaries, long chains of gold called *cordelières* which hung from the girdle, together with necklaces and rings

---

#### COLOR NOTATION—PLATE XIV

- A*—Gown, R  $\frac{3}{8}$ ; design, R  $\frac{3}{4}$ . Flounce, Y  $\frac{8}{10}$ . Sleeves, uppers, G  $\frac{5}{8}$ ; puffs, white; cuffs, R P  $\frac{5}{8}$ . Cord and *amônière*, Y  $\frac{5}{8}$ . Veil, white.  
*B*—Hose, B  $\frac{3}{8}$ . Doublet, Y  $\frac{3}{8}$ , gold. Undertunic at neck, white. Jacket, R  $\frac{3}{8}$ . Collar and bandings, white. Hat, N 6.  
*C*—Gown, B  $\frac{3}{4}$ . Collar, white. Vest, R P  $\frac{3}{4}$ ; band, Y  $\frac{7}{8}$ . Sleeves, alternate, B  $\frac{3}{4}$ , R P  $\frac{3}{4}$ . Cuffs, Y R  $\frac{3}{4}$ . Shoes, Y  $\frac{3}{8}$ . Hood, B  $\frac{3}{4}$  and white; facing, Y  $\frac{3}{8}$ . Cord, Y  $\frac{7}{8}$ ; pendant, gold, mirror. Necklace, pearls; pendant, gold.  
*D*—Overdress, black, edged with white fur. Cuffs, Y R  $\frac{3}{4}$ . Trimming on bodice, gold. Undersleeves, white; slashes, R  $\frac{4}{10}$ . Underskirt, Y  $\frac{3}{8}$ ; bands,  $\frac{3}{8}$ . Girdle, gold. Pendant, gold; stone, R  $\frac{4}{10}$ . Hood, black, white fur.  
*E*—Costume, Y  $\frac{1}{2}$ . Undertunic showing in slashes, white. Girdle, Y  $\frac{7}{8}$ , stones, R  $\frac{4}{10}$ . Necklace, Y  $\frac{7}{8}$ , stones, R  $\frac{4}{10}$ . Hat, Y  $\frac{1}{2}$ , plume, white. Ruff, white. Bands below shoulder puffs, Y  $\frac{7}{8}$ , stones,  $\frac{4}{10}$ .



A B C D E

PLATE XIV—THE RENAISSANCE IN FRANCE—1500

- A—1515—A lady of rank.  
 B—1550—A nobleman wearing the long trunk-hose, the doublet and jacket. The embroidered doublet was gradually transformed into the waistcoat.  
 C—1545—A lady of rank wearing the fitted garment with the great, hanging sleeves. A small cap of velvet takes the place of the exaggerated head-dress. The girdle, with pendant set with jewels, was indispensable.  
 D—1520—A fashionable dress showing the pointed and boned bodice to which the open skirt was attached.  
 E—1558—A lady of rank wearing a variation of the prevailing style. The slashed bodice and sleeves show the underdress of contrasting material.

profusely set with emeralds, turquoises, diamonds, and sapphires, completed the costume. Muffs which at this period were called *contenances* were in fashion, and were carried exclusively by women of rank. With the introduction of the wide skirt, the broad shoes, and the little low cap, the tall stiff lines of the Gothic period began to give way to the curved lines of the Renaissance.

With the coming of Henry II to the throne in 1547 troublesome times were brewing. The extreme splendor of the fashion of the previous period changed into one of gloom. Bright and gay colors became more somber in tone, and were for a time succeeded by black, which later alternated with the brilliant and showy. The great fullness of skirts and the enormous sleeves were characteristic of this period.

The ruff, a new fashion and one which became extremely popular, was introduced from Italy by Catharine de' Medici, the wife of Henry II. This novel accessory of costume was destined to run the whole gamut of extravagance. In its early days the ruff was usually of plaited lawn or fine material, encircling the throat and reaching to the ears. (*D, E, F*, Plate XV.) Later, however, it was made of the

---

#### COLOR NOTATION—PLATE XV

- A*—Breeches, white, B  $\frac{5}{8}$ . Doublet white, gold; stripe, B  $\frac{5}{8}$ . Hose, white. Shoes, Y  $\frac{8}{8}$ ; slashes, B  $\frac{5}{8}$ . Mantle, black, gold; lining, Y  $\frac{8}{8}$ , Y R  $\frac{7}{8}$ , gold. Hat, black, gold. Feather, white. Gloves, Y R  $\frac{7}{8}$ .
- B*—Skirt, R  $\frac{5}{10}$ . Bodice, R P  $\frac{3}{4}$ ; banding, Y  $\frac{7}{8}$ . Apron, black. Head-dress, black. Ruff, white.
- C*—Breeches, white, Y  $\frac{8}{8}$ , gold. Peplum, Y  $\frac{8}{8}$ , G Y  $\frac{7}{8}$ . Doublet, Y  $\frac{8}{8}$ , or white. Belt, black. Mantle, black; banding and insignia, Y  $\frac{8}{8}$ , gold. Toque, black, Y  $\frac{8}{8}$ , gold. Feather, white. Ruff, white. Hose, white. Shoes, Y  $\frac{8}{8}$ , or white. Insignia, gold; ribbon, B  $\frac{5}{8}$ . Ornaments, gold and gems.
- D*—Overdress and bodice, brocade, R  $\frac{4}{6}$ , R  $\frac{3}{6}$ . Bandings, Y  $\frac{7}{8}$ , Y R  $\frac{7}{8}$ , G  $\frac{3}{4}$ . Sleeve puffs, guimpe, ruff, white. Underdress, G  $\frac{3}{4}$ . Girdle, gold; *cordelière*, black; ornaments, gold with stones, R  $\frac{4}{10}$ . Toque, black; feathers, white.
- E*—Overdress and bodice, brocade P B  $\frac{4}{8}$ , P B  $\frac{3}{8}$ . Underskirt, sleeves and guimpe, white. All bandings, Y  $\frac{7}{8}$ . Necklace and *cordelière*, pearls; stone, G  $\frac{5}{8}$ .
- F*—Overdress and bodice, P B  $\frac{5}{8}$ . Band and undersleeves, R P  $\frac{5}{8}$ . Great cuff, R  $\frac{5}{8}$ . Small cuffs, guimpe and ruff, white. Necklace, girdle, pendant, gold. Stone, R  $\frac{4}{10}$ . Head-dress, black, white.





A

B

C

D

E

F

## PLATE XV—THE RENAISSANCE IN FRANCE—1500

*A*—1547—Costume worn by Francis I. The long hose with the puffed trousers of silk and velvet; the fitted doublet with huge sleeves; broad-toed shoes and little hat with a feather picture the dress of this leader of fashion.

*B*—1558—This costume pictures the leg-o-mutton sleeve which was revived at this time, and the Marie Stuart cap.

*C*—1589—The costume worn by Henry III. The king wears the corset, the fitted doublet with peplum, the short breeches, and the velvet cape.

*D*—1560—A lady of rank wearing the fashionable dress of the day—the boned bodice and open skirt.

*E*—1559—A fashionable lady wearing the pointed bodice and hoop-skirt.

*F*—1575—A costume showing the prevailing fashion.

most exquisite laces and extended not only to the top of the ears, a very modest height (*A*, *E*, Plate XVI) but to the top of the head, and the ultra-fashionable did not hesitate to raise it beyond the top of the head-dress.

An amusing incident about the ruff is told by Brantome, the historian. On one occasion a gentleman of the court was in conversation with Queen Catharine. The subject was ruffs. The gentleman expressed his surprise that women should care to wear such deep ruffs, and his doubt of their ability to take their soup without soiling them. The next moment a valet handed the queen a *bouilli* for refreshment. The queen taking a long handled spoon sipped the *bouilli* without embarrassment and then said: "You see, Monsieur de Tresnes, that with a little intelligence one can manage anything."

After a brief space of dark colors, the women of France were again seized with a boundless caprice for finery. The clergy again issued edicts, and laws were passed regulating the color and quality of materials according to rank. Only a princess was privileged to wear a crimson costume, while other ladies of high degree might have only a part of the gown of this royal color. Silk was forbidden to working women, except for trimmings. The general type of woman's dress and head-dress of this period was very charming. The most exquisite needle work was often lavished upon the garments, and many ladies of rank decorated their cos-

---

#### COLOR NOTATION—PLATE XVI

- A*—Overdress and bodice, Y R  $\frac{5}{8}$ ; stripes, Y R  $\frac{1}{8}$ . Underskirt, white; bandings, Y R  $\frac{1}{8}$ . Cuffs, collar, white; edge of collar, head-dress, Y  $\frac{7}{8}$ . Chains, gold; stones, R  $\frac{4}{10}$ , G  $\frac{7}{8}$ . Fan, B G  $\frac{1}{8}$ , white.
- B*—Trunk-hose, white. Doublet, R  $\frac{7}{8}$ ; slashes, white. Jacket, black; fur, Y  $\frac{7}{8}$ , Y R  $\frac{1}{8}$ . Hat, black, white, gold. Shoes, Y  $\frac{5}{8}$ , or white. Gloves, Y  $\frac{1}{8}$ . Belt, Y  $\frac{7}{8}$ , gold. Chain, gold.
- C*—Overdress and bodice, P B  $\frac{4}{8}$ . Banding on sleeve, R P  $\frac{1}{8}$ . Collar, vest, white. Underdress, R  $\frac{1}{8}$ ; banding, Y  $\frac{7}{8}$ , Y R  $\frac{7}{8}$ . Head-dress, black, white.
- D*—Overdress and bodice, P B  $\frac{4}{8}$ . Sleeves, Y  $\frac{7}{8}$ ; slashes and bandings, B G  $\frac{1}{8}$ . Underdress, R  $\frac{5}{10}$ ; banding, B G  $\frac{1}{8}$ . Head-dress, black, white.
- E*—Mantle, N 4. Slashes in sleeve, Y  $\frac{7}{8}$ . Hat, N 4. Feather, white.



A

B

C

D

E

## PLATE XVI—THE RENAISSANCE IN FRANCE—1500

- A—1574—A lady of rank. The open overdress displays the handsome underskirt of a harmonizing color. The jeweled *cordelière* was always worn with dresses of this type. The Medici ruff and Marie Stuart cap picture the vogue at this period.
- B—1545—Costume worn by Francis I. He wears the trunk-hose and the open jacket, displaying the elaborate doublet.
- C—1590—A lady of rank wearing the barrel-shaped hoop. The pointed bodice and puffed sleeves continue.
- D—1586—A costume of the same period.
- E—1598—A nobleman. The long boots of Russia leather were introduced by Henry IV. The *mancheron*, or false sleeve is seen in the costumes of both men and women.

tumes with *fers* (E, Plate XIV), an ornamentation resembling metal buttons. Laces too, imported from Venice, Brussels, and Genoa, added a pleasing decorative note to the costume.

In many of the costumes of this and later periods the curious custom of wearing the *mancherons* came into vogue, and was adopted by both men and women. (E, Plate XVI.) These were false sleeves which hung from the shoulder at the back, or from the epaulette, and extended below the hip. The general lines of the gowns continued similar to those of preceding reigns. The slashed and embroidered costumes, the close bodice, the puffed sleeve, and the ruff remained in vogue. Usually necklaces were discarded when the ruff was worn though occasionally, in court circles, the two were seen together.

The general head-dress was a little cap, pointed in the center, coming down to the edge of the forehead, making the face look heart shaped. This is the particular style known as the "Marie Stuart." (B, F, Plate XV.) Black velvet and silk hoods were also much in vogue. (D, Plate XIV.) This was the favorite head-dress of Catharine de' Medici. They were often padded, and a square of stuff was fastened to the string of the hood which could be drawn like a veil over the lower part of the face. This type was usual in cold weather. The charming little toque or cap with soft crown and narrow brim was exceedingly popular with both men and women. A little feather was always worn at one side, giving a piquant charm to the wearer. (E, Plate XIV; C, Plate XV.) Hats were less generally worn, and were usually oval-shaped with wide brims and made of fine materials of fine felt.

The curious innovation in head decoration was the wearing of a mask, called *loup*, meaning wolf. This name arose from the fact that when first worn it had a tendency to frighten the children. It was considered very bad form indeed for any lady of quality to go upon the streets without the *loup*. These masks were made of black velvet and at first were quite short, allowing the lower part of the face to



be seen. Later they were made longer, coming to the edge of the chin. The short ones were kept in place by being fastened behind the ears; the longer ones were secured in a more elegant way—by a glass button held between the teeth. The object of the mask was presumably one of protection. It preserved from sunburn the French complexion, which was usually made up with white paint and rouge.

Paint had been introduced into France by Catharine de' Medici, and the faces of the fashionable and the wealthy bourgeoisie were literally coated with patches of white paint and vermillion. Pomades and drugs reigned galore! Strange and weird were the concoctions destined to outdo nature herself in promoting beauty. The wings and claws of pigeons, pulverized and mixed with fresh eggs, lilies, Venetian turpentine, shells, ground mother of pearl, and camphor, the whole distilled with musk, was the witching pomade of the period. All of this vanity created another indispensable trinket, the dainty little hand-mirror, which must ever be ready. Consequently it hung from the girdle, and thus milady was never in doubt as to her correct appearance.

The religious wars overshadowed France at this period (1560-1574), and had a gloomy effect upon all matters of dress. Charles IX openly professed his contempt for over-attention to dress, and during the first year of his reign sent out the royal edict: "We forbid our subjects, whether men, women or children, to use on their clothes, whether silken or not, any bands of embroidery, stitchings or pipings of silk, guimp, etc., with which their garments or part thereof might be covered or embellished, excepting only a bordering of velvet or silk of the width of a finger, or at the most two borderings, chain stitchings or back stitchings at the edge of their garments." He also forbade farthingales of more than one and one-half yards in width, gold chains, buttons, and all devices for ornamentation.

As usual, however, Fashion continued to wield her scepter. The king might pass edict after edict, but it was of no avail. The great arts and crafts movement of the Middle

Ages had taught the people the use of their hands. This, combined with a knowledge of pattern, enabled a woman of the middle class to embroider her gown at no expense to herself, and to make it as finished and beautiful as that of the great lady who spent immense sums on her clothes. The fine laces of Brussels and Venice were also imitated by the craftswomen of the period, and ornaments of the finest workmanship, made by their own hands, were used as rich accessories to their costume. Towards the end of the reign of Charles IX (1560-1574) we find an interesting account of costume given by the Venetian ambassador, who was evidently a close observer of fashion. In this account he says:

French women have inconceivably slender waists; they swell out their gowns from the waist downwards by stiffened stuffs and vertugadins, the which increases the elegance of their figure. They are very fanciful about their shoes, whether low slippers or escarpins. The cotillon (underskirt), which in Venice we call *carpetta*, is always very handsome and elegant, whether worn by a bourgeoisie or a lady. As for the upper dress, provided it is made of serge or *escot*, little attention is paid to it, because the women, when they go to church, kneel and even sit on it. Over the chemise they wear a *buste* or bodice, that they call a *corps piqué*, to give them support; it is fastened behind, which is good for the chest. The shoulders are covered with the finest tissue or network; the head, neck, and arms are adorned with jewels. The hair is arranged quite differently from the Italian fashion; they use circlets of wire and *tampons* over which the hair is drawn in order to give greater width to the forehead. For the most part their hair is black, which contrasts with their pale complexions; for in France, pallor, if not from ill health, is considered a beauty.

When Henry III came to the throne in 1574 the gloom in France had by no means been lifted. Religious strife and bloodshed still made the atmosphere of Paris heavy. One would think that under such conditions fashion would step aside and give place to thoughts of more serious import. Generally speaking the national mood is reflected in the dress of the period; but at times extreme frivolity will flaunt itself in the face of disaster. Just such a condition in France attended the accession of Henry III.

Instead of the simplicity which Charles IX tried to sustain, Henry of Valois set the pace for his nobles in the most eccentric extravagance of dress. Great was the luxury and license of the French nobility. The men and women vied with each other in the elegance of their dress to such an extent that the gentlemen became as feminine as possible in their attire, and their whims and absurdities were unbounded. They imitated the ladies in wearing not only necklaces, rings, and ear-rings, but also ruffs and rolls of artificial hair. They adopted the corset to give them slim waists, and the busked doublet (the doublet with boned front coming down to a point), which gradually evolved into the padded front, forming a pouch-like protuberance which imparted a grotesque appearance to the wearer. This fashion, however, did not last, possibly because it was clumsy, or still more likely, because it created a great deal of ridicule. It was in the latter part of this century that pockets were introduced in the trunk-hose, thus doing away with the pouch which had been in common use for six hundred years. The doublets, also called pourpoints, were usually open, revealing the most exquisite Venetian point. Fans were carried by these "curled darlings" of society, and as a vanity of vanities they wore at night masks and gloves saturated with oils and pomades.

Henry himself wore the little plumed toque, the aigrette of diamonds, and the ruff. (*C*, Plate XV.)

At one time he appeared in a ruff made of fifteen breadths of cambric a half-yard in depth. "To see his head against that ruff," said Pierre de l'Estoile, "put one in mind of St. John the Baptist's head on a charger."<sup>a</sup>

The serious minds of the time were aghast over the king's eccentricities. D'Aubigné exclaimed:

So that at a first glance each comer was at a loss  
To know whether he beheld a king-woman or a man-queen.

Worse than all this, however, was the king's love for paint, powder, and perfume. Perfumes were the rage. Everything was bathed in amber, musk, ambergris, and other

scents. With all this foppishness in gentlemen's attire, certainly feminine extravagances may be condoned.

The whalebone bodice, worn as tight as could be endured became the vogue. "When the princess or duchess," says




Fig. 30. Steel corset worn by Catharine de' Medici

Montaigne, "had not whalebone bodies, they tightened their waists with wooden splints; for, above all, it was necessary to astonish the world with a slender waist." Fig. 30 shows a type of steel corset worn by Catharine de' Medici.

The bodices were loaded with beads, embroidery, or gold and jewels. Pearls were arranged in design on both the bodices and skirts. The girdles were often the work of artists in goldsmithing, and the mirror which continued to be a part of feminine attire was richly set

with jewels. Ruffs assumed fantastic proportions; in fact the one note in women's attire was the exaggeration of former styles and the over adornment of their gowns. The farthingale was not to be overlooked, and it grew apace.

As Isabelle of Bavaria and Agnes Sorrel each had her day as a leader of fashion, so at this period of the Renaissance Marguerite of Valois, the king's sister, became the social arbiter for her sex. She was very beautiful and very charming, but with all her beauty and engaging manners she is said to have degraded the fashions of the period. It was she who lengthened the waist to an excessive degree; who puffed the sleeves at the shoulders and tightened them at the wrist; and lastly tried to replace the farthingale with masses of padding on the hips. (*C*, Plate XVI.) Thus the days of the Renaissance wore on in unbridled extravagance.



Not until the close of the century did the change come; then it was that the gloom which hung over Paris during the last half of the century appeared in costume. The murder of the Duke of Guise in 1583 created a period of extreme depression. Deep mourning prevailed in the city, and fashionable costume became intolerable. Feeling ran so high that there was no hesitation on the part of the people in laying hands upon the offender in dress. A woman wearing the obnoxious ruff or the over-puffed or slashed sleeve might be attacked and the superfluous adornments torn to shreds.

So deep was the gloom and so great the depression that the few remaining years of the early Renaissance under Henry IV were largely years of recuperation. It took even gay Paris time to find herself. Those who would be fashionable, according to d'Aubigné, adopted brilliant colors—"rat color," "widow's joy," "envenomed monkey," or "chimney sweep." They also began to arrange the hair itself as a head-dress, which gave rise to enormous quantities of false hair and powdered wigs.

Thus the first century of the Renaissance ended. Although the Renaissance was destined to become the brightest period in the world of art and letters, its opening century contributed little but extravagance and gloom to the world of dress.



## CHAPTER VIII

### THE RENAISSANCE IN FRANCE

(1600)

WITH the opening days of the new century, Paris begins to breathe more easily and gradually to emerge from the stifling atmosphere of the past into the bright Parisian sunshine. The love of change, the love of admiration, and the love of elegance are so largely a part of the French temperament that once the spirit revives, it goes on to free if not extravagant expression.

Henry IV, one of the greatest statesmen and soldiers of the period, occupied the French throne during the first ten years of the century. Giving himself wholeheartedly to the stupendous task of reconstruction after the religious strife and bloodshed of the preceding period, he was naturally less interested in matters of dress than were the foppish puppets whom he succeeded in the royal office. The position of arbiter of fashion for the kingdom did not appeal to him; whenever he deigned to don elegant attire, it was always from a sense of duty rather than from taste. Toward the close of the century, however, one fashion entirely new to the period was set by the king,—the high boots of Russia leather, which were worn on all occasions, even for dancing. (*E*, Plate XVI.) It is said that the king introduced the fashion in compliment to one of his equerries. The few who did not wear boots were barred from polite society unless they wore silk stockings. Even in winter anything but silk was tabooed by the elite; but in order to secure a little warmth several pairs were worn, one over the other.

The general style of dress remained quite similar to that of the previous century. The long-waisted doublet and the quilted stuffed-out trunk-hose or breeches met no change

until the successors of Henry IV came to the throne. (*D*, Plate VIII.) The name "breeches" as applied to trousers is first used in the opening years of this century.

With woole, with flax, with hair also,  
To make their breeches wyde.

—*From an old ballad.*

During the court festivities of these early years the pendulum began to swing gradually, very gradually, toward greater and greater luxury.

In the reigns of Louis XIII and XIV we hear again the words of disapproval, and the edicts go forth, only, however, to be smiled upon and to vanish!

The boots introduced by Henry IV were worn by men of fashion throughout the period, but in 1625 they were reduced in height and the top increased to a great width, falling over the middle of the leg, displaying the silk stocking or boot-hose. (*A, F*, Plate XVII.)

Men's dress of this period had its origin no doubt in Flanders, and flourished about the time of the marriage of Louis XIII to Anne of Austria, a daughter of Phillip III of Spain. With the bringing of this new Spanish influence into France, the Italian styles introduced by Catharine de' Medici and Marguerite of Valois in the preceding century gave way to the *mode espagnole*.

The trunk-hose of the past were now replaced by trousers. The word is rather obscurely derived from the old French *trousser*, which meant to tie up, to tuck, or to gird. The coming of the short trousers marked a distinct departure in the garments of men. Usually they extended to the knee or a little below. They were made of linen, batiste, or well starched Holland cloth, and were often trimmed with edgings of lace, ruffles, and ribbon. These short trousers have passed into the annals of costume under the name of "rhingraves." (*A, F*, Plate XVII.) The name owes its origin to the Count of Salm, who bore the title of Rhingrave, and who introduced the short trousers into fashionable society in Paris.

These very fanciful trousers, the great topped boots, the shoulder cloak with the large cape collar, the broad brimmed hat with the drooping feather, and the sword dangling at his side, completed the dashing gallant of the period.

The beard which was worn pointed at this time was shortly reduced to a small tuft on the chin, and called the "imperial." (*A, F*, Plate XVII.) It is said that the style was inaugurated by the king, who in one of his eccentric moods had his principal gentleman attendant shaved, leaving the little tuft on the chin. Immediately the "royal beard," as it was dubbed, became the fashion.

The dress of the French gentleman of this period, contemporaneous with the reign of Charles I of England, was similar to the English fashions, and has been made familiar to the world in the works of the Flemish master, Sir Anthony van Dyck.

Among the ladies the farthingale still continued the fashion, though not in the extreme style of the preceding century. Now it resembled a large bell as it fell over the roundly padded hips. (*B, C*, Plate XVIII.) Three petticoats, each of a different color, were usually worn beneath the gown, and the lady, by assuming queer but elegant mannerisms in walking, managed to display all three. The

---

#### COLOR NOTATION—PLATE XVII

- A*—Rhingraves, P B  $\frac{1}{2}$ . Jacket, Y  $\frac{7}{8}$ . Waistcoat, collar, white. Ruffles, B G  $\frac{1}{4}$ . Mantle, Y  $\frac{1}{4}$ , Y R  $\frac{5}{8}$ , Y  $\frac{7}{8}$ , gold; lining, R  $\frac{5}{8}$ ; banding, gold. Hose, R  $\frac{5}{8}$ . Shoes, B G  $\frac{1}{4}$ . Points, B G  $\frac{1}{4}$ . Hat, B G  $\frac{1}{4}$ ; feather, white. Shoulder band, Y  $\frac{7}{8}$ , R  $\frac{5}{8}$ .
- B*—Overdress, bodice, P  $\frac{1}{4}$ . Vest, banding, Y  $\frac{7}{8}$ , Y R  $\frac{7}{8}$ ; lining, white. Underskirt, white; banding, Y  $\frac{7}{8}$ , Y R  $\frac{7}{8}$ , G  $\frac{5}{8}$ . Flowing sleeve, white. Head-dress, white. Fan, Y  $\frac{5}{8}$ , Y  $\frac{7}{8}$ .
- C*—Overdress, bodice, P B  $\frac{1}{2}$ . Bandings, Y  $\frac{7}{8}$ , Y R  $\frac{7}{8}$ , gold. Underskirt, R  $\frac{5}{8}$ . Gloves, Y R  $\frac{3}{4}$ . Fan, Y  $\frac{7}{8}$ .
- D*—Overdress, bodice, B G  $\frac{5}{8}$ , B G  $\frac{5}{8}$ . Underskirt, sleeves, Y R  $\frac{5}{8}$ . Collar, white. Bandings, Y  $\frac{7}{8}$ .
- E*—Overdress, bodice, R  $\frac{7}{8}$ ; bandings, Y  $\frac{7}{8}$ . Underdress, white; trimmings, Y  $\frac{7}{8}$ , Y R  $\frac{7}{8}$ . Fan, Y R  $\frac{5}{8}$ . Collar, cuffs, white.
- F*—Trousers, jacket, Y  $\frac{7}{8}$ , Y R  $\frac{5}{8}$ . Blouse, collar, cuffs, embroidery, white. Mantle, P B  $\frac{1}{2}$ ; lining, G  $\frac{5}{8}$ , banding, Y  $\frac{7}{8}$ , Y R  $\frac{5}{8}$ , gold. Boots, B G  $\frac{5}{8}$ . Hat, N 5; plume, white. Shoulder band, Y  $\frac{7}{8}$ , Y R  $\frac{5}{8}$ , gold. Ribbon bow, trimming on trousers, P B  $\frac{1}{2}$ .





A

B

C

E

D

F

## PLATE XVII—THE RENAISSANCE IN FRANCE—1600

A—1600—A lord of the court. Rhingraves or short trousers of fine linen, batiste or Holland cloth succeed the trunk-hose. The wide-topped boots, the cape of rich material and the plumed hat complete the costume of the dashing gallant of the day.

B—1694—A lady of the court wearing a gown of rich fabrics, trimmed with bands of gold lace, and the Fontange head-dress.

C, D—1668—Ladies of fashion carrying the long train of the overdress.

E—1600—This early dress resembles the types of 1595. The overdress is open in front displaying the beautiful underskirt.

F—1600—Cavalier wearing short, lace-trimmed trousers, turned-down boots, shoulder cape and plumed hat. The beard, the Imperial, was the popular fashion set by the king.

rigid corset still remained indispensable, and the bodice was also heavily boned and was carried down to a deep point at the waistline. Possibly to relieve the discomfort caused by the corset, the neck and shoulders were bared most liberally—in fact, to a degree termed “indecorous” by the clergy. Finally His Holiness, the Pope, interfered. The threat of excommunication, however, had little effect. Fashion still continued to wield her scepter as she chose.

Fans were adopted as a means of allaying the annoyance caused by the torturous stays. A lady was seldom seen without her fan. These were very beautiful and dainty adjuncts to the costume. Many were mounted in wood, ivory, mother-of-pearl, gold and silver. Toward the end of the century the trade in fans had increased to such a degree that the makers of fans formed themselves into guilds, similar to the guilds of other trades. In the seventeenth century there were more than five hundred manufacturers of fans in Paris.

The importance of the fan is set forth in this letter written at a later period by Mme. de Staël to a friend:

Let us picture to ourselves a most charming woman, splendidly dressed, graceful and gracious to the highest degree; yet if with all these advantages she manages her fan in a bourgeoisie way, she may at any moment become a laughing stock. There are so many ways of playing with that precious appendage that by a mere movement

---

#### COLOR NOTATION—PLATE XVIII

- A*—Coat, R  $\frac{1}{2}$ . Cravat, white. Hat, P B  $\frac{1}{2}$ ; feather, P B  $\frac{1}{2}$ , P B  $\frac{1}{2}$ . Hose, R  $\frac{1}{2}$ . Shoes, Y  $\frac{1}{2}$ . Band on sleeve, gold. Muff, Y R  $\frac{1}{2}$ .  
*B*—Dress and bodice, B  $\frac{1}{4}$ . Puffs in sleeve, corsage, Y R  $\frac{1}{4}$ . Collar, cuffs, trimming on sleeve, white. Ribbon in hair, B  $\frac{1}{4}$ . Head-dress, Y  $\frac{1}{2}$ . Recticule, Y R  $\frac{1}{2}$ , Y R  $\frac{1}{2}$ .  
*C*—Overdress, bodice, brocade, R P  $\frac{1}{2}$ , R P  $\frac{1}{2}$ . Banding and vest, Y  $\frac{1}{2}$ , Y  $\frac{1}{2}$ , Y R  $\frac{1}{2}$ . Puffs on sleeve, P B  $\frac{1}{2}$ . Underdress, P B  $\frac{1}{2}$ . Head-dress, R P  $\frac{1}{2}$ . Veil, white. Fan,  $\frac{1}{2}$ .  
*D*—Doublet, hose, Y R  $\frac{1}{2}$ , Y R  $\frac{1}{4}$ . Hat, Y R  $\frac{1}{4}$ . Shoes, Y R  $\frac{1}{4}$ . Ruff, white. Belt, Y R  $\frac{1}{4}$ , gold. Insignia, gold, white center; ribbon, B  $\frac{1}{2}$ .  
*E*—Trousers, Y  $\frac{1}{2}$ . Doublet, ruff, white. Jacket, G Y  $\frac{1}{2}$ ; belt, Y  $\frac{1}{2}$ . Hose, B G  $\frac{1}{4}$ ; points, Y  $\frac{1}{4}$ ; shoes, N 5. Hat, Y  $\frac{1}{2}$ .  
*F*—Dress, B G  $\frac{1}{4}$ . Cape, B  $\frac{1}{4}$ ; fur, Y  $\frac{1}{2}$ . Collar, cap, white.



A B C D E F

## PLATE XVIII—THE RENAISSANCE IN FRANCE—1600

- A—1695—A courtier carrying the muff. The long coat succeeded the doublet and the cravat took the place of the ruff and broad collar.
- B—1650—A lady of the court. The falling collar and turned-back cuffs continued through the century.
- C—1614—A lady of rank. The boned bodice with slashed peplum was fashionable in the garments of both men and women.
- D—1600—Costume worn by Henry IV. The short-waisted doublet with peplum corresponds with the fashion in women's dress.
- E—1600—A citizen wearing the knee-breeches fastened with points, and the short jacket with ruff and cuffs.
- F—1600—A woman wearing the simple flowing gown with the little shoulder cape, which gradually grew into the modern tippet.



of the fan one can tell a princess from a countess, a marchioness from a plebeian. And then it imparts such gracefulness to those who know how to manage it: twirling, closing, spreading, rising, or falling according to circumstances.

Sleeves were large, and were confined at the wrists with cuffs. Over the sleeve proper a second sleeve, caught at the shoulder and cuff, but remaining open and showing the real sleeve, was sometimes worn. The second sleeve was often decorated with rows of buttons, but only as ornament; they served no useful purpose.



Fig. 31. Chopines. They were adopted by fashionable women to make them appear taller.

Venetian and Florentine laces were much admired at this period. The wired ruffs and collars of these exquisite laces emphasized the line and whiteness of the shoulders and neck, as well as the delicately beautiful work of the needle. So great was the demand for these foreign laces and so much French gold was going into the coffers of other nations that their importation was forbidden.

Then it was that quantities of ribbon, in lieu of lace, profusely adorned the skirts, bodice, sleeves, and hair of the women, as well as ornamented the dress of the gay cavalier. Loops of ribbon, rosettes of ribbon, yes, garlands of ribbon bedecked the costume.

Added to this extravagant use of ribbon was a great love of jewelry. Necklaces of diamonds, strings of pearls, and colored glass mounted as jewels, which were made by a clever French artisan, were in great demand. The queen is said to have worn on one occasion a gown with thirty-two thousand pearls and three thousand diamonds, and of course the queen's example was followed by all the lesser lights of the court and by those just outside the charmed circle. Added to this was the taste for the richest kinds of materials, garments of brocade, satin, and exquisite damask. Though the long flowing gowns largely concealed



the shoes and stockings, still a love of bright color displayed itself even here. Silk stockings of scarlet, apple-green, and light blue were the common quest. The shoes or slippers were equally gay, being of blue, red, violet, or yellow satin, with very high heels. In fact, heels of eight centimeters were considered quite ordinary. This extreme brought forth much lively comment.

Tall Lise *will* be, despite her nature.

—REGNARD.

For outdoor wear velvet clogs or pattens with thick cork soles were slipped on over the high-heeled shoes. The chopines, introduced into Italy and thence into France from Turkey, and eagerly adopted by the fashionable, no doubt called forth much similar satire. (Fig. 31.)

You will have clumsy actresses,  
Half woman and half patten.

—VOLTAIRE.

But just think of their pattens,  
Which raise them half a foot.

FRANÇOIS COLETET, *Les Traces de Paris*.

There were gloves for all occasions, the various styles being named after the perfumes with which they were scented, or after the royal lady whose fine skill invented the perfume. There were *gants de Neroli*, after the Princess Neroli whose perfume was in high favor; *gants à la Frangipaire*, after a Roman nobleman whose similar invention had won him distinction; then there were the gloves *à l'occasion*, *à la nécessité*, and *à la Phyllis*. Many of these were very elegant, the back and gauntlets often ornamented with embroidery.

Perhaps the most expensive article which demanded a real sacrifice to do without and to which very few were equal was the girdle or sash of silk, which was decorated with silver plates or discs, chased or designed in enamel. To these belts were often hung keys, purses, and various gewgaws.

Of all the frailties of feminine vanity, one of the most unusual made its appearance during the reign of Louis XIII. The wearing of patches certainly was a novelty! A patch was simply a bit of black silk court plaster given an advantageous position near the mouth, upon the chin, or near the eye to increase its luster. The dark patch was believed to enhance, by contrast, the fairness of the skin. It is said that patches were first prescribed as a remedy for headache, but retained as an aid to beauty. (B. Plate XVII.) Every lady carried the little patch-box, which was also supplied with a mirror; and indeed it was no unusual sight to see a fair damsel upon the public promenade calmly adjust a patch or two.

Again the masks were in vogue and their popularity had greatly increased. To conceal one's features behind a mask may hide beauty or it may not, but the element of mystery has its charm.

A caprice new to the period, however, was the affection bestowed upon the muff and the little muff-dog. The muff was small, and the dog, even more diminutive, was carried within its cozy depths. The lap-dog was indispensable to the correct appearance of the fashionable lady. To caress the little head protruding from the muff, feed it dainty bits of cake and sweets and lavish upon it endearing phrases, constituted the lofty aim of the fashionable lady. The grace and artful manner in which these marks of affection were bestowed established the degree of refinement and taste of this fair daughter of Eve. In the *Book of Addresses* for 1692, the Demoiselle Guérin, Rue de Bac, Paris, is given as the approved shop for the making of muffs especially for this purpose.

The first muff bearing any resemblance to that now familiar to us is seen in a satirical engraving by Jasper Isaac, entitled *L'Ecuyer à la Mode*, and signed 1634. This is a cylinder of silk or some other material, not fur, trimmed on each end with bands of thick white fur. It is in the precious engravings of Hollar, Abraham Bosse, Arnould,

Mandraft, Boumar, and Trouvain, that we may readily note the authentic birth of the muff.

Middle class women who could not spend more than fifteen or twenty francs for this luxury used muffs made of cat skin or dog skin. In the latter part of the century sable was the favorite fur among the court belles.

It is not surprising that with all these frailties and follies becoming so pronounced another storm of disapproval was heard. The stern edicts of Richelieu came forth about 1633. The ban was placed on all the elegancies of fashion. Gold lace, fringes, lace work enriched with gold or silver, were prohibited throughout the country.

The lack of these rich materials necessarily made a change in the dress. There was now no overloading with ornaments or laces; in fact, nothing to suggest the extreme. The skirt began to fall in large simple folds to the floor; the farthingale became passé; the large ruff was succeeded by a band or collar fitting under the chin. In fact, the dress became serious, almost to the point of severity, but not for long.

France ever smiles and shrugs her shoulders over edicts. The fair ladies of France now take this modest costume "according to edict" and transform it into one more elegant and more charming than any their artful hands had yet devised, and one which, with slight changes, was destined to play a distinguished role in the brilliant court of Louis XIV.

With the advent of Louis XIV fashion evolved into a point of etiquette, with the king as sole arbiter. Paris became the acknowledged center and home of fashion and taste. Several influences conspired to bring this about at this time. Chief among these was the understanding and appreciation of the importance of industry on the part of Colbert, the able Prime Minister of Louis XIV. Through his influence a great forward movement took place in all the industries. It was at this time that lace-making in France reached its highest development. The discovery of a route to the East around the Cape of Good Hope was a

second direct cause. The French trade in silks, no longer dominated by Italian merchants, now dealt directly with Asiatic ports. Consequently Italian taste, which had formerly exerted a marked influence on the dress of France, was more and more ignored in French design. The beautiful gardens which were being built, supplying motifs of design, were of far reaching importance. The high position of artists was an inspiration to excellence. All of these factors, combined with the taste of Louis and the court queens, had a share in the establishment of Paris as the acknowledged fashion center. The court followed every dictate, and the bourgeoisie followed the example set higher up. Each endeavored to outshine the other in the richness of his dress or in the individual eccentricities which might be added to complete the costume. One fashion was scarcely born when another appeared upon its heels. Never in the past had fashion reached such unlimited extravagance. Of course the king issued edicts, but on the other hand encouraged extravagance by his own example.

It was some ten years previous to this (1660) that the periwig, which has since claimed a place for itself in the history of costume, made its initial bow to the Parisian world.

A very pretty story is told of its origin. When Louis XIV was a child his beautiful and abundant locks of hair, which hung in great waving masses over his shoulders, won the admiration of all. One day his courtiers, by way of compliment, had heads of false hair made to resemble the king's natural locks. When the king grew to manhood, as a return compliment he adopted the peruke, and by so doing set the mode for some years to come.

Now the simple costume worn at the close of the previous reign takes on unbounded elegance. The full straight skirt is made of richest materials, either silk or satin, trimmed with bands of plaiting or puffs of gold lace; over this is a voluminous second skirt, open in front and trailing in great folds behind. (*B, C, D, E*, Plate XVII.) The length of the train was decided entirely by the prestige of



the wearer. The queen's train measured nine ells;<sup>1</sup> those of the king's daughters, seven; other princesses', five; and that of a duchess, three. The imposing train was usually carried in graceful style over the left arm.

The bodice was fitted and quite snug, and the front ended as before in the long point, which, however, gradually grew shorter. Dainty bits of gimp, chenille, and ribbon adorned the bodice, and these bits of trimming when placed in tiers at each side of the bodice were called "ladders." The sleeves became close-fitting, and were finished with ruffles of fine lace or other dainty material.

Men tailors were patronized in this century, as in the past, by these leaders of fashion.

At this period the silk worm was introduced into France, and silk of all kinds was manufactured at Lyons.

The taste for fine laces also led to the establishment of home manufactories. The very ordinary kinds which were produced in Lyons, Normandy, and Auvergne no longer satisfied the popular taste, and manufactories of the finer sorts were established at Valenciennes, Havre, Lille, Dieppe, LePuy, and the Bois de Boulogne. The most exquisite of the laces naturally could be purchased only by the women of wealth; those of lesser means were quite content with a lace called *gueuse* or *neigeuse*.

Later "transparents" became the fashion. These were dresses of the finest gold or azure brocade, worn under a transparent black gown of lace. The shimmer of gold and black was the desired effect at this period of French elegance. "Have you heard of transparents?" writes Mme. de Sevigne. "They are complete dresses of the very finest gold or azure brocade, and over them is worn a transparent black gown of beautiful English lace, or of chenille velvet, like that winter lace that you saw. They form a "transparent," which is a black dress with a gold, silver, or colored dress just as one likes, and this is fashion."

The present Jardin des Plantes is the outgrowth of the

---

<sup>1</sup>Ell—About 1½ yds.

work of a clever horticulturist who here cultivated all sorts of foreign as well as domestic plants with the view of supplying designers with ideas for these embroidered and brocaded materials.

During the early years of the century the arrangement of the hair led to the innovation of many pretty styles. In one, *à la Ninon*, the hair was parted in the middle and allowed to fall in loose ringlets to the shoulders, sometimes partly concealed by a transparent white veil. (C, Plate XVII.) When the hair was arranged *à la garçon*, a horizontal parting was made along the forehead and a few loose curls fell over the brow. Later, the hair was cut short and curled. Long ringlets, called *moustaches des dames*, were adjusted by pin or ribbon to the sides of the head, and fell over the ears to the shoulders and even below. This style developed into a taste for wigs and curls and what-nots of the wig-maker's art.

Soon after the year 1645 a rather venturesome Frenchman contrived to establish a reputation as a lady's hair-dresser. Previous to this a lady's hair had usually been dressed by her own maid. He was successful, however, only for a time; his daring getting the better of his wisdom, his clientele became gradually less. His successor, one Mme. Martin, brought into being the popular fashion of wearing the hair in several rows of short curls. This style was immediately adopted by Mme. Maintenon, and became the popular mode—*à la Maintenon*.

Later a mere chance precipitated a new style of head-dress which was destined to play a conspicuous part in the closing days of the century. During one of the royal hunting parties at which the Duchess of Fontanges, a favorite of the king, was present, the fair lady displayed her rare ingenuity. A gust of wind suddenly and without warning carried off the Duchess' hat; but, nothing daunted, she gathered up her disordered locks and confined them by tying her ribbon garter around her head. The entire party was enchanted with the result, and the next day every one appeared with the head-dress arranged *à la Fontanges*.

The inspiration of the Duchess had become the aspiration of the followers of fashion, and the *à la Fontanges* prevailed for years with many variations. (*B*, Plate XVII.) In the end it became an intricate structure of wire about two feet high, upon which were mounted in successive tiers ribbons, laces, and flowers, each part of the unusual conceit having a distinctive name.

A stockade of wire  
Supports the superb structure  
Of the lofty head-dress;  
Even as in time of calm upon the sea  
A vessel bears its mast.

—*From the French.*

The king frowned upon all these eccentricities, and continued to frown, for they were not given up until the early part of the next century.

The various arrangements of the hair kept coming and going, and since the hair itself was much lower, high ruffs went out and were succeeded by large flat collars of lace and embroidery, which fell very low over the shoulders and arms. (*B*, *C*, Plate XVIII; *F*, Plate XVII.) The cuffs which matched the collars were very large, sometimes extending from the wrist to the elbow. This fashion of the large flat collar and cuffs lasted until 1672, when it entirely disappeared.

The little shoulder cape or *palattrie* (called *pelerine* by the English, but in fact the very modern tippet) was introduced at this time. (*F*, Plate XVIII.) The extremely low-cut bodice, which was worn during court functions and for full dress, caused the Princess Palatine, Charlotte of Bavaria, daughter of the Elector Palatine, to introduce the fashion to avoid the immodest exposure of the shoulders. The short capes were usually made of gauze or lace in summer, and of fur in winter.

About this time, 1670, a decided change is noticeable in the costume of the French gentleman—a change which subsequently took place in all countries looking to France as the center of fashion. The doublet gave way to the coat

and waistcoat, each descending to the knees and fastened all the way down. (*A*, Plate XVIII.) Silver brocade was now used only for the waistcoat, while the coat proper was made of less costly stuffs—cloth, poplin, and camlet. The only decoration of the coat was a large bunch of ribbon on the right shoulder. Further, the cravat of lace or linen, tied at the neck with a bow of ribbon, took the place of the large falling collar.

This new cravat was inaugurated after the battle of Steinkirk, which took place in 1697. It is said that the French officers, taken by surprise had no time to prepare an elaborate toilette, but simply threw their cravats about their necks and rushed out to meet the English. After that the “Steinkirk” tie was adopted by both men and women of the fashionable world. (*A*, Plate XVIII.)

Swords were now worn only by those who were properly qualified; they were carried in broad baldricks fringed with silk. The baldricks were partly covered by scarves or sashes which were worn about the waist.

During 1668 the muff made its appearance in the costume of gentlemen, being suspended by a ribbon about the neck. (*A*, Plate XVIII.) In the priceless old prints of St. Jean and Bonnard we have preserved to us the French gentleman under Louis XIV carrying his huge muff with all the graceful languor befitting a leader of fashion. Never before in history had the taste for furs been so lavishly displayed as in this and the succeeding century. It was in this century that the art and craft movement of the Middle Ages attained its highest development. Designers of jewelry and textiles abounded. Manufactured articles from the various countries were being sent over all the world. It became easy for the craftsman of this day to execute many and new designs, since he had access to the silks and ornaments of the Orient, the laces of Brussels and Venice, the textiles from Spain, and the well made articles from England and Germany. Ideas from all these sources were combined and elaborated. The use of vases, crowns and animals became common. Cupids, the horn of



plenty, and garlands of flowers were combined with many streamers and bows of ribbon. Wreaths, and festoons of foliage looped with cord and tassel, were among the interesting details of design.

Toward the end of the century, besides the reigning belles of Versailles, Mme. de Fontanges, Mme. Maintenon, and Mlle. de la Vallière, the stars of the Paris stage were becoming an influence in the fashion world. Little eccentricities of the popular singers of the day were quickly caught and copied. At one time the king presented Mlle. de Brie and Mme. Molière with mantles which they wore in the comedy *Sicilien*. This recognition by the king was an added reason for the popularity of the belles of the stage.

The long clinging robe, without the suggestion of a plait, a style designed by Mme. Molière, and one which revealed the lines of the figure to advantage, was looked upon with high approval by the leaders of fashion.

Thus the seventeenth century wore on in a pomp and splendor which was not confined to the limited circle of court leaders and those of distinguished rank, but extended to that of lesser folk as well. In fact, dress was scarcely any longer an index of rank; the cook wore her laces with the dignity of a countess, and the tailor donned the attire of the gentleman of the court. It is further said that in going to church these gentle dames borrowed a lackey to carry the train of their gowns. A poet of the day voiced his satire in the following lines:

No longer are our ladies to be distinguished  
From the women of the people;  
Since a person of honor  
Wears a colored petticoat  
Or changes the fashion of her clothes,  
In short, since she dresses herself  
In a gaudy manner.  
A bourgeoisie does as much as that;  
She, too, will put on plumes  
And stick in moustaches,  
False hair and pads,  
"Tours," plaits and knots;

White and yellow coifs,  
With ells of lawn in them,  
And those fine striped silks  
Which are sometimes not paid for;  
For often such bravery of dress  
Hides much roguery.

—From the French.

The Renaissance (1500-1700) is known as the age of extreme styles. It must be admitted that the costumes lacked the grace of the long flowing line of the classic period, and that the figure, hampered in steel and bone, had little opportunity to display its natural artistic proportion and line. Nevertheless the beautiful textiles of rare color, heavy brocades, satins, and velvets, the fine linens, the rarest of laces, and strings of pearls and ornament produced a mass of richness and color imparting to the costume an air of grandeur unequaled in any other age.



## CHAPTER IX

### FRENCH COSTUME (1700)

**I**N THE opening years of the new century, the brilliant reign of Louis XIV takes on a strangely somber hue. In marked contrast to the gaiety of former years, the tone becomes heavy and dull. The king repented of the follies of his youth, and now resigned himself to the spiritual direction of Mme. Maintenon, whom he secretly married in 1685.

Extravagance in all lines was given up. Stuffs were of one color; lace was restricted to the cravat and ruffles; buttons succeeded points; and ribbon, which was now limited to shoulder knots and cockades, finally disappeared altogether. The trouser was superceded by short tight breeches; in fact everything was reduced in size except coat sleeves, coat skirts, and wigs. The skirts of the coats were stiffened with wire or other material to make them sufficiently bouffant, being a fit companion for the monstrous panier. (*A*, Plate XIX.) The wig had immensely increased in length and descended almost to the waist. In 1705 the wig was powdered white, and not only the wig but the shoulders as well. The long queue was turned under and tied, and known as the "club."

The making of a wig, or peruke, demanded the greatest skill and moreover a fine artistic sense. Those who excelled in this particular line were called *perruquiers*. They had their academy and were considered artists. The wigs they produced were marvelous and of great value.

Colbert, the French statesman and financier, was highly indignant over such extravagance and tried to initiate a change of fashion. Fashion, however, was not quite ready to follow the dictate of a mere statesman.

Things wore on thus until, toward the close of his reign, Louis suddenly tired of his own moroseness and the melancholy tone of his court and besought the fine ladies and gentlemen to restore the gaiety of former years. The response was instantaneous. Immediately the beautiful gowns reappeared, the *fontange* was again the mode, skirts were elaborately trimmed, and even the lineal descendant of the farthingale peeped its head above the opening years of the new century in the guise of the hoop.

The new trimmings for the skirt were called *falbalas* (anglicised, "furbelows") and *pretintailles*. The *falbalas*, though known in ancient times, were flounces of plaited silk or lace, and were the invention of one M. de Langlee, son of a waiting maid to the queen, who gave it the more modern name. This youth, through the queen's favoritism, had become the oracle of fashion to the French world. The *pretintailles* were cut-out patterns laid on the dress, making it resemble a piece of upholstery. This style led to the revival of brocaded stuffs of gold and silk.

A woman in *pretintaille* and *fontange*  
 Thinks herself as beautiful as an angel;  
 But this vain *falbala* by its vast size,  
 Makes her as big as a tower;  
 And all this set-out inflates and stuffs her up,  
 Until she resembles a fat turkey.

—Lines printed under a caricature of the period.

The outer skirt, cotillon, of the previous years was now trussed up behind, and a shaped form of gummed material was placed under the skirt to give it greater amplitude.

#### COLOR NOTATION—PLATE XIX

- A*—Coat, B G  $\frac{3}{4}$ , Y  $\frac{3}{4}$ , gold. Waistcoat, B G  $\frac{3}{4}$ , white, gold. Cravat, white; tie, black. Hose, B G  $\frac{3}{4}$ . Shoes, black; buckles, gold. Hat, black; plume, white.
- B*—Sacque, R  $\frac{3}{4}$ ; dot, black; ribbon, B  $\frac{3}{4}$ . Cap, white; ribbon, B  $\frac{3}{4}$ .
- C*—Skirt, Y  $\frac{3}{4}$ ; bodice and panier, Y  $\frac{3}{4}$ . Front of bodice, Y  $\frac{3}{4}$ ; ribbon and trim, B  $\frac{3}{4}$ .
- D*—Costume, white; design, R  $\frac{3}{4}$ , G  $\frac{3}{4}$ . Front of bodice, white; ribbon, R  $\frac{3}{4}$ . Muff, R  $\frac{3}{4}$ .
- E*—Trousers, black. Coat, Y R  $\frac{3}{4}$ . Waistcoat, Y  $\frac{3}{4}$ . Cravat and hose, white. Hat, black. Shoes, black; buckles, metal.





A

B

C

D

E

## PLATE XIX—FRENCH COSTUME—1700

A—1750—A man of rank wearing the fitted coat with extended coat-skirt. The hat, cravat and buckled shoes are characteristic of the century.

B—1760—The watteau sacque worn over the hoop.

C—1760—A variation of the hooped costume showing the draped panier and boned bodice.

D—1720—The hooped costume showing a popular trimming of the period. The little wired hood and diminutive muff were favorite accessories of dress.

E—1700—A citizen of France wearing the long coat, the waistcoat and ruffled cravat. The knee-trousers, hose and buckled shoes were worn well on toward the end of the century.

The noise made by the stiffened linen in walking, or when touched ever so lightly gave them the name of *criarde*.<sup>1</sup> The *criarde*, as did the farthingale, gave the appearance of added slimness to the waist. Above all else, the waist must be diminutive. (Plate XX.) Consequently, it is not surprising that the hoop or panier soon made its bow to the French world.

With the passing of Louis XIV in 1715, Mme. Maintenon retired to St. Cyr, where she founded a school for the education of poor girls of good families. Thus the influence which had caused the temporary lull in the brilliancy of court life passed away. Now Paris was again fully astir, and the most lavish display reigned not only in the palaces of the king, but in the salons of the bourgeoisie as well. Thus the regency began under the Duke of Orleans.

The fashions during the regency and the reign of Louis XV are so similar that it is almost impossible to mark the point of transition (1715-1774). Both lived under the motto "All for pleasure"; the realm of fashion was ruled entirely by the ladies of the court. Mme. Pompadour and Mme. du Barry were the favorites of Louis XV. They wielded the scepter of fashion this way and that, following the dictates of their own capricious fancy. It was Pompadour who set the fashion for gowns of pronounced stripes, and the dainty flowered silks which have become associated with her name.

---

<sup>1</sup>Criard—noisy fellow.

#### COLOR NOTATION—PLATE XX

- A—Dress, B G  $\frac{1}{4}$ ; banding, stripes, B G  $\frac{2}{3}$ . Hat, B G  $\frac{2}{3}$ ; ribbon, R  $\frac{1}{4}$ . Kerchief, white; dots, R  $\frac{1}{4}$ .
- B—Skirt, B G  $\frac{1}{2}$ ; flounces and puffings, white. Overdress, Y R  $\frac{7}{8}$ ; puffings, white; ribbon bow, B G  $\frac{1}{2}$ . Hat, white; plumes, white; flowers, R  $\frac{1}{2}$ , B G  $\frac{1}{2}$ . Stocking, white. Shoes, R  $\frac{1}{2}$ .
- C—Dress, P B  $\frac{1}{4}$ , P B  $\frac{1}{4}$ . Scarf, Y  $\frac{1}{4}$ ; design, R  $\frac{1}{2}$ . Bonnet, Y  $\frac{1}{4}$ ; ribbons, R  $\frac{1}{2}$ .
- D—Skirt, B  $\frac{1}{4}$ ; flounce and puffing, white. Corsage bow, R  $\frac{1}{2}$ . Upper bodice (shoulder to bust), white. Bow at neck, white. Ribbon in hair, R  $\frac{1}{2}$ ; plumes, white. Stockings, white. Shoes, R  $\frac{1}{2}$ .
- E—Overdress, bodice, B G  $\frac{2}{3}$ ; trimming and puffs on sleeve, white. Underskirt, Y  $\frac{7}{8}$ ; flounce, white; ribbon, white; trimming, G  $\frac{1}{2}$ . Hat, Y  $\frac{1}{2}$ ; trimming, B G  $\frac{2}{3}$ ; flower, R  $\frac{1}{4}$ , G  $\frac{1}{2}$ . Fan, white, B G  $\frac{2}{3}$ .



A

B

C

D

E

## PLATE XX—FRENCH COSTUME—1700

- A—1790—A lady of rank, wearing the fitted jacket, the shoulder scarf and the tall crowned hat—a costume brought in by the approaching Revolution and termed “masculine” or “British.”
- B—1780—A lady of the court. The short hooped skirt, the trailing overdress and the towering head-dress mark the reign of Marie Antoinette.
- C—1789—The days of the Revolution brought in more simple styles. The waist became short, and the long scarf was invariably worn about the shoulders.
- D—1780—A type of short dress made fashionable by Marie Antoinette during her days of farming at the Petit Trianon. A crook was often carried with this costume.
- E—1760—An elaborate panier costume with stiffly boned bodice.



The farthingale had made its reappearance in the new guise of hoop and panier in 1711. (Plates XIX, XX.) The panier derived its name from its resemblance to a large basket, being a framework constructed of hoop, reed, or whalebone, held together with cord and tape. The real origin of the panier is quite obscure. It is believed by some that the farthingale had probably survived in some obscure German village, and was carried to England in the time of Queen Anne; here it was adopted by the English ladies, who in turn introduced it into France. M. Quicherat tells an amusing incident relative to the popularity of the hoop-skirt in France:

Some unusually stout women had ordered petticoats made for them mounted on hoops. These were intended for the privacy of the ladies' own apartments. One summer evening, however, without a change of attire they were led to risk a stroll in the gardens of the Tuilleries. As soon as the pair approached, they were surrounded by the curious crowd. Both men and women, eager in their curiosity, pressed upon them from all sides, until the venturesome dames were rescued by a gallant officer of the court. The women reached home, deeply humiliated and believing they had been hopelessly scandalized by the incident. On the morrow, however, they were amazed to discover that they had set a new fashion, not only to the court but to the city as well!

The first paniers were simply the large hoops bound together with tape, and known as *paniers à guéridon*. (B, D, Plate XIX.) Those of a second style were given the form of arches springing from the waist, and were called *paniers à coudes* because the wearer could rest her elbows upon them. (Fig. 32; B, D, E, Plate XX.) This is the type with which our modern idea of panier is always associated. Its outstanding feature is the width of the sides and the flatness of the front and back. The wide swinging paniers became the last word in fashion and attained the most extravagant dimensions. They continued to grow until they reached a breadth of six feet, their circumference being eighteen. The largest boxes at the theater could accommodate only three ladies; as they rode through the avenues of Paris, their skirts extended from each side of the carriage.



The unprecedented demand for whalebone in the construction of paniers became a source of great revenue to Holland. Coopers and basket-makers alike undertook the manufacture of paniers; their prices became the ruin of homes, and their use the misery of pedestrians.



Fig. 32. *Paniers à coudes*

The story is told of a French youth who saw two ladies approaching, dressed in the latest breadth of panier. He understood the situation at a glance; it was necessary for him either to turn back or leave the path, neither of which he cared to do. When the ladies drew nearer and were within a few feet of him, he deftly turned a handspring which landed him over and beyond them. He then nonchalantly pursued his way.

Throughout the history of French fashions such extremes have always led to the same end. War is declared against the panier! The anathemas of the clergy were hurled against paniers, the venom of the press assailed them, and the ridicule of the scholarly world was heaped upon them. Churchly authority, argument, and ridicule

were alike powerless. Again Paris smiled and shrugged her shoulders.

A pamphlet published in Paris in 1725, entitled *Indignité et Extravagance des Paniers pour des Femmes Sensées et Chrétiennes*, contained the following:

But I wish to know, ladies, by what evil genius you are possessed, and what can be your opinion of us, that you endeavor when in such deplorable case to pass yourselves off to us and to the eyes of the Christian world as spiritual and devout persons, while you are laden with an immense and superb panier, that takes up the room of at least six persons, and is the miserable cause of the inconvenience you experience in passing along, having to hold your panier in both hands and displaying wooden hoops under an arrogant and splendid skirt. Is it not the said panier that makes your carriages groan and that bulges through them like the sails of a ship, while you are holding your noble wooden heap in both hands, and displaying it beneath a costume that is a scandal to the church and a laughing stock to the whole world, and that insults the magnificence of our altars by its audacious splendor?

Voltaire's disapproval was voiced in the following satirical lines:

After dinner, the indolent Glycera  
Goes out, just for the sake of going out, having nothing to do.  
Her insipidity is deposited in a chariot  
Wherein her tightened body groans under the trammels  
Of a heavy panier which protrudes from the two windows.

The charming and graceful fashion which we have named "watteau" after the painter of French gallantry was now combined with the panier (1730). (*B*, Plate XIX.) The gown sometimes fitted to the waist only in the front, and the back hung from the shoulders over the wide-spreading panier, falling to the floor in easy folds. For the watteau costumes, silks and brocades were used; also many of the lighter materials—lawn, dimity, muslin, and flowered stuffs of bouquet pattern and vines. The sleeves were close-fitting and finished with billows of lace.

The leading actresses of the day did their part in making the panier popular. Mlle. Jancourt played the part of Galatea in *Pygmalion* and wore a costume which had been presented to her by Mme. Pompadour—a polonaise

with paniers, satin slippers, and a huge pouf ornamented with green leaves and surmounted with three ostrich feathers.

It is to the French actresses, Mlles. Clarin and Hus of the *Comédie Française*, that the press and the clergy are both indebted for the disappearance of the panier. Shortly after this a little book was published entitled *Les Paniers supprimés au Théâtre*. The ladies of high rank began to follow the example set by the two actresses and the hoops became passé.

Then it was that we heard more of the corset, and the women gave up the one folly for the other.

Is there anything more beautiful than a corset,  
Which naturally defines the figure,  
And shows how one is made  
In the mould of nature?

—*From the French.*

Toward the middle of the century the daintily colored cambrics which had been imported from India and Persia became fashionable. In fact the cambric gown took precedence over the gown of silk. At this same period, (1759) a print manufactory had been established at Jouy just outside Versailles. Soon this industry was putting out cambric prints quite as beautiful as those imported from the East. When this was discovered by the court leaders, Jouy prints immediately became the fashion. They were soon adopted by the great mass of the people and continued to be worn for many years.

The scarf or mantilla, (borrowed from the Spanish *mantilla*), of silk or satin, was worn about the shoulders or thrown over the head and the ends tied loosely in front. This was a continuation of the formal style of head-dress set by Mme. Maintenon. In winter a full mantle or cape was worn, sometimes lined with fur and buttoned all the way down the front. The hood, *bagnolette*, was held out from the face by means of wire. Later the little wired hood became the fashionable all-season head-dress. (*D*, Plate XIX.)

Again head-dresses began to grow high. They were raised about the forehead, arranged in bows and rolls mingled with ribbon, feathers, and jewels, and finally given the supreme finish, a thick covering of powder. Mme. de Graffigny, a French writer, protested against these high head-dresses, and preferred to wear her own hair close to the head, powdered and covered with a small cap. This little cap was adopted by many leaders of fashion and was worn for years by all French women.

The great ambition of the ladies of this period was to have not only small waists, but the smallest possible shoes. The heels were still very high and the jeweled and enameled buckles were in popular favor.

Among the small necessities of the complete toilette were necklaces, tablets set in chased gold, crosses of gold filigree, and the little bags or reticules.

Patches, paint, and powder were still the final touch to the *toilette française*. The patches were of various shapes, and given as many different names. The "coquette" was placed on the lips, the "gallant" in the middle of the cheek, the "impassioned" patch at the corner of the eye, and the "rougish" on the nose. Sharp criticism arose over the wide-spread fashion of patches, and the great court preacher, Massillon, delivered sermon after sermon in which he vehemently anathematized patches. Strangely, however, more patches than ever were worn, and further they were now dignified by the name *mouches de Massillon*, (spots of Massillon). Could it be that the ladies themselves were indulging in sarcasm!

Powder, a starch pulverized and scented, was used until 1760, when it disappeared for a time. It returned, however, in 1780, and after the Revolution it reappeared under the Directory in 1795.

Lady Mary Wortley Montague who visited Paris at this time gives an interesting impression of the French leaders of fashion:

Their woolly white hair and fiery faces make them look more like skinned sheep than human beings.



From the time of Louis XIV fans were indispensable. With their mounts beautifully carved in mother-of-pearl and ivory, they still continued to rule the feminine world.

Toward the end of the reign of Louis XV the first Indian or Cashmere shawl was imported into France.

In 1725-1775 the same general lines of the gown continued. The best period of the Louis Quinze costume was between the exaggeration of the Regency and the accession of Louis XVI, in 1774—the reign of the beautiful and artistic Mme. Pompadour.

To appreciate the charm of the period we have only to call to mind the canvases of the French painters of the day.

With the accession of Louis XVI a new Queen of Fashion, Marie Antoinette, rules in the realm of dress. Thus each goddess has her little day only to be succeeded by the next.

The *watteau* and *panier* continued with slight variations. The new queen did not venture to make a decided change in the mode of dress, but directed all the energy of her artistic nature to that marvelous invention of the eighteenth century, the head-dress, with which the name of Marie Antoinette is inseparably connected. The mere whim of the artful queen turned the head of a fair lady into the most wonderful landscapes, into sea pieces, and into towering pyramids. Little cardboard figures of men, women, and children were added to complete this absurdity, and women were proud to wear the freakish novelties devised at court.

Mlle. Rose Bertin, who next to the queen was arbiter of taste at the French court, became famous throughout Europe for her marvelous constructions in head-gear. Her name, as well as that of the queen, is historically associated with these monstrosities of the eighteenth century.



Fig. 33. Head-dress à la Belle Poule (After Robida)

Imagine a hedgehog lying upon the head! And more, considered beautiful! The *herisson*, or hedgehog style as it was called, consisted in frizzing and tangling the hair from the tips to the roots. This was carried up very high and was encircled by a ribbon to keep it in place. Later it was reduced to a *demi-herisson*, or half-hedgehog.



Fig. 34. *Pouf au sentiment*  
(After Robida)

One of the most amazing of all these fantastic creations was the coiffure à la *Belle Poule*, which became fashionable at the time the frigate "La Belle Poule" was victorious over the English ship the "Arethusa." Upon the sea of waving hair rested the ship in full sail—all its masts, guns, and sailors complete. (Fig. 33.)

Ridiculous names were given to these inventions of the queen and of others who strove to surpass her. There was the "English Garden," "The Forest," "Enameled Meadows," "Spaniel's Ear," "The Ingenuous Maiden," "The Councilor's Wife," "The Royal Bird," "Mad Dog," and many others. The comet of 1773 was the suggestion for a new head-dress. Contemporary with its appearance, the "Comet" became the rage, with flame colored ribbons the conspicuous feature. The mother of Louis Philippe, the Duchess of Chartres, wore in her hair a most marvelous combination of designs made from the hair of her departed relatives. Moreover, by way of added ornament were little images of her son in his nurse's arms, a little negro, and a parrot nibbling a cherry. No doubt these figures were mementoes of significant events in the life of the lady. The *pouf au sentiment* (Fig. 34) was the favorite court style, and consisted of various ornaments fastened in the hair,—branches of trees representing a garden, birds, butterflies,

cardboard cupids flying about, and even vegetables. As a finishing touch a thick coating of powder was added to the towering mass.

These great scaffoldings of gauze and feathers reached such a height that it was quite impossible for the ladies to




Fig. 34, a. Caricature of period

sit in their carriages, and it became necessary for them to kneel upon the floor of the coach to protect the fragile beauty of the towering head-dress. The caricatures of the period show these French belles in their Sedan chairs with the roof taken off to permit the top of the snow-covered edifice to come through. (Fig. 34, a.) It was Marie Antoinette who set the fashion of wearing plumes in the hair and carried it to the greatest extravagance. French literature refers many times to this one caprice of the queen. In Soulavie's *Memoires* we read: "When Marie Antoinette passed through the gallery of Versailles, one could see nothing but a forest of waving plumes a foot and a half higher than the ladies' heads." A lady of the court declared: "It was a fine sight to see that forest of plumes in the Versailles gallery, moving with the least breath of air. It looked like a moving garden of bright flowers, gently caressed by the zephyrs."

One day the queen appeared in a gown of chestnut brown which pleased the king so much that he commented on its beauty, calling it "flea color." Thereafter, flea color became the fashion. "Old flea," "young flea," and "flea back," were so much in demand that the dyers were unable to meet the needs of the trade.

The names given to the colors of this period are quite as ludicrous as those given to the head-dresses. There was "Paris mud," "rash tears," "canary's tail," "agitated nymph's thigh," "newly arrived people," "stifled sigh"; and after the burning of the Opera House in 1763 the fine ladies would have nothing but "burnt opera house," described as a shade of flame color. As for ribbons, the most exclusive were "conviction," "the sigh of Venus," "a sunken eye," "an instant," "attention."

Trimmings were "indiscreet complaints," "great reputation," "vapors," "agitation," "regrets," "sweet smile," etc. Shoes were long and narrow, with emeralds set in the seam of the heel. These were given the trade name *venez-y-voir* (come and see).

The costume of one of the belles of the period is described by a French writer as follows:

Her gown was a "stifled sigh" trimmed with "superfluous regrets," with a bow at the waist of "perfect innocence," ribbons of "marked attention," and shoes of "the queen's hair" embroidered in diamonds with *venez-y-voir* in emeralds. Her hair was curled in "sustained sentiments," a cap of "assured conquest" trimmed with waving feathers or ribbon of "sunken eye," a "cat" or pelatine of swan's-down on her shoulders of color called "newly arrived people," a Medici arranged as befitting, a "despair" in opals, and a muff of "momentary agitation."

Under Louis XVI the designers drew from all sources. Foliage, flowers, landscape, allegories, Chinese ornament, and Arabesque composition appear in all the design of the period. Stripes in fabrics were revived by Marie Antoinette. So fashionable did they become that in 1788 it was said that "Everybody in the king's cabinet looks like a zebra." The Antoinette stripes, unlike those of Mme. Pompadour, were broken with flowers, medallions, and



ornament. Her taste is everywhere seen in the entwined ribbons and garlands of the time.

In 1780 the fires of the revolution were smoldering, and about to break forth into the Terror. Still the old



Fig. 35. a, shoe of 1780; b, shoe of 1790

regime continued; French society was still brilliant, though lowering clouds foretold the coming storm.

✓ This year witnessed the birth of the modern hat as we understand it in the twentieth century. The new straws imported from Italy took the popular fancy. Shapes were as whimsical as the minds that conceived them. (Plate XX.) Some were tall and straight, with little if any brim, and adorned with a bit of ribbon, lace, or feather; some were funnel-shaped and equally elaborate in trimming, while others resembled parasols, their wide brims almost hiding the face.

For the sake of variety many were made of silk and trimmed with ribbons, ruches, and tufts of cock's feathers.

The theater continued to exert a marked influence over the fashions, and nearly every popular actress of the day found herself famous, at least for a time, in the craze for the latest hat.

About 1780 the high heels of the fashionable shoe were thrust farther beneath the foot. (Fig. 35, a.) Toward 1790 the opposite extreme, the low flat heel, became the vogue. (Fig. 35, b.)

Gowns with full skirt and drawn-in waist continued to be worn. The novelty of the period was the fichu of gauze which filled the low-cut neck of the bodice, giving the chest an ill-proportioned prominence. (*F*, Plate XXI.) All kinds of materials were in vogue,—satins, silks, and cloth,

either plain or striped. However, they gradually became more simple. Cottons, India prints, and lawns were adopted.

Women at this period wore watches with little fobs (*C*, Plate XXI); indeed one was not sufficient—the leader of fashion must needs adorn herself with two.

As the years wear on, the old world of frivolity and luxury grows more blasé, seemingly ripe for destruction as it is engulfed in the catastrophe of the Revolution. The monarchy that has endured for centuries is about to fall. As the horizon darkens, the tone of Paris grows serious.

By 1792 all is changed. The salons of Paris are closed; king, queen, France's greatest and fairest, face the guillotine; Paris crouches in deadly fear of the Terror—the tremendous social and political upheaval of the Revolution.

No more brocade, tissues, and gold lace! No more trains, feathers, and furbelows! The appearance of the French woman was strangely altered. Changed conditions were reflected in the dress, which showed little ornament. Skirts were plain, worn with a sash about the waist; bodices were extremely simple, worn with short sleeves or long close-fitting sleeves, with the kerchief or fichu folded at the neck. (*F*, Plate XXI.) The only ornament was some small symbol of the Revolution, military or naval trophies, or perhaps the national colors. All classes were leveled, even the very wealthy adopting great simplicity of dress.

English fashions came into favor for a time. Close-fitting jackets with large lapels were adopted by women of

---

#### COLOR NOTATION—PLATE XXI

- A*—Coat, G  $\frac{5}{2}$ ; braid, G  $\frac{4}{1}$ . Hose, hat, G  $\frac{4}{1}$ . Shoes, C  $\frac{2}{1}$ . Cravat, white.  
*B*—Dress, B  $\frac{5}{6}$ . Bandings on bodice, Y  $\frac{7}{4}$ . Scarf, Y  $\frac{7}{4}$ . Hat, Y  $\frac{7}{4}$ ; bands, P B  $\frac{4}{2}$ ; flowers, Y  $\frac{7}{4}$ , Y R  $\frac{7}{4}$ .  
*C*—Dress, white; stripes, R  $\frac{5}{6}$ , B  $\frac{4}{4}$ ; band, B  $\frac{4}{4}$ . Front of bodice, white. Cuffs, B  $\frac{4}{4}$ . Sash R  $\frac{5}{6}$ ; fringes, R  $\frac{5}{6}$ . Hat, black; ribbon, R  $\frac{5}{6}$ ; cockade, R  $\frac{5}{6}$ .  
*D*—Trousers, Y  $\frac{8}{6}$ . Waistcoat, white. Coat, Y R  $\frac{4}{4}$ ; revers, white. Hose, white; stripe, B  $\frac{5}{6}$ . Tie, white. Hat, Y R  $\frac{4}{4}$ . Shoes, black.  
*E*—Dress, R  $\frac{5}{6}$ . Trimmings and revers, B G  $\frac{4}{4}$ . Hat, B G  $\frac{5}{4}$ -Y R  $\frac{7}{4}$ .  
*F*—Skirt, Y  $\frac{8}{6}$ . Basque, P  $\frac{4}{4}$ . Hat, P  $\frac{4}{4}$ . Fichu, white. Flowers, R  $\frac{5}{6}$ , G  $\frac{7}{6}$ .



A

B

C

D

E

F

PLATE XXI—FRENCH COSTUME—1700

A—1785—A gentleman of France wearing the long topcoat with revers.

B—1795—The costume worn during the Directory.

C—1790—A costume of the Republic called *à la Constitution*. This was of fine lawn or muslin striped in red, white and blue. The helmet-shaped hat was adorned with red, white and blue feathers.

D—1785—A gentleman wearing the knee-trousers, undervest and coat with cutaway front.

E—1795—A costume of the Directory. While the gowns of the period were simple, many were trimmed with borders and revers.

F—1795—A lady of rank wearing the novelty of the period, a fichu of gauze which filled the low-cut neck of the bodice.

fashion, and with these waistcoats and cravats were frequently worn. They also adopted the long plaited hair and "club" of the men, and carried the cane as gracefully as their brothers had formerly sported the muff. London became and remained for some years the center of fashion. Paris, concerned with matters other than fashion, willingly accepted the styles from across the channel.

Perhaps the most marvelous miracle of the Revolution was the total disappearance in France of the powder-puff and the rouge-pot. No wonder the chronicles record: "Our way of living is being purified; extravagance and luxury are diminishing."

Though the mind of France was serious in the extreme, striking public events were likely to give rise to a new mode; be it a trinket in jewelry or a bit of millinery. When Charlotte Corday focused attention by the assassination of Marat, the large hats gave way to caps *à la Charlotte Corday*. (Fig. 36.) On the taking of the Bastille, fragments of its stones were polished, set in gold, and worn by patriots who thrilled at the name *Liberté*.

Jewels, *à la constitution*, were also much in favor. The Constitution jewelry bore the word "Patrie." The costume *à la constitution* was of fine lawn or muslin in red, white, and blue stripes or flowers; the cambric neckerchief, the vermilion sash, and the helmet-shaped cap, with possibly a spray of feathers or a red, white, and blue cockade at the side. (C, Plate XXI.) In 1793 the wearing of a tricolor cockade was obligatory for women, under penalty of seven days' imprisonment.

Thus fashion responded, in a measure, to the great events of the period.

After the passing of the Terror, chastened and blood-stained France lifted her head and tried again to be merry. Then appeared the *incroyables* and the *merveilleuses*—those freaks of fashion, the natural outcome from so vast an upheaval. (C, D, E, Plate XXII.)

Looking back upon them from today they appear as caricatures of figures from the ancient world. As the



statesmen of the Revolution, Danton, Marat, Robespierre, chose for their models the patriot-martyrs of the Greek and Roman democracies, Demosthenes and Brutus; so the women of the period harked back to antiquity for the popular fashions. The *merveilleuses* were the feminine exaggerations, devoted to the worship of the antique. (C, Plate XXII.) There were no more Parisians; the craze for antiquity seemed universal. Gowns became long, straight, diaphanous tunics, short in front and trailing behind, confined by a girdle worn high. Usually the long train was lifted and carried in grotesque fashion in front. (C, Plate XXII.) The leaders of fashion often wore the tunic slashed from the hip to the foot, displaying flesh colored tights and a golden garter. The cold winters of France affected the ladies not at all. They still continued to go lightly clad, and the furs of the previous century having been discarded, only a mantle, wrap, or large circular cloak, *rotonde*, shielded them from the wintry blasts, the ice and snow. The arms were usually bare, laden with bracelets or covered with long kid gloves. Hats were various, but the more modish among the *merveilleuses* preferred the small hat elaborately trimmed with ribbon or tall feathers. (E, Plate XXII.)



Fig. 36. Charlotte Corday cap (After Robida)

And what shall we say of wigs! With the tunics *à la Diane*, *à la Flore*, *à la Galatine*, or *à la Minerva*, the wigs naturally aspired to *à la Sappho*, *à la Venus*, or *à l'Aspasia*. The various arrangements of the hair were borrowed from the types seen in the closely curled hair of the Greek statues.

The little reticule was a very necessary part of the costume for the gauzy materials of the day were too flimsy to support a pocket, and the handkerchief and purse were still the necessary adjuncts of the toilette. (E, Plate XXII.)

The shoes resembled the old-time sandal, being a light weight sole held in place by ribbons laced about the ankle. Not every *merveilleuse*, however, was willing to disfigure the foot with a sandal; some preferred to go unshod, wearing upon the toes little rings of gold. Another type of *merveilleuse* wore a high cravat which was folded several times about the bared neck in a clumsy and awkward manner. This, with the disordered locks of hair streaming over the bare ears and about the face, and the huge hat all astir with ribbons, presents a picture in perfect accord with the mental tone of France. (*E*, Plate XXII.)

While the *merveilleuses* adopted the gowns "antique," the *incroyables* simply brought theirs from across the Channel. Their high-collared coats and huge cravats and twisted walking-sticks were decidedly English. (*D*, Plate XXII.) In fact, the costume not displaying a touch of "English" was considered decidedly bourgeois.

Suddenly the Titus coiffure became the fashion, no doubt suggested by the lingering influence of the guillotine. Fashion dictated closely cut locks, allowing only a few of the loose-flowing ringlets to remain to soften the brow. (Fig. 37.)

To complete the harmony of the costume a red shawl or red necklace was often worn with the Titus coiffure. Other popular styles were *à la victime* and *à la sacrifice*.

---

#### COLOR NOTATION—PLATE XXII

- A*—Gown, white; border, R  $\frac{1}{2}$ . Scarf, G Y  $\frac{1}{2}$ . Hat, white. Girdle, white. Boutonnière, B G  $\frac{1}{2}$ , R  $\frac{1}{2}$ . Gloves, Y  $\frac{1}{4}$ . Parasol, G Y  $\frac{1}{2}$ . Shoes, white.
- B*—Gown, white. Scarf, turban, R  $\frac{1}{2}$ . Shoes, R  $\frac{1}{2}$ . Gloves, Y  $\frac{1}{4}$ . Brooch, gold R  $\frac{1}{2}$ .
- C*—Tunic, white; border, Y  $\frac{3}{4}$ , Y R  $\frac{1}{4}$ . Scarf, R  $\frac{1}{2}$ , B  $\frac{1}{2}$ , black. Head-dress, Y R  $\frac{3}{4}$ , Recticule, Y R  $\frac{1}{2}$ , Y R  $\frac{1}{2}$ , black. Bracelets and brooch, gold, B G  $\frac{1}{4}$ .
- D*—Trousers, Y  $\frac{1}{2}$ . Waistcoat, R  $\frac{1}{2}$ . Coat, G  $\frac{1}{4}$ . Cravat, white. Hat, G  $\frac{1}{4}$ . Boots, black; tops, Y R  $\frac{1}{2}$ .
- E*—Dress, Y  $\frac{1}{2}$ , Y  $\frac{1}{2}$ , Y R  $\frac{1}{4}$ ; border, B  $\frac{1}{4}$ . Hat, Y  $\frac{1}{2}$ , Y R  $\frac{1}{2}$ ; trimming, R  $\frac{1}{2}$ . Sandals, straps, R  $\frac{1}{2}$ . Recticule, R  $\frac{1}{2}$ , B  $\frac{1}{2}$ . Y  $\frac{1}{2}$ . Bodice, P B  $\frac{1}{2}$ ; trimming, G  $\frac{1}{4}$ . Cravat, P B  $\frac{1}{2}$ . Gloves, black.



A

B

C

D

E

## PLATE XXII—FRENCH COSTUME—1800-1814

A—1804, B—1814—Women of rank wearing the costume of the Empire. The finest of materials were popular. The turban of the Orient was adopted and with the poke-bonnet became the leader in fashionable headgear.

C, E—1800—The *Merveilleuses*, or "Impossibles," the feminine product of the Terror. They adopted the antique in dress, copying that of Greece and Rome. Jewels bedecked both fingers and toes. (After Robida.)

D—1800—The *Incroyable*, or "Unimaginable," the masculine product of the Terror. These men were exaggerated copies of the English fashion. The high-collared coats, huge cravats and twisted walking-sticks reflect the spirit of the time.

The Directory (1795-1804) followed the Revolution. The antique costumes became more and more restrained, the waist short, and the skirt long and clinging. At this time, following the Egyptian campaign, the India shawl with Persian design was introduced. It became so popular that it led to imitation by the French, and later to the Paisley copy made in Paisley, Scotland.



Fig. 37. Titus coiffure  
(After Robida)

Under the Empire, the costume became simple and beautiful. The celebrated portraits of Mme. Récamier and Josephine de Beauharnais by Jacques Louis David, the court painter of Napoleon, show the

charm, beauty, and grace attained by these costumes in the opening years of the new century.



## CHAPTER X

### COLONIAL COSTUME IN AMERICA

(1620-1781)

**D**URING the wonderful seventeenth century new vistas were opened. The English, Dutch, and French were setting sail for the new land beyond the sea. Many were seeking the religious freedom denied them in the Old World, others were in quest of adventure and wealth, and still others were lured by the opportunity for larger living.

The greater number of colonists came to America through stress of circumstance. They found a wide gulf between the European manner of living and that found necessary as dwellers in the New World. Looking back from the highly developed living of the twentieth century, one is wont to believe that these earliest settlers, so occupied in finding a new home, and adjusting themselves to new conditions, were not concerned with dress, and the exacting demands of fashion. However, drawing our knowledge from old records, it is evident that these early New Englanders had an inborn regard for the niceties of dress, that even in this early day the "moral effect" of clothes was appreciated.

The various groups of settlers in the New World brought with them certain habits of dress, and ideas concerning dress which were particularly characteristic of the group itself.

The first settlers in Massachusetts, the Pilgrims or Separatists, came to Plymouth in 1620, having previously lived for a time in Holland after leaving England. Their garments followed the general lines and fashions of those of the English court under James I (1603-1625), in which the doublet and hose were the outstanding features. This col-

ony was poor, and their condition did not improve until the second and third generations.

Following the Pilgrims came the Puritans of the Massachusetts Bay Company. They were Puritans but not Separatists and their condition was much different. This colony was not poor but had the advantage in wealth and aristocratic connections. Many of their number held degrees from English universities. It is said they brought property aggregating in value a million dollars. Charles I was on the throne of England at this time (1625-1649), and the dress of the Puritan fathers followed the lines of this luxurious period with one exception—all extravagance was eliminated.

Many of the Virginians and neighboring colonists were Cavaliers, sympathizers with the Royalist faction in England, and with them fine dress was a hobby.

The colony in Manhattan was made up of both Dutch and English elements. The Dutch brought with them their characteristic thrift and optimism. Their customs and the details of their dress were similar to those of the homeland.

A knowledge of the relative social and financial state of the different colonies leads to a clearer understanding of certain conditions and surprises in dress. Though the dress of all these early settlers bore the stamp of that center of fashion—the French capital, in each instance the individuality and taste of the homeland was seen, possibly in a change of color, an added ornament or a difference in material. However, in the dress of the Pilgrim and Puritan there were other significant differences, of far greater import. Though the dress followed the type of the period, all extravagance had been omitted and all color subdued. The rich laces, ribbons, feathers and other gay trimmings were conspicuously absent—an evidence of revolt against the extremes of English court dress. Not only had those of Puritan faith expressed their feeling by a change of dress, but many did likewise who still remained with the Church of England. Further, this change toward more simple dress had been made previous to their departure for

the new land. No doubt the materials were heavier, the shoes more substantial; and still other changes, advisable under the new conditions of living, were also made.

The dress of the early settler in America, particularly of the Pilgrim and Puritan, has always been associated with the word "dull," "drab," and "sad-colored." These words picture to the mind a group of gloomy, sober-hued individuals. This, however, was by no means the dress that these early Puritans presented. The colors were dark, to be sure, but by no means dull. They were warm tones of brown, varying from dark rich hues to orange and presented a picture of far more warmth than is commonly associated with the period. Other colors worn and classified in the old records as "sad-colours" are purple, deere-colour, and French green.

Early historical data furnish reliable sources of knowledge on this dress of the first New Englanders. The various lists of the Colonization Company of London, furnishing apparel to the different groups, are still preserved. Here each article is named and frequently described, even the color being given. Many of the old wills bequeathing various articles of apparel are still on record, as are also private letters in which extensive wardrobes ordered from London, are listed with full descriptions. There remain, besides, personal letters, diaries, and last, but by no means least, the portraits of famous folk dressed in the costume of the period.

Looking through the inventories of the Colonization Company we find that the distinguishing characteristic of all clothes coming to America, is their wearing quality. Doublets and jerkins were of leather or heavy woollens; the cassock, a garment similar to a coat, was of canvas and fastened with hooks and eyes, for "buttons were a vanity." Heavy shoes and stockings were also listed, and the mandillion, a loose cloak, is described as of "strong durable stuff."

As prosperity became more general, however, the drift was toward finer and costlier dress. The leather doublets

and breeches were replaced by others of fine wool, and it is said that even damask and velvet were ventured. Women's dress, too, tended to become more elaborate and costly until the inevitable laws were passed to prohibit such luxury and regulate the dress. As early as 1634 the Massachusetts court forbade the purchase of

—any apparell either Woolen, or Silk, or Linen, with any lace on it, Silver, Gold or Thread, under the penalty of forfeiture of such clothes. Also that no person, either man or woman, shall make or buy any Slashed Clothes, other than one Slash in each sleeve and another in the back. Also that Cut-works, embroideries, or Needlework Caps, Bands, or Rails,<sup>1</sup> are forbidden hereafter to be made and worn under the aforesaid penalty.<sup>2</sup>

In 1634 all use of lace, except a small edging on linen was forbidden. From 1620 to 1640 the usual costume of a well-to-do Puritan colonist of Massachusetts Bay consisted of a cloth doublet and breeches, stockings or hose of dark gray or green wool, fastened to the knee-breeches by points of black galloon or ribbon. (*A*, Plate XXIII.) The tall broad brimmed hat was of black felt. The beaver hats which were so popular in England were also worn. These were very expensive, and of course could not be purchased except by the very wealthy.

Of all the felts that may be felt  
Give me the English beaver.

From *Merry Drolleries*, 1661.

The large white collar or "playne band," which superceded ruffs, and the turned-back cuffs of Holland linen were indispensable to the Puritan costume. The change from the standing ruff to the falling band took place in the seventeenth century in France, and was simply the turning down of the high ruff. This falling band gradually became known as simply the "fall," and was worn by both men and women.

<sup>1</sup>Rail, or Rayl—A woman's loose gown or sack worn during the day.

<sup>2</sup>Alice Morse Earle, *Two Centuries of Costume in America* (New York: The Macmillan Company, 1903), p. 61.



## WHY WOMEN WEAR A FALL

A Question 'tis why women wear a fall?  
 And Truth it is to Pride they're given all;  
 And *Pride*, the Proverb says, *will have a fall*.

All Puritans took great pride in the nicety of this "playne band." The doublets, waistcoats and cloaks of the colonists were usually fastened by hooks and eyes, but buttons must have been worn, for records show that buttons were used for traffic with the Indians. They were sometimes made of coins, often Spanish dollars; pewter buttons were also made, and doubtless worn on men's clothes from earliest colonial days. Buttonholes were a matter of ornament as well as use, being often embroidered in silver or gold thread or bound in gay colors.



Fig. 38. A clog

The Puritan woman wore gowns of cloth in purple, russet or gray. The skirt of the gown was turned under and looped back, showing the petticoats of homespun and linsey-woolsey. (*B*, Plate XXIII.) Over this was worn the large apron of white linen. Every woman of consequence had a white apron in her wardrobe. The large kerchief was put about the shoulders on going out-of-doors. The hood was a necessary part of the outdoor costume, and was made of dark colored silk or camlet.<sup>3</sup>

The hood is plainly a development from the custom of throwing a strip of linen over the head and tying it under the chin. Throughout the colonies hoods were worn by women of every station. In very cold weather the cloak and hood were of heavier material or fur, sometimes fur-trimmed. Many of the early engravings of the Puritan woman picture her a statuesque figure in voluminous skirts, the outer one gathered up and carried, displaying the under petticoat. The tall beaver hat, similar to that worn by the men was quite as commonly worn as the hood.

<sup>3</sup>Camlet—a material of hair, silk or wool, or all these materials combined, in general use in colonial days for cloaks and petticoats.

Woolen stockings and stout shoes with wooden heels completed this substantial costume. In rainy or inclement weather clogs were worn. (Fig. 38.) These were somewhat similar to the pattens of the French woman. Though all served the same purpose, types varied. In general they were simply thick wooden soles, raised by means of rings of iron fastened underneath. Straps adjusted about the instep kept them in place.

In the colony of Manhattan the dress of England mingled with that of the Hollanders. The Dutch women were wonderfully skilled in lace-making and embroidering; they also understood the making and mixing of dyes, which they used in coloring their garments. They understood carding and weaving. The woolen materials worn by the family as well as the household linens were made at home. The coarse cloth called "linsey-woolsey," the warp being linen and the woof, wool, was made throughout the colony.

The fashionable lady of New Amsterdam about the year 1660 wore the loose jacket, or samare, edged with fur, and a full gown over an equally ample petticoat. (*E*, Plate XXIII.) The portraits of the period show the hair arranged by turning the side locks under and tying with ribbon, while the remainder was fastened at the back in a coil into which ribbon was frequently twisted.

The colors in Dutch gowns as a rule were quite gay. The appearance of these dames of New Amsterdam is accurately pictured by Washington Irving:

Their hair, untortured by the abominations of art, was scrupulously pomatumed back from their foreheads with a cardle, and

---

#### COLOR NOTATION—PLATE XXIII

- A*—Coat, trousers, hat, black. Hose, G  $\frac{4}{5}$ ; points, black. Shoes, black. Cape, black; lining, G  $\frac{4}{5}$ . Collar, cuffs, white.
- B*—Skirt, Y R  $\frac{1}{2}$ . Overdress, R P  $\frac{3}{4}$ . Apron, collar, cuffs, white. Hood, R P  $\frac{3}{4}$ , Y R  $\frac{1}{2}$ . Muff, Y R  $\frac{1}{2}$ . Shoes, black.
- C*—Coat, waistcoat, trousers, Y R  $\frac{5}{8}$ . Shoes, black. Hose, Y R  $\frac{5}{8}$ . Cravat, collar, cuffs, white.
- D*—Dress, N 7. Apron, G  $\frac{4}{5}$ . Collar, cuffs, apron, front of bodice, white. Hood, N 7, white.
- E*—Skirt, G  $\frac{4}{5}$ . Overdress, Y  $\frac{1}{2}$ . Samare, Y  $\frac{1}{2}$ , R  $\frac{3}{4}$ ; fur, white. Ribbon, G  $\frac{4}{5}$ .



A

B

C

D

E

PLATE XXIII—COLONIAL COSTUME IN AMERICA—1620-1725

- A*—1620-1640—A Puritan colonist. The costume was usually of black cloth. The broad-brimmed hat, the "playne band" and turned-back cuffs, heavy shoes and mantle completed the typically Puritan dress.
- B*—1620-1640—A Puritan woman wearing a characteristic type of dress. The kerchief about the shoulders, the apron of white Holland linen and the turned-back cuffs were indispensable.
- C*—1682—The Quaker dress was a survival of the French dress of 1660-1680, with all the extravagances eliminated.
- D*—1682—The dress worn by Quaker women. The dress was usually of soft-colored silk.
- E*—1725—The dress worn by women of New Amsterdam. The full skirt and the loose jacket, or samare, edged with fur are frequently seen in the paintings of the Dutch masters.

covered with a little cap of quilted calico, which fitted exactly to their heads. Their petticoats of linsey-woolsey were striped with a variety of gorgeous dyes, though I must confess these gallant garments were rather short, scarce reaching below the knee; but then they made up in the number, which generally equalled that of the gentlemen's small clothes; and what is still more praiseworthy they were all of their own manufacture, of which circumstance, as may well be supposed, they were not a little vain.

Those were the honest days in which every woman stayed at home, read the Bible, and wore pockets—aye, and that too of a goodly size fashioned with patchwork into many curious devices and ostentatiously worn on the outside. These, in fact, were convenient receptacles where all good housewives carefully stored away such things as they wished to have at hand; by which means they often came to be incredibly crammed. Besides these notable pockets they also wore scissors and pincushions suspended from their girdles by red ribbons, or, among the more opulent and showy classes, by brass and even silver chains, indubitable tokens of thrifty housewives and industrious spinsters. I cannot say much in vindication of the shortness of the petticoats; it doubtless was introduced for giving the stockings a chance to be seen, which were generally of blue worsted with magnificent clocks; or perhaps to display a well turned ankle and a neat though serviceable foot, set off by a high-heeled leathern shoe, with a large and splendid buckle.

There was a secret charm in these petticoats, which no doubt entered into the consideration of the prudent gallant. The wardrobe of the lady was in those days her only fortune; and she who had a good stock of petticoats was as absolutely an heiress as is the Kamtschatka damsel with a store of bear-skins or a Lapland belle with plenty of reindeer.

The dress of settlers in Connecticut and Maine followed the same general lines as those of the Puritans. Many of the Southern colonists were Cavaliers. They had no particular feeling against fine dress. The great tobacco crops of the South yielded rich returns and the ready funds, together with the taste of these settlers, expressed itself in a luxuriousness of dress quite comparable to that of the fashion circles of London and Paris.

In 1660, as in France and England, the doublet was gradually transformed into the coat, which became the general style of men's attire. With the coat came the vest, the cravat, wigs, garters and buckles. All these came in about the same period, between 1660 and 1666. The cravat, or neckcloth, as it was frequently called, was a scarf of



white linen, quite sheer and over two yards in length. It was passed twice about the neck and lapped in front after the manner of the French Steinkirks.




Fig. 39. Wigs. a, campaign wig; b, Ramilie tail; c, periwig

Wigs were not in general use in England when Plymouth and Boston were settled, and had not been adopted for general wear before 1670. Numerous references to wigs are made in the diaries of famous folk both in England and in the colonies. From this it is evident that wigs had a tremendous run. They were worn by governors, ministers, magistrates and "plain people," as well. Many of the portraits of this early day picture the great black thickly curled wigs of the colonists. In 1673 the legislature of Massachusetts took up the matter, and the clergy hurled denunciations from the pulpit. They were hotly termed "Bushes of Vanity," "Artificially deformed Maypowles fit to furnish her that in a Stag play should represent some Hagge of Hell." "Monstrous periwigs such as some of our church members indulge in make them resemble locusts that come out of the bottomless pit." The Puritans resolved that "Ye wearing of extravagant superfluous wigs is altogether contrary to truth." However this matter of wig-wearing was a most difficult one to solve, for among those who had adopted the wig were the most prominent members of the colonies. By 1716 the fashion was general. Wigs were called by various names which passed from the

French court to England. The peruke and periwig were the distinctly formal wigs. (Fig. 39, c.) In May, 1706, the great victory of Marlborough on the battlefield of Ramillies gave the name to the new style of wig. The "Ramilie" wig was puffed out at the sides and had a long queue, called the "Ramilie tail." It was tied with a large bow at the top and a smaller one at the bottom. (Fig. 39, b.) This style of wig was worn for many years; finally the length of the braid was reduced to seven inches and later cut off altogether. The Campaign wig was curled and had long side pieces twisted at the ends. (Fig. 39, a.) Later, in the reign of George II, bob wigs came in, aiming to represent the natural hair. These were sent to New England in great quantities and eagerly purchased by the colonists.

About the same time that wigs became popular, muffs were introduced for gentlemen's wear. It is a severe strain on the imagination to see our colonial fathers adopting that novel French vanity, the muff. It is nevertheless true that they, as well as the French and English of the period, were enthusiastic over this whim of Dame Fashion. It was believed to lend an air of importance and dignity to the wearer. *The Boston News Letter*, of March 5, 1715, announces: "Any Man that took up a Man's muff drop't on the Lord's Day between old meeting house and the South are desired to bring it to the Printer's office and shall be rewarded." The first muffs were made of rich materials, not always fur, and trimmed with laces and ribbon. It was some time after this that fur muffs became fashionable.

While the dress of men was taking on new vanities, women were adding strange eccentricities to their toilette. Patches were in vogue as early as 1650, and were widely worn by the belles of the day. At the same period in France the following appeared:

Our ladies have lately entertained a vain custom of spotting their faces out of affectation of a mole, to set off their beauty such as

Venus had; and it is well if one black patch will serve to make their faces remarkable for some fill their faces full of them, varied into all manner of shapes.

Perhaps the extreme of patch-wearing as described in Bulwer's satirical lines was not seen on this side of the Atlantic:

Her patches are of every cut,  
For pimples and for sears;  
Here's all the wondering planets' signs,  
And some of the fixed stars,  
Already gummed to make them stick  
They need no other sky.

The patches were usually carried in very costly patch-boxes of silver, ivory and tortoise shell.

About 1701 hoops became the fashion. Though at first they were considered as "trenching on morality," by 1713 the reign of the hoop had begun in earnest. Even though they were condemned by the press and the clergy as against the "Light of Nature and the Laws of God," they still prevailed. They reached their most extreme form about 1745. Many and varied were the types of hoop, and the hoop and petticoat combination. Even the children were hooped as modishly as their fashionable mothers. The hooped petticoat is seen in many of the charming costumes of the period.

With the adoption of all these luxuries of fashion the dress became more and more extravagant. This love of dress so evident throughout the colonies affected also the simple Quaker folk. At the time the Quakers came to Pennsylvania with William Penn, no distinctive style of dress had been adopted. It had not, at this time become necessary to formulate any strict rules of dress. It is true that the color and style of dress among the Quakers was serious when compared with the fashionable dress of that day. However, it would indeed be a gala dress for our gentleman of the twentieth century. The Quaker dress was a survival of the English fashion worn during the reign

of Charles II (1660-1685), similar to the French, of 1660. (C, Plate XXIII.) It was dark brown or plum in color and without trimming of any kind. The full shirt sleeves ended in ruffles which fell over the hand, and the neckcloth was of the finest linen but always untrimmed. Though the hats were similar in style to those of the French period, they were never adorned with a feather. They were set straight upon the head, and never "doffed in deference to either rank or sex." The hair was cut with a short bang across the forehead, and fell to the shoulder. Occasionally it was powdered; moreover periwigs are said to have been worn by these "genteel Friends." With slight modifications in material and color the general style of Quaker dress remained the same for years.

The dress of Quaker women followed in its general lines the prevailing mode; full skirts, pointed bodices, kerchief and hood. (D, Plate XXIII.) However, the manner of adjustment and the lack of ornamentation produced an effect of severe plainness. The gown was usually of some soft colored silk; the fine white kerchief was an indispensable nicety of the costume; the long full apron was also of silk, and usually of a dark green color. In 1698, at Aberdeen, the following was resolved: "Let none want aprons at all, and that either green or blue or other grave colors, and not white upon the street or in public at all; not any span-gled or speckled silk or cloth or any silk apron at all." The report at Lincolnshire in 1721 says: "We think Green aprons are Decent and Becoming to us as a People."<sup>4</sup> The black hoods were worn by Quaker women for a long time. Late in the century they adopted the beaver hat, and in the nineteenth century, the poke-bonnet. Like all other items of colonial dress the hood may be traced directly to the French court, and to Mme. Maintenon's preference for this particular type. It was undoubtedly chosen by the followers of Fox because, historically, it suggested godliness of mind.

---

<sup>4</sup>Earle, *Two Centuries of Costume in America*, p. 601.



The black silk hood with formal pride  
 First rolled beneath the chin was tied  
 So close, so very trim and neat,  
 So round, so formal, so complete,  
 That not one jag of wicked lace  
 Or rag of linen white had place  
 Betwixt the black hood and the face,  
 Which peeped from out the sable hood  
 Like Luna from a sullen cloud.

Under the black hood which was put on for outdoor wear was worn the little ruffled cap of sheer lace. The hair was parted in front and arranged in a coil at the back.

In William Penn's book, *Some Fruits of Solitude*, we read a message of counsel to his people, whose welfare was ever his first concern:

Choose thy clothes by thine own eye, not another's. The more simple and plain they are, the better. Neither unshapely, or fantastical and for use and decency, not for Pride.

In 1726 when the love of dress was becoming excessive, the "women friends" at the quarterly meeting at Burlington sent the following message to their fellow women-workers:

At first, That Indescent fashion of hooped Pettycoats, or ye imitation of them, Either by Something put into their pettycoats to make you set full, Wearing more than is necessary, or any imitation whatever, which we take to be but a Branch Springing from ye said corrupt root of Pride.

And Also that none of sd friends Accustom themselves to wear their Gowns with Superfluous folds behind, but plain and Decent. Nor to go without Aprons. Nor to wear Superfluous Gathers or Plaits in their Capps, or Pinners, Nor to wear their heads drest high behind; Neither to cut or lay their hair on ye forehead or Temples.

And that friends are careful to avoid Wearing Striped Shoes or Red and White heel'd shoes, or Clogs or Shoes trimmed with gaudy colors. And also that no friends Use ye Irreverent practice of taking Snuff or handing a Snuff box one to Another in Meetings, lest it Divert ye mind from ye more inward spiritual exercises which all ought to be Concerned in.<sup>5</sup>

However, notwithstanding all this precaution, it was not long before Philadelphia, Penn's own city, was taking the lead in matters of dress.

<sup>5</sup>Earle, *Two Centuries of Costume in America*, p. 609.

During the early years of the new century times were thriving and costume was gradually growing more and more elaborate. However, in Massachusetts the everyday dress still continued to show the same tendencies as in early years. All materials had wearing quality. Women wore dresses of camlet or moire camlet (watered camlet) over stiffened petticoats made of durant, a close-grained woollen material. The "falling whisk," or "whisk," of fine linen or lace suggests the French period of 1866-1700. The whisk was probably another name for the "fall"; both no doubt refer to the turned-down ruff of the previous century. At this time the dresses were cut low and the whisk used to cover the neck. The popular style of wearing the hat over the little ruffled cap has been made familiar in the pictures of Hogarth.

The close commercial relations between England, France and the colonies made it possible to keep up with all the latest decrees of fashion. In order to publish abroad the most recent modes, jointed dolls dressed in the latest fashion were sent from Paris to London and thence to America. These fashion dolls date back to a former period. In 1391, according to French records, a doll was sent to the Queen of France; one hundred years later another was sent to the Queen of Spain. Later they were sent to the larger cities as forecasts of fashion. In 1764 these dolls were made the size of a full-grown person, dressed in the latest mode, and called *grand courrier de la mode* (guide to the fashions). The inventions in millinery and coiffure were likewise illustrated in these traveling dolls.

At regular intervals of from four to five months came the fashion dolls to the colonies, and all the mantua-makers made haste to copy the latest ideas for their wealthy patrons. The *New England Weekly Journal*, of July 2, 1733, contains the following announcement:

To be seen in at Mrs. Hannah Teatt's, Mantua-maker at the head of Summer Street, Boston, a baby dressed after the newest fashion of Mantuas and Nightgowns, everything belonging to Dress Latilly arrived on Captain White from London. Any ladies that desire to

see it may either come or send, she will be ready to wait on 'em; if they come to the house it is two shillings, if she waits on 'em it is seven shillings.<sup>6</sup>

In 1757 two fashionable mantua-makers of Boston announced that they had

just arrived from the kingdom of Ireland, and have furnished themselves from London in patterns of the following kinds of wear for Ladies and Gentlemen and have fixed a correspondence to have from thence the earliest fashions in miniature.<sup>7</sup>

Thus the fashion dolls of the day published abroad the latest dictates in dress quite as effectively as the modern fashion periodical.

Going on with the century, times were indeed prosperous, and greater richness and extravagance in dress was indulged. Boston became a center of fashion and display. This in part was inspired by the extravagance of political leaders who endeavored to follow the styles of the English court which in turn drew its inspiration from the court of France. The wealthy took on an extreme richness of attire which set the wheels of rivalry in motion. One English traveler wrote in 1740: "Both the ladies and gentlemen dress and appear as gay in common as courtiers in England on a coronation or birthday."<sup>8</sup> Hawthorne looking back to the period wrote: "There are tokens everywhere of a style of luxury and magnificence we had not associated with our notion of the time. The gaudiest dress permissible by modern taste fades into Quaker-like sobriety compared with the rich, glaring splendor of our ancestors."

During these early years of the century the dress of New York was rich in materials and lavishly ornamented with jewels. Imported brocades, taffetas, poplins, silks and satins were generally worn. The ladies adorned themselves with necklaces, flowers, aigrettes, handkerchiefs, silk gloves and mitts, satin shoes and silk hose and in winter donned the richest furs. Indeed the love of dress on the part of

<sup>6</sup>Earle, *Two Centuries of Costume in America*, p. 661.

<sup>7</sup>*Ibid.*, p. 666.

<sup>8</sup>Earle, *Costume of Colonial Times* (New York: Charles Scribner's Sons, 1894), p. 24.

the colonial dames of New York caused much comment by travelers of the period. One, Chevalier de Crève Cœur, declared: "If there is a town on the American continent where English luxury displays its follies, it is New York."

Philadelphia completed the trio of the large centers that were becoming famed for their lavishness in dress. The colonial gentleman of the period wore the fashionable dress adapted from the French of 1700. The style of coat was not changed. It was still straight and full-skirted, and the tails stiffened with buckram or wadding. (*B*, Plate XXIV.) Thus our gentlemen's dress of the day vied with the hoop and panier of the ladies. Waistcoats were often elaborately trimmed with lace and embroidery. Shoes with square toes were gradually giving way to the more pointed, though the red heels still continued the vogue.

The colonial dames wore rustling gowns of silk, satin and brocade, with bodices cut low. In the National Museum in Independence Hall, Philadelphia, is a charming costume of this period. It is of yellow damask silk and looped back with narrow braid and ribbons, showing the French tendencies of the eighteenth century. The bodice and edges of the skirt are finished with ruchings of pinked material. The dainty slippers worn with the costume are of white satin.

It was about 1750 that powdered hair invaded the ranks of the colonists, and every colonial dame wore her hair thickly covered with fine white powder. The origin of hair powder is quite obscure. It is said to have been introduced

#### COLOR NOTATION—PLATE XXIV

- A*—Petticoat, Y  $\frac{3}{4}$ . Overdress, Y R  $\frac{3}{4}$ ; design, R  $\frac{3}{4}$ , G  $\frac{3}{4}$ . Cap, kerchief, puffs on sleeves, white. Shoes, black. Fan, Y  $\frac{3}{4}$ .  
*B*—Coat, trousers, P  $\frac{3}{4}$ . Vest, P  $\frac{3}{4}$ , Y  $\frac{3}{4}$ . Cuffs, cravat, hose, white. Shoes, black. Buckles, gilt.  
*C*—Gown, Y  $\frac{3}{4}$ ; design, R P  $\frac{3}{4}$ , G  $\frac{3}{4}$ , R Y  $\frac{3}{4}$ . Ribbon, black.  
*D*—Coat, trousers, P  $\frac{3}{4}$ . Vest, P  $\frac{3}{4}$ , bandings, Y  $\frac{3}{4}$ , gold. Cravat, cuffs, white. Ribbon on hair, black. Shoes, black.  
*E*—Overdress, brocade, Y  $\frac{3}{4}$ , B  $\frac{3}{4}$ , Y R  $\frac{3}{4}$ , Y R  $\frac{3}{4}$ . Skirt, white. Vest, white; ribbon, Y R  $\frac{3}{4}$ . Fan, Y  $\frac{3}{4}$ , Y R  $\frac{3}{4}$ , black.  
*F*—Overdress, Y  $\frac{3}{4}$ ; trimmings, white. Skirt, white. Fan, white.





A                      B                      C                      D                      E                      F

PLATE XXIV—COLONIAL COSTUME IN AMERICA—1710-1777

- A—1770—The quilted petticoat, the watteau overdress and little cap are characteristic of the period.
- B—1710—A colonial gentleman, wearing the fashionable dress of the French of 1700. The long skirt of the coat is stiffened with buckram.
- C—1777—The fashionable watteau of colonial days.
- D—1727—A colonial costume. The long-skirted coat is worn with a waistcoat elaborately trimmed with lace and embroidery.
- E—1725—A colonial dame in the hooped skirt and the boned and pointed bodice, wearing the pompadour with a curl.
- F—1725—A dress of the same period with the overdress looped in panier effect.

into France by Marie de' Medici, about 1600; however, it is known to have been used at a much earlier date. At this time the pompadour style of hair-dressing ranged to various heights and continued for many years. This fashionable style was attained by



Fig. 40. The calash

drawing the hair back from the face and over a roll or cushion of hair. These rolls grew from one of small size to those of much greater dimensions. After reaching an exaggerated height a change gradually took place and the roll descended to about two inches in height, and the hair was roughed and pulled high in the center. This was named the "macaroni roll." The term originated in 1770 in London with a group of Englishmen who had just returned from a town in Italy

and had formed themselves into a club called the "Macaroni Club." In matters of dress it stood for all things that were eccentric and extreme.

During the reign of the high head-dress, the calash, often called the "bashful bonnet," was fashionable. (Fig. 40.) It is said to be the novel invention of the Duchess of Bradford. It was of great size, usually of brown or green silk, or dainty white material. It was extended by whale-bone run through shirrings, which were usually about three inches apart. The neck line was drawn in and fitted with a little cape. The resemblance to the extension top of a light form of carriage called *calèche*, which was commonly used in France, is striking. No doubt it was due to this resemblance that the bonnet received its name. The use of the term "bashful" arose from the arrangement of the ribbon streamer at the top edge. This permitted it to be drawn over the face, if the fair wearer wished, or pushed

back of the head. This bonnet was worn well on toward the end of the century and continued to be in use by old-fashioned ladies even to a later day.

Toward 1755 the charming *watteau* was in high favor. (C, Plate XXIV.) The *watteau* is often called the French *sacque*, though it was usually long, falling to the floor. Frequently, however, it was looped in *polonaise* fashion, thus showing to more advantage the costly *petticoat*. (A, Plate XXIV.) These costumes were often of flowered silk and brocade; quite as frequently of muslins, dimities and other dainty fabrics. Many variations of the *watteau* were played upon until the nineteenth century, when the Empire became the leading mode. The *flounces*, plaited, pinked and lace-edged, which were the *falbalas* of the French, were often festooned about the *petticoat*, and frequently trimmed the *sacque*. The *pretintailles* of France were also introduced in the form of *appliqués*. These were large designs in color, cut out from one material and sewed upon another. Other trimmings of the century were pinking, ruching and narrow plaited ruffles set on in semi-circular or wave pattern.

Between 1770 and 1776 the quilted *petticoats* were as much in favor as were the hooped *petticoats* of earlier years. (A, Plate XXIV.) These fashionable *petticoats* were usually made of dainty colored materials, filled with a layer of cotton or wadding, and then run with stitches, quilt fashion, to keep the wadding in place. Often the stitches were so arranged as to form a pleasing border or design at the lower edge. Much of the value of these garments was in the handwork, for they were often elaborately quilted. The handsomest *petticoats* were of quilted silk or satin, and no design was too elaborate for the skillful needlewoman of the period. Over this the *watteau sacque* of dimity or chintz was worn. It was looped back somewhat after the French fashion of the same century.

The little cap so fashionable in the early years of the Washington administration dates back to colonial times. (A, Plate XXIV.) It was made of laces and the finest

gauze and remained the fashion for nearly half a century. This quaint head-dress was no doubt the direct descendent of the French cap, which was worn generally in England and then carried to America. The portraits of Martha Washington and others of the period have familiarized us with this dainty head-dress of colonial times. The long pointed bodice was the very acme of fashion during the greater part of the century, and it seems, with the hooped petticoat, the fichu and the little cap, to be a distinguishing characteristic of colonial dress.

The early painters, Copley and Stuart, have left to posterity a rich heritage of costume in their portraits of American men and women of this early period.

With the oncoming days of the Revolution, one is wont to believe that all thought of fashion must vanish. Quite to the contrary, however, historical records assert that much gaiety and style in dress continued in the larger centers—Philadelphia, New York and Boston. It is undoubtedly true that great poverty and want existed side by side with all this extravagance and show. This love of dress, so manifest in the later days of colonial history, blossomed afresh during the succeeding period and became the distinguishing characteristic of the early years of our national life.



## CHAPTER XI

### AMERICAN COSTUME (1781-1900)

THE opening years of American life are strangely colored with gaiety and extravagance—an unusual hue after so depressing a period. Victory and independence had come to the colonies. The future was bright. Spirits were high. At the same time conditions were unsettled. Political institutions were as yet unorganized. The relation of the state to the national government was under debate; the people had not yet adjusted themselves to any well defined national life. Naturally all these influences, combined, were tonal in shaping the expression of dress in these first years of independence.

Abounding extravagance, clearly the mental tone of the new republic, was the striking feature in the costume of the period. This was largely independent of foreign influences, for both France and England were soberly clad. Paris, under the lowering clouds of the Revolution, had become serious-minded. This was reflected in the dress of the day. In conservative England, restraint in the use of frills and furbelows tended to produce a quiet and unostentatious type of dress. In contrast with these two world centers, America, so young, so bouyant, presented an appearance quite compatible with her youth.

Quoting from an account of the inauguration ball written by one Colonel Stone, a clear idea of the love of dress in these early days may be gleaned:

Few jewels were then worn in the United States, but in other respects the dresses were rich and beautiful, according to the fashion of the day. One favorite dress was a plain celestial blue satin gown with a white satin petticoat. On the neck was worn a very large Italian gauze handkerchief, with border stripes of satin. The headdress was a pouf of gauze, in the form of a globe,

the creneau, or headpiece which was composed of white satin having a double wing, in large plaits, and trimmed with a wealth of artificial roses, falling from the left at the top to the right at the bottom, in front, and the reserve behind. The hair was dressed all over in detached curls, four of which in two ranks, fall on each side of the neck and were relieved behind by a floating chignon. Another beautiful dress was a perriot, made of gray Indian taffeta with the dark stripes of the same color—having two collars, the one yellow, and the other white, both trimmed with blue silk fringe, and a reverse trimmed in the same manner. Under the perriot was worn a yellow corset or bodice, with large cross stripes of blue. Some of the ladies with this dress wore hats à l'Espagnole, of white satin, with a band of the same material placed on the crown, like the wreath of flowers on the headdress above mentioned. This hat, which, with the plume, was a very popular article of dress, was relieved on the left side, having the handsome cockades—one of which was at the top, and the other at the bottom. On the neck was worn a very large plain gauze handkerchief, the ends of which were hid under the bodice.<sup>1</sup>

Other instances of recorded extravagances are preserved. One French economist declared that the wives of bankers and merchants were clad alike in the very height of French fashion. He adds: "At Mr. Griffin's house, at dinner, I saw seven or eight women all dressed in great hats, plumes, etc. It was with pain that I remarked much of pretention in some of these women; one acted the giddy, vivacious; another, the woman of sentiment. This last had many pruderies and grimaces. Two of them had their bosoms very naked. I was scandalized at this indecency among republicans."<sup>2</sup>

Among the many personal letters of famous folk portraying the dress of these early years are those of Mrs. John Adams, the wife of our first minister to England. In writing from London to one of her friends in America, she says:

I am a little surprised to find dress, unless on public occasion, so little regarded here. The gentlemen are very plainly dressed, and the ladies much less so than with us. 'Tis true you must put a hoop on and have your hair dressed; but a common straw hat, no cap, with only a ribbon on the crown is thought sufficient dress

---

<sup>1</sup>Earle, *Two Centuries of Costume in America*, p. 735.

<sup>2</sup>*Ibid.*, p. 735.

to go into company. I have seen many ladies but not many elegant ones since I came. There is not that neatness which you see in our ladies.<sup>3</sup>

The extravagances in American dress soon attracted the attention of the national leaders, chief among whom was Benjamin Franklin. Franklin himself was always considered a model of dignity and simplicity in dress. He, with other leaders, discussed publicly the offending extravagances. Display and show were condemned and the public urged to exercise restraint in matters of dress.

The lines of costume in these early days followed in the main the dress of the French Directory. They were long and clinging. Waists were short and necks were low. The buffont, or puffed-out fichu, so popular in France at this period, became a part of every woman's costume.

Hat styles also followed the lines of the Directory. At this time many new types of hats were evolved. The little toque, which was an outgrowth of the French turban, was one of the popular hats of the period. (C, Plate XXV.)

Especially noticeable at this time (1790) is a change which took place in the attire of gentlemen. The knee-buckles were discarded and the trousers buttoned or tied below the knee. These were similar to those worn by the gentlemen of France. Naturally with the short breeches, stockings were still in evidence and received much careful attention. The lines of the coat also changed, the fronts formed a long curve downward and back, meeting the long tails. This was the typical costume worn during the Washington and Adams administration. (B, Plate XXV.)

With the beginning of the new century, Americans began to adopt the strange costume seen in the French capital. As Paris dresses, the world dresses. Thus it has always been, century after century, since Paris established herself as the world's fashion center. The source of the wide-collared coats and swathing neckbands in America is plainly evident. The *incroyables* called themselves the Republicans of France; the Republicans of America adopted the

<sup>3</sup>Earle, *Two Centuries of Costume in America*, p. 733.

same dress. All the eccentricities of the French Republican were seen in the American dress, the tight trousers, high boots, short-waisted coat with long narrow tails, the cocked hat and tangled hair.

Not only the *incroyables* but the *mervilleuses* also were reflected in a small way in the new land. The lightest and thinnest of materials were adopted and worn throughout the severe winters. Muslin, crepe, and organdy gowns were the order of the day. Necks were low and sleeves were short. Velvet, silk, and cloth shoes alternated with those of kid. For outdoor wear little shawls and cloth capes were thrown about the shoulders. At this time, the pelisse was an indispensable item in every wardrobe. The enveloping pelisse was popular several years. In its original form it resembled the modern three-quarter jacket with close sleeves. The neck and sleeves were edged with fur for it was decidedly a winter garment. In France it resembled a cape with large openings for the arms.

The French Empire was proclaimed in 1804 and with it the dress of the period, the Empire, became the most fashionable mode of attire. This style evolved in France from the styles of the Republic and Consulate. The distinguishing feature of the Empire dress is the long flowing line, the short waist, and the absence of pressure on any

---

COLOR NOTATION—PLATE XXV

- A*—Dress, R  $\frac{3}{8}$ . Mantle, R P  $\frac{1}{4}$ . Hat, Y  $\frac{5}{8}$ ; ribbon, R  $\frac{1}{4}$ . Shoes, black. Hose, belt, white.
- B*—Coat, trousers, hat, Y R  $\frac{1}{4}$ . Hose, vest, Y  $\frac{5}{8}$ . Shoes, black; buckles, silver. Cravat, white. Ribbon, black.
- C*—Dress, white; trimmings, P B  $\frac{6}{8}$ , Y  $\frac{5}{8}$ . Hat, white; feather, P B  $\frac{5}{8}$ . Reticule, white, P B  $\frac{5}{8}$ , Y R  $\frac{1}{4}$ . Hose, white. Gloves, Y  $\frac{5}{8}$ . Shoes, black.
- D*—Dress, B  $\frac{7}{8}$ ; trimming, white. Sash, B  $\frac{1}{4}$ . Hat, R  $\frac{3}{8}$ ; plumes, B  $\frac{7}{8}$ , B  $\frac{1}{4}$ . Hose, white. Shoes, black.
- E*—Dress, pantalets, R  $\frac{3}{8}$ ; trimming, white; dots, black. Scarf, N 6; stripes, R 5, G Y  $\frac{5}{8}$ , R  $\frac{5}{8}$ . Bonnet, R  $\frac{3}{4}$ ; lining,  $\frac{5}{8}$ ; trimming, black, white; dots, black; flowers, R  $\frac{5}{8}$ , G  $\frac{5}{8}$ . Hose, white. Shoes, black. Fan, N 6, R  $\frac{5}{8}$ .
- F*—Dress, R P  $\frac{5}{8}$ ; trimming, R P  $\frac{1}{4}$ , Y  $\frac{7}{8}$ . Bonnet, R P  $\frac{1}{4}$ ; lining, R  $\frac{3}{8}$ ; feather, Y  $\frac{5}{8}$ , Y  $\frac{5}{8}$ . Muff, Y  $\frac{7}{8}$ ; trimming, white; lining, Y  $\frac{3}{4}$ . Shoes, black, white. Hose N 8.





A B C D E F

PLATE XXV—AMERICAN COSTUME—1790-1824

- A*—1804—The American adaptation of the costume worn during the French Empire and known as the "Empire."
- B*—1790—The costume of an American gentleman. The long coat is similar to that worn during the Washington administration.
- C*—1790—The American dress of this period echoes the fashion of the French Directory.
- D*—1824—The shortened flaring skirt and short waist succeeded the Empire. Breadth of shoulder began to appear about this time.
- E*—1811—A pantalet costume which appeared in a fashion plate of this date. The poke, the scarf and the fan echo the French fashion of the period.
- F*—1816—The costume of this period was incomplete without the huge muff and towering poke.

part of the body. (*A*, Plate XXV.) This was indeed a contrast to the tightly laced and boned bodices of previous centuries, and marks one of the great changes in the costume of women. By 1810 the dresses



Fig. 41. Wedding dress  
of 1813

grew shorter, just escaping the floor, and were frequently trimmed at the lower edge. Formerly the sleeves were short puffs on the shoulder; in 1813 they became long and close fitting, falling well over the hand. The wedding dress of Mrs. Sidney Grubb, who married Archibald Irwin in December, 1813, is shown in Fig. 41. The dress was made in Philadelphia in the same year. The very short-waisted bodice is laced at the back with cord, the sleeves are long and close. The only ornamentation is a trimming made of net formed into three deep petals and edged with cord. These are fastened at the shoulder with little white satin buttons. The style of slipper worn with

the gown followed the style of the period, being low and without the heel, merely the sole being thickened at the back.<sup>4</sup>

Many times during the twentieth century we have been threatened with the return of that fashion which made its appearance during the year 1800—the wearing of pantalets. (*E*, Plate XXV.) The fashion reports of this early period pronounce pantalets a “distinct novelty.” The lightness and transparency of women’s dress at this period is no doubt the cause of their adoption. At this time many of the leading French and English fashions were featuring dresses with pantalets. One of the French magazines of the period writes: “The pantaloons will have a short run, being truly ungraceful.” Again we read: “A few of our

<sup>4</sup>Sketched by courtesy of Miss Louise Booth of Peoria, Ill., a great-granddaughter of Mrs. Irwin.

*haut ton* have adopted the short frock and the trousers of the same texture edged with lace. This dress is much too singular to be graceful.”<sup>5</sup>

Certainly this was a clear forecast, for the pantalets have never been popular, and though they threaten they have never returned. At the same time that pantalets appeared, pantaloons for men's wear were ushered in.

Looking back we find the doublet and hose of Tudor times were replaced by knee-breeches and stockings. For nearly two hundred years these continued to be the favorite style of men's dress.

The nineteenth century marks the beginning of long trousers, the introduction of which was violently opposed. It is quite true that the ancient Britons, the Anglo-Saxons and Danes had worn a long garment similar to trousers, and that workingmen in both England and America wore a kind of trouser called “tongs” or “skilts.” However, it was not until the nineteenth century that the long trouser proper was generally adopted.

In the early days while Fashion was evolving the new order in men's dress, the trousers passed through many stages of development. Sometimes they flared at the ankle, and again they were close. Sometimes they were made of elastic stockinet under which false calves were worn; others were of non-elastic corduroy and called “tights.” The words of an old chronicler describes graphically the close fit of these tight pantaloons: “The pantaloons over which I wore boots, were of non-elastic corduroy. It would be unjust to the tailor to say they fitted like my skin, for they sat a great deal closer. When I took them off my legs were like fluted pillars grooved with the cords of the pantaloons.” In 1810 trousers and gaiters were made all in one.

Large cloaks were worn by the very fashionable, and many of these were lined with bright colored silk. The high crowned silk beaver completed this very correct attire.

---

<sup>5</sup>Earle, *Two Centuries of Costume in America*, p. 774.

(E, Plate XXVII.) About 1824 the first signs of the frock became visible. The long coat-tails of previous years were shortened. Both coats and overcoats were long, fitted at the waist, and slightly full skirted. Sleeves were long and snug at the wrist, the cuff extending over the hand. Collars were high and cravats of muslin and silk were worn. (C, Plate XXVIII.)

The long cloak was also one of the favorite wraps of the women of the period and was worn as generally as the pelisse and the spenser. During the summer, shawls, short mantles, like dolmans, the long silk scarf, and the ever popular spensers, a necessary part of every wardrobe, were popular. All fashion plates from 1800 to 1833 refer to spensers. (F, Plate XXV.) One under the date of 1803 reads:

Spensers are worn both for walking and carriage dress. Levantines, spotted silks, striped lutestrings<sup>6</sup> are the favorite materials. The trimming is always of satin. The Augusta spenser is one of the prettiest of dress spensers. The waist if finished in tabs is cut in the form of leaves. In velvet spensers, black, purple, and bottle green are favorite colors. The velvet is cut bias. Percale dresses are worn with these.<sup>7</sup>

The spensers, of course, varied in style. Some were shaped like a blouse, an eton, or zouave, and opened in front. (B, Plate XXVII.) They were all short, never going below the waistline. For summer the spensers were of silk and frequently trimmed with fur. The origin of the spenser is interesting. It is invariably recorded in every history of fashion. It had its beginning in a man's coat, a top-coat, invented by Lord Spenser. This gentleman, so the story runs, ventured to make a wager that he could set a fashion which would become popular inside of six months, and further, that it would be a form of dress wholly meaningless and unnecessary. He forthwith called for a pair of shears, cut off the tails of his coat close to the waist, donned his hat and went out for a stroll. He was a handsome man and one well known in fashionable

---

<sup>6</sup>Lutestring or lustring, a soft half lusted pure silk material which was generally worn.

<sup>7</sup>Earle, *Two Centuries of Costume in America*, p. 799.



circles. In a few days several London dandies were seen wearing the spensers and in two weeks all London had donned the garment. All our boleros, zouaves and Spanish jackets have doubtless been evolved from the spenser.

In 1804 the poke-bonnets appeared. These were made of straw, willow and chip; they were also to be had in Leghorn and Tuscan. These straw bonnets were worn in winter as well as in summer and were frequently tied down with a red silk handkerchief or a folded silk or lace veil. Other shapes were also popular; the "Lavinia," worn from 1805 to 1815, resembled a gypsy hat with its broad brim and scant trimming; the "Troutbeck," a flat straw hat, was popular in 1803, and the Shaker-bonnets, which were small pokes of strawboard were also widely worn. Hats and bonnets were all large and really gave more shade to the face than the diminutive parasols that covered them.

The bonnets and hats so covered the head that little of the coiffure could be seen. In 1813 the hair was simply arranged in a low coil at the back, and short curls fringed the forehead. Flowers worn in the hair were very fashionable and were not removed when the bonnets were adjusted.

Foot-gear followed the same capricious fancy as in the eighteenth century. The shoes were generally low, though the ankle-boots laced at the back had been introduced. The year 1800, further witnessed the introduction of rights and lefts in shoes, and shoe polish and shoe blackening began to be employed. Previous to this a mixture of lampblack, suet, and tallow had been used.

Toward 1820 a change began to take place in the style of dress. The ladies began to tire of the clinging Empire, and dresses began to stand out from the figure. (*D, F*, Plate XXV.) The waist still remained high, scarcely a waist at all. This, with the bell-shaped skirt, heavily festooned, and the large poke-bonnet was the first step toward the 1830 costume. Later a change in the position of the waist took place. It was gradually shifted and soon reached the natural waistline, and now with the full skirt was much more charming. (*A, B, D*, Plate XXVI.) To

keep the harmony of the *tout ensemble*, the hats and bonnets became larger and were more heavily trimmed and the coiffure also had its changes. The short front curls were arranged on each side of the parting, and the rest of the hair was fastened up with loops interwoven with ribbon, erect upon the crown of the head. For very dressy occasions, feathers of maribou and plumes were often set amid these loops of hair and ribbon. The younger women wore flowers and large tortoise-shell combs, and curls were everywhere arranged in all sorts of fanciful ways.

The leg-o-mutton sleeve appeared in France in 1820, but went out to reappear in 1830. The same sleeve appeared in America in 1827 but did not reach an exaggerated width until later. However, the sleeves continued to grow and the fullness reached to the elbow where it joined the deep tight cuff. Padding was used in the top of silk sleeves, for they could not be starched sufficiently to meet the demands of fashion. They were also frequently ornamented with large ribbon bows and broad streamers falling from the shoulders. The fashions of the thirties and forties continued to be exaggerations of the styles of the twenties. (Plate XXVI.) In 1830 skirts were short to the ankles, full and extended, and these, with the huge sleeves made all other details of the costume fade into insignificance.

To give still greater breadth to the shoulders, bretelles or revers were worn. (*B, E*, Plate XXVI.) These were shaped like a cape meeting at a point in the back and passing over the shoulders, usually descended to the waistline. Between these broad shoulders and the breadth of skirt the poor little bodice was of slight consequence. It was

---

#### COLOR NOTATION—PLATE XXVI

- A*—Dress, stripes, B  $\frac{1}{6}$ , white. Bonnet, B  $\frac{1}{4}$ ; veil, white; flowers, R  $\frac{1}{6}$ , G  $\frac{1}{6}$ . Parasol, R  $\frac{3}{8}$ .  
*B*—Dress, R  $\frac{1}{6}$ . Bonnet, B  $\frac{3}{8}$ ; ribbons, B  $\frac{3}{8}$ ; flowers, R  $\frac{1}{6}$ , G  $\frac{1}{6}$ . Belt, P B  $\frac{1}{4}$ . Scarf, P B  $\frac{1}{2}$ ; banding and fringe, black. Gloves, P B  $\frac{1}{4}$ .  
*C*—Trousers, vest, Y  $\frac{3}{8}$ . Coat, tie, hat, black.  
*D*—Dress, white. Ribbon bows, R  $\frac{1}{4}$ . Collar, white. Scarf, B G  $\frac{3}{8}$ . Hat, Y  $\frac{3}{8}$ . Ribbon, R  $\frac{1}{4}$ .  
*E*—Dress, B  $\frac{1}{4}$ .



A

B

C

D

E

## PLATE XXVI—AMERICAN COSTUME—1832-1884

- A—1842—A fashionable belle of the period wearing the full triple skirt. Many petticoats were worn to give the bouffant appearance.
- B—1832—A costume of the day emphasizing breadth of shoulder and the diminutive waist. Gloves and the flower-trimmed poke complete the fashionable dress of the time.
- C—1850—The nineteenth century marked the advent of long trousers for men. Coats were short, with long skirts. High collars and cravats of silk or muslin were worn.
- D—1884—A lady of fashion wearing the long full skirt, trimmed with bows of ribbon. The shawl at this time was very popular. Lace mitts alternated with gloves in popularity.
- E—1834—A costume picturing the fashionable bretelle and the way in which it was adjusted at the back.

fitted as snugly as possible, not a sign of a plait or a pucker being allowed to creep in. The materials were as beautiful as they were varied; embroidered cambrics were very popular, also cashmeres, muslins, and crepes. A number of evening dresses of the period were made of tulle over satin, saracenot or colored gauzes.

The period of 1830 is especially interesting in the development of American costume, for it was at this time that *Godey's Lady's Book* appeared. This was the very first woman's magazine published in the United States. It was founded by Louis Antoine Godey, who continued to be its publisher until its sale to a stock company in 1877. This publication was soon followed by the *The Union Magazine* and *Peterson's Magazine*, each taking its place among the leading fashion books of the country. In 1867 *Harper's Bazaar* was offered to the public. This fashion book was published by the noted firm of Harper Brothers of New York, which was established in 1833, and still continues in this the twentieth century to be managed by their descendants.

Toward 1837 skirts lengthened, ankles were no longer visible and only the toe of the shoe was seen beneath the undulating edge. The skirts were beginning to be trimmed with flounces and bows of ribbon and many petticoats were worn in order to attain the desired effect. (Plate XXVI.) Above all else, the waist must be exceedingly slender, and to secure such an effect without discomfort, advice like the following was given:

Have your dresses made with very loose bands, cut on the cross-way, and with a point in front, so as not to have the gathers under the point of your dress; let the petticoat be made of crinoline or wear what we call a *jupon à tournure*, which is a petticoat made of a thick and stiff cotton or thread material, not dimity, but a sort of honey comb pattern all over; this will make your dress appear sufficiently bouffant and form a proper contrast to the waist, thereby sparing the necessity and agony as well as injury of tight lacing.

In 1843 long trailing dresses were the vogue in Paris. A few years later they reached America. It is almost im-



possible to believe that ladies once trailed through the city streets. A Parisian paper of this date contains the following interesting account:

The administration of la ville de Paris has it in contemplation to do away with the scavengers in our good city, as they say it is a useless expense to pay men for doing that which the ladies so kindly perform gratis in walking through the fashionable promenades.

In *Godey's Lady's Book* for 1852 we find the following wholesome advice, which is decidedly interesting from an American point of view:

Apropos of the springtime but at the risk of incurring the disapprobation of some of our lady friends, we venture a remonstrance against the still prevalent practice of wearing trains in the street. They may remember a picture of a "Punch" of last winter, where mounted cannon were represented as novel Parisian street-sweepers, but scarcely less formidable to us seem the skirts dragging their slow length along, cleaning the crossing at the expense of neatness, comfort and good taste. In the first place American ladies are noted for their lavish street toilets. Silks and even satins that no French or English woman would think of wearing unless in a carriage or drawing room, our ladies put into constant street service. The immoderate length of dress was never *intended* by its inventor to figure in this way before the public. The French woman whose immaculate white stockings have never a spot of dust would shudder at the idea of walking with ankles—let us speak plainly—soiled and damp by the constant contact with the muddy drapery. We protest against it as a *Lady's Book*, in the name of neatness, common sense, and economy. Discoloration is inevitable; fringes are an ordinary sequence; and when such expensive silks are worn as we see at the present day, few purses can or ought to afford the outlay. Neither grace or expediency can be urged in its favor, and we trust the recent introduction of street sweepers into our large cities will preclude the necessity of our ladies' any further aid to the sanitary resolutions of the Common Council.

During the second quarter of the nineteenth century mantles were of various materials, according to the season. The long scarves of silk, crepe, and satin were trimmed with fur in winter; and the pelerines took on various forms and shapes; some just draped the shoulders, others covered the bodice and the long broad ends were allowed to hang down in front. Long cloaks, the pelisse, the redingote were also worn, and fur muffs and tippets continued in

vogue. Shawls were a general favorite at this period. For summer wear they were usually of crepe or printed berage of cashmere patterns. The center of these shawls was usually filled with a neat pattern on a white ground, and the borders were of dark rich Indian colors. Shawls, however were various; there were those with plain centers of white, green, or blue; there was the "gossamer berage" which was very delicate and beautiful; and shawls with and without fringe, all fine in texture.

Under "Fashion News" in the *London News* of 1845 is the following reference to shawls: "Nothing can be more graceful than the present promenade costume. The rich and soft cashmere shawl, so peculiarly fitted to the demisaison, alone gives a peculiar character of elegance and distinction to the toilette."

Gloves were likewise in great variety. With short-sleeved dresses they reached to the elbow, while with the long-sleeved dresses they were short, usually with one or two buttons. Frequently the gloves were edged with frills of lace or ruching. Lace mittens were also worn through the thirties and forties.

Parasols almost usurped the place of the fan in milady's favor, and seldom did she emerge for a promenade or drive without her tiny fringed sunshade.

It was about the middle of the nineteenth century that the first step was taken toward one of the great inventions of the age. In 1846 Elias Howe, Jr., secured his first patents on the sewing machine. In 1851 Allen B. Wilson and Isaac M. Singer applied for patents. These early sewing machines have been so improved that there are now special attachments for making every conceivable article of clothing. In the United States the production of sewing machines has become a gigantic industry.

Approaching the second half of the century we come upon the great innovation of the period—crinoline.

There are flagrant follies in fashion which must be endured while they reign, and never appear ridiculous till they are put out of fashion.

—*Curiosities of Literature.*

To the critical of the twentieth century crinoline is forever dubbed as one of the "flagrant follies" of the past. In fact crinoline ushered in a long line of "flagrant follies" which stand forth silhouetted in the mind as the most unreasonable and ugly fashions that ever descended upon womankind. Still, it is not left for us of today to ridicule, anathematize, and excommunicate; in its own day it met the same response. But of what avail? Crinoline became the fashion. Even though the weight of starched and flounced petticoats and yards of crinoline and horsehair would seem an intolerable burden to our American belles, it was of no moment. *Fashion must be obeyed.* The subject of crinoline



Fig. 42. The canezone

was a very serious one in Paris, and the style had its opponents as well as its supporters. Though it was ridiculed by everyone, and by husbands in particular, it became the mode when the all-powerful Empress Eugénie set the example and donned crinoline. Then its reign became universal. (Plate XXVII.)

The previous years of full and flounced skirts, balloon sleeves, and large hats had prepared the eye, if not the mind, for the innovation; and when crinoline came it seemed only the natural development. Crinoline was a stiff unpliant material, which was set around the lower edge of the under side of the skirt to keep it sufficiently propped out. The width of the crinoline varied from six to fifteen inches, and was frequently still wider. With skirts four or five yards in width there must have been no little weight to support. For those who followed the extreme in fashion, entire petticoats of crinoline were to be had; while those who did not take kindly to the new mode followed it at a safe distance by wearing flounced and stiffened petticoats of coarse muslin. These petticoats were specially adapted to summer and evening dresses of thin material.

The washable materials, such as fine muslins, cambrics, and other white stuffs, were exceedingly popular at this time, and silk also was a general favorite. In fact, the ladies of the period considered their wardrobes quite incomplete without the one silk dress. It was the day when women had their "best clothes." The silk dress was always in this class, and was worn for church, for calls, and when one "dressed up" to sit about the house on Sunday afternoons.

Not only did the hoop and crinoline create a new mode in these days, but the style of the sleeve changed as well. They are now reversed, and instead of the fullness at the shoulder, it is found at the bottom of the sleeve. (Plate XXVII.) This brought in the fashionable undersleeve, which later developed into the bishop sleeve.

In 1852 the canezou seemed to take the place of the dainty lace and embroidered capes. (Fig. 42.) This was a happy medium between the high and low corsages, and worn with skirts of different materials. Thus skirts whose bodices were partially worn could be utilized to advantage. For summer wear these were of the daintiest materials, and were edged with laces or bordered with the buttonhole stitch. With such a vogue for crinoline, the hoop seemed inevitable. Indeed our grandmothers looked quite askance at this second innovation of their time. The die was already cast. Soon crinoline was supplemented by the hoop. (Plate XXVII; Fig. 43.) A correct hoop

---

#### COLOR NOTATION—PLATE XXVII

- A*—Dress, P B  $\frac{7}{8}$ ; trimmings, P B  $\frac{1}{4}$ . Hat, P B  $\frac{7}{8}$ ; trimming, R  $\frac{5}{7}$ , R  $\frac{1}{4}$ . Gloves, Y  $\frac{5}{8}$ . Parasol, P B  $\frac{1}{4}$ , P B  $\frac{7}{8}$ , R  $\frac{5}{7}$ .  
*B*—Skirt, B  $\frac{1}{2}$ ; trimming, R  $\frac{1}{4}$ , black. Zouave, R  $\frac{1}{4}$ ; trimming, black. Blouse, white. Belt, B  $\frac{1}{4}$ ; buckle, gilt. Hat, black; feather, white; buckle, gilt. Gloves, Y  $\frac{5}{8}$ , black stitching.  
*C*—Dress, Y G  $\frac{5}{8}$ ; trimming, Y G  $\frac{5}{8}$ . Bonnet, white; trimming, Y  $\frac{5}{8}$ . Gloves, Y  $\frac{5}{8}$ . Collar, white. Puffs in sleeve, white.  
*D*—Dress, N 7; trimming, N 7. Bonnet, white; flowers, Y  $\frac{5}{8}$ , white, G  $\frac{5}{4}$ . Puffs inside sleeve, white. Gloves, Y  $\frac{5}{8}$ .  
*E*—Coat, trousers, N 3. Collar, cravat, white. Cape, N 3; lining, R  $\frac{5}{8}$ . Gaiters, N 6. Shoes, black.





A B C D E

PLATE XXVII—AMERICAN COSTUME—1820-1865

- A—1865—A belle of the hooped period. Diminutive hats and parasols were worn with this voluminous dress.
- B—1865—A lady of fashion wearing the hooped skirt and the eton, a variation of the spenser. Gloves are always worn when milady walks abroad.
- C—1850—A costume of the crinoline period showing the beginnings of the sleeve, full at the wrist.
- D—1860—A fashionable dress with dolman-like sleeve set in low on the shoulder.
- E—1820—An American gentleman of this period reflects in his dress much of the French influence. He wears the high neck-cloth, the broad-collared coat, the long tight trousers and the fashionable cape lined with bright colored silk.

consisted of "four narrow steels each covered with tape and run into the muslin or calico petticoat. The one nearest the waist usually measured one and three-quarter yards in length, while that at the lower edge of the skirt was two



Fig. 43. The hoop

and one-half yards in length. These steels with the exception of the top hoop were not allowed to meet in front, but a space of a quarter of a yard was allowed." Later, hoops were designed in various ways, many of them consisting of several covered hoops diminishing in size toward the waist, and held together by strings of broad tape reaching from the lower edge to the belt.

The year 1865 marked a change in shoes. They were now made entirely of kid or patent leather, and frequently the two were combined. The lacing was over the instep, the heels were high, and gradually became still higher.

In the early part of the sixties the hair was fastened up in a shapeless mass and held in a net. Silk nets were extremely chic, and many were spangled with jet. Frequently the front hair was parted in the center, combed down on each side making a loop over the ear, or arranged in masses of ringlets. Later the graceful side curl became the fashion and with it flowers were often arranged in the hair. (Fig. 44.)

Bonnets continued to be worn; in fact the entire nineteenth century seems to be a period of bonnets. Hats, of course, were frequently worn, but the bonnet held first place. The size and shape of bonnets varied from time to time. Sometimes the fronts were fitted close to the head, and again they were very open. Frequently the open bonnets were trimmed with quilling of lace and ribbon just inside the brim, suggesting the colonial fashion of the little frilled caps under the hats. In summer, bonnets of tulle and fancy straws were worn. These were often large at the back, with curtains of lace covering the hair. In winter they were of velvet and beaver, and trimmed with fur, laces, and ribbon. Toward 1863 the bonnets became tall and pointed in front.

One of the novelties of the mid-century was the black silk sacque, which was worn by matrons and the more youthful as well. These were made both close-fitting and loose, with wide sleeves set in low on the shoulders, and were trimmed with fringes, lace, and ribbon.

There was a decided taste for jewelry at this period; ear-rings, brooches, necklaces, and bracelets were in vogue. In place of bracelets, black ribbons were frequently worn about the wrist.

The hoop-skirt and crinoline continued to be worn well on toward 1870. About this time skirts were cut in gores. This was approved as a point of economy. The sixteen or seventeen yards of material necessary for a correct gown were now reduced to ten or twelve. These were worn lined with



Fig. 44. Coiffure of the early '70's

horsehair or over horsehair petticoats, for the extension was still desired even after the steel hoop had lost somewhat in favor.

Then came the startling tournure, or petticoat bustle. At this time bustles were considered an absolutely indispensable part of all kinds of dresses, and often formed part of the skirt. Two shirrs, like those which had been used in the old-fashioned hoop-skirt, were run in the skirt linings, and served to hold the steel springs. When not a part of the skirt they were adjusted separately to the figure. Some of those of the period were made of a series of four or six spiral wires, resembling springs, about four inches in diameter and placed side by side vertically. These were encased in cloth, and attached to an adjustable belt. Bustles were worn high, and bustles were worn low. They were combined with the large hoop, and again with the small hoop. (*A*, Plate XXVIII.)

In a fashion book of the time one reads: "The newest bustles are made of eight narrow frills of barred muslin or haircloth, very full, pleated on a V-shaped foundation of the same material that is curved into shape by strings tied across it—not by the objectionable bone or steel hoops. If anything more is needed, one or two steels are put in casings across the back breadth of the dress skirt."

A hat shape similar to the gentleman's round hat was worn, and on this was built up a pile of lace, flowers, and feathers to adorn the head. A sort of queue composed of

---

#### COLOR NOTATION—PLATE XXVIII

- A*—Dress, N 6; trimming, sash, P B  $\frac{1}{4}$ . Hat, N 6; flower, R  $\frac{3}{8}$ , G  $\frac{5}{8}$ ; ribbon, P B  $\frac{1}{4}$ . Parasol, N 6, P B  $\frac{1}{4}$ . Gloves, Y  $\frac{1}{4}$ .  
*B*—Polonaise, basque, Y  $\frac{1}{4}$ . Skirt, basque front, R P  $\frac{3}{8}$ . Embroidery, white, Y  $\frac{1}{4}$ . Hat, Y  $\frac{1}{4}$ ; ribbon, R P  $\frac{3}{8}$ ; flower, R  $\frac{3}{8}$ , G  $\frac{5}{8}$ . Parasol, N 4, white. Shoes, black. Gloves, Y  $\frac{1}{4}$ .  
*C*—Plain material, P B  $\frac{3}{8}$ ; figured, P B  $\frac{5}{8}$ , P B  $\frac{3}{8}$ . Hat, P B  $\frac{5}{8}$ ; ribbon, P B  $\frac{3}{8}$ ; plume, P B  $\frac{1}{2}$ . Gloves, Y  $\frac{1}{4}$ .  
*D*—Gown, B  $\frac{1}{4}$ . Bretelles and trimming, white. Gloves, white. Fan, Y  $\frac{1}{4}$ , black.  
*E*—Skirt, Y  $\frac{1}{4}$ . Blouse, G  $\frac{1}{4}$ . Frills, collar, white. Hat, Y  $\frac{1}{4}$ ; flower, R  $\frac{3}{8}$ , G  $\frac{5}{8}$ ; ribbon, G  $\frac{1}{4}$ . Parasol, G  $\frac{1}{2}$ , G  $\frac{1}{4}$ . Gloves, white.  
*F*—Trousers, black, N 4. Coat, black, N 4. Hat, shoes, black. Gloves, N 6.





A                      B                      C                      D                      E                      F

PLATE XXVIII—AMERICAN COSTUME—1873-1897

- A*—1873—The fashionable bustle dress which succeeded the hoop. The sleeves continue large at the cuff.
- B*—1883—A costume showing the popular vogue for combining materials. The draped overskirt and bustle are characteristic of the '80's.
- C*—1878—A costume picturing the fashion for combined materials in dress. The standing collar of linen and the bowtie were worn at this time.
- D*—1895—A lady wearing the princess dress, with skirt and bodice in one with no line to mark the waist.
- E*—1897—Toward the turn of the century, skirts of one color and material, and waists of another.
- F*—1895—The general costume of men, which changed very little during succeeding years.

flowing ends of lace and ribbon was fastened behind, over which fell flowers and flexible stems. (Fig. 45.) With the high hats that continued to be worn with the lofty chignon and the excrescences of poufs and loops, milady was expected to bend slightly forward in walking. Indeed she



Fig. 45. Hats of the '70's

*must* do so in order to maintain her equilibrium! Everybody affected the Grecian bend! The degree of grace with which the tilt was managed was a passport to the realm *distingué*.

The dress now became a construction of flounces, fringes, loops, and puffings; and the great mass trailed a yard or two after the wearer. And this was fashion! (Fig. 46.)

By way of variety, came the bustle-skirt, combining a bustle and petticoat in one. These had a hoop on the back that stopped at the sides, and tapes attached to the sides were tied underneath the hoop to give the desired effect. This particular style was known as the "tilter." Later tilters were made without the petticoat combination.

In those days of bustle and elaborately flounced and looped skirts, shoulder straps were furnished to support the great weight. These were frequently of elastic ribbon, sewed permanently on the skirt back, and were passed over the shoulder and hooked or buttoned to the belt in front. These straps transferred the weight from the hips to the shoulder.

The hair still continued to be plaited over pads in a chignon worn high upon the crown of the head. False hair was generally worn, and so great was the demand for these tresses from foreign heads that great quantities were imported from France. This hair was chiefly procured in Auvergne, Normandy, and Brittany, and hair-cutters made a special business of collecting it in April and May. The demand for false hair naturally raised the price, and those whose purses were limited contented themselves with tow and other materials commonly used in lieu of hair.

From '70 to '75, while the hoop was on the wane, the silhouette changed. It was difficult to give up the full skirt; women had become so accustomed to yards and yards of material that it was a real trial to adjust themselves to less.

Gradually all the fullness of the skirt was gathered at the back. The skirts were drawn so tightly over the knees that walking was difficult. That is the period known as "tied-back" time. (Fig. 47.) With the large hoop losing in popularity, and the tied-back effects gaining, the bustle gradually assumed more important proportions. The bustle, both with and without a small hoop, was worn well into the next century. In fact, the distinguishing characteristic in the costume of the '80's is the bustle, the boned basque, and the looped polonaise. (Fig. 48; *B*, Plate XXVIII.)

Fashion always swings from extreme to extreme, and it is not surprising that, following the hoop, gowns which



Fig. 46. Hoop, tilter and trail  
(Courtesy Marshall Field & Company)

moulded the figure became the last word in style. About 1882 the fashionable "jerseys" were introduced. In the early eighties these were of an elastic cashmere fabric similar to that known as stockinet, and closely fitted the figure. Their elegance of shape and finish was combined with a



Fig. 47. "Tied-back" time (After Kretschmer and Rohrbach)

comfort and freedom of action in marked contrast with the preceding fashions. The jersey bodices were exceedingly popular, and as largely worn in America as in Europe, where they were adopted by the children as well as by their modish mothers.

So much for the bodice. The width of skirts was also reduced till they too were very much narrower. Soon costumes began to be designed in two colors, or in two different materials. (*B, C, Plate XXVIII.*) It was usual to have the skirt of one hue and the polonaise of another; or, a plain fabric for the basque, with flowered stuffs for the skirt. However, this was frequently reversed, the flowered or figured materials being used for the larger part of the dress and the plain for the skirt.

Brocades, velvets, and silks were in high favor and these were elaborately trimmed with laces, fringes and passementerie. The thinner and more delicate materials were worn in the warmer season—printed India pongee, light-weight foulards, French cashmeres, and Chinese crepes.

Bonnets were still the last word from Paris. There were horsehair bonnets, proclaimed the "French novelty"; kid bonnets, in the natural leather color, the crown moulded into form and the brim covered with folds of velvet and felt; bonnets of velvet and silk in endless variety.

The dolman was a favorite out-of-door wrap. These varied in length and were made of the finest brocades, silks,



and satins elaborately trimmed with puffing of silk, fringes, and passementerie. Outdoor jackets with short backs and long fronts were also worn.

Toward the end of the seventies several new movements in dress took place in London, Germany, and France which were destined to play no small role in the costume of succeeding generations.

The Æsthetic Movement had its home in London. The followers of this movement were interested not only in dress, but in art generally. The existing order of things in home furnishing, surroundings, civic conditions, as well as in dress were vigorously attacked. Wonderful were the changes wrought. Color and color harmony began to have a new meaning. The more subtle hues which were hitherto known only to the few, began to appear. The most delicate hues as well as



Fig. 48. The bustle (After *Harper's Bazaar*, 1883)

the richest tones in pleasing variety were now produced by the English dyers, who had adopted the ancient custom of using vegetable dyes.<sup>8</sup>

The Dress Reform Movement<sup>8</sup> began about the same time in Germany. It started with the idea that wool was the only proper covering for the human body. Everything must be wool, even the handkerchiefs. This period marks the beginning of the famous Jaeger Company. Previous to this the underclothing in both summer and winter had been of cotton, and naturally the soft warm wool was in great demand. Indeed it was impossible to keep up with

<sup>8</sup>Georgiana Hill, *A History of English Dress* (New York: 1893), p. 277.

the orders for woolen sheets, stockings, gowns, and materials generally. It was at this period that the ever-popular union-suit with its equal distribution of weight over the figure, was introduced. This movement merged into the agitation for a new system of dress. All the shortcomings of the modes of the day were taken up and vigorously attacked and great indeed was the feeling directed toward the corset. This new crusade was supported by doctors and sanitariums alike. The leaders were most radical, taboos the corset as an instrument of torture. Further, they advocated the "divided skirt" as the only proper, sane, and sanitary garb for women. The new type was freely discussed and even demonstrated by a few of the more daring. The innovation succumbed, however, when she who ventured forth was stigmatized as "the new woman."

Though the aim of the movement was not entirely achieved, the discussion did much to awaken people to some of the existing incongruities of dress.

Just about this time the entrance of women into the athletic world did much to forward the movement toward a comfortable and easy dress. This was an English influence that had its effect in both France and America. English and French women rose early, donned short skirts, a comfortable blouse or jacket and stout shoes to walk, ride, or hunt. In America cycling, golf, and tennis, which necessitate an easy and comfortable dress, were the favorite sports of women. Time was when vigorous exercise of any sort was thought unfitted for women. A five mile tramp was unheard of, and cycling considered shocking beyond words; a young woman seldom engaged in any exercise more energetic than a prosaic game of croquet. Indeed, our grandmothers would stand aghast at the modern gymnastic costumes, the tennis frocks, boating flannels, and the "up-to-date" riding togs. Fig. 49 shows a riding habit of the seventies.

The entrance of women into the business and professional world has had an effect undreamed of in previous

centuries. Women began to adapt their clothes to their manner of living and their needs, demanding that they be useful as well as beautiful. Each of these influences in turn, has been most potent in forcing the trend of fashion toward greater simplicity. Moreover, it is the wonderful nineteenth century that gave birth to that great invention—the paper dress-pattern. It is this paper pattern, so universally employed today, that has contributed more directly than any other one influence to the development of feminine dress. *Pomeroy's Democrat* of 1871 said: "The sewing machine has



Fig. 49. Riding habit of the '70's  
(Courtesy Marshall Field & Company)

done more than the piano to happyize our homes, and following the sewing machine has come the Butterick pattern."

In July of the same year, the *Home Journal* comments: "They should be ranked with the benefactors of mankind, this firm that has worked out the problem of clothes."

It is due to these pioneers in the fashion world, Ebenezer Butterick and his wife Ellen Butterick, that this problem of the paper dress-pattern was planned and carried out.<sup>9</sup> Before this there had been only intricate diagrams which required the practiced hand of the skilled to trace and cut. Naturally this limited beautiful and well-made clothes to the more wealthy women of the period.

These interesting paper patterns began with an idea—an idea suggested by Ellen Butterick to her husband. One day she modestly proposed that a paper pattern for a

<sup>9</sup>*Delineator*, November, 1910.

child's dress might be a boon to mothers. The idea developed, resulting in a drafted and cut pattern for a child's Garibaldi suit, which was the first paper pattern offered to the world. Needless to say, all children were soon wearing Garibaldi costumes. Then came the desire for women's patterns. This soon became a demand, for the advantages of the child's paper pattern was being recognized the world over. In 1871 over six million paper patterns were sold.

Along with the paper pattern was the increased circulation of the popular fashion books, which not only pictured the present but anticipated the coming types, and discussed materials, trimmings, and modes in general. Thus the creating of fashions was becoming of greater interest to an ever widening circle. Moreover personal taste and decision were entering into the choices of line and color and the stern decrees of Dame Fashion were less blindly followed.

Another inspiration toward fashion-creating was awakened in France when the Historical Exhibition of the Costume of France was held in 1878. This was indeed a history of costume in concrete form. Curiosities which had hitherto been hidden away in private collections were dusted and presented. Many of the objects were of special interest in showing the earliest manufactures of France. There were garments of the Middle Ages and the early Renaissance, and of the sixteenth and seventeenth centuries. These were shown not only because they were objects of history, but as subjects for study. There were dress ornaments, bracelets, rings, pins, brooches, and ear-rings; women's hoods of various types, a fashionable doll dressed in the costume of the Medici period; women's hawking-gauntlets in chased steel, exquisite fans, patch-boxes, antique bags, and purse clasps, beautifully chased betrothal rings, diamonds in settings of old silver, curious Roman trinkets and quantities of rare Egyptian jewelry dating from the time of the Caliphs. Moreover, the Scandinavian Ethnological Museum of Stockholm forwarded a series of remarkable costumes dating about 1820. This was a wonderful collection and proved a great incentive to manufac-



turers, designers, milliners, and all concerned with the production of beautiful wearing apparel.

It was the growing taste for extreme simplicity that created the tailor-made gown, which even today holds first place for smartness and luxury as well. Though the tailored costume appeared simple, it was very expensive, for every detail must be perfect. Side by side with all this simplicity there was also much gay attire.

The decided taste for sports of all kinds did much to make the popular shirt-waist even more popular. These waists during the early days were very simple in line, full in front, with yoke backs and shirt sleeves. Frequently the standing linen collar was worn with the bow tie. This fashion for odd waists led to a taste for colored waists of red, blue and green plaid or stripes with black and white or dark-toned skirts. The wearing of skirts of one material with waists of another became quite the mode (*E*, Plate XXVIII), not only for everyday wear but for evening and reception toilettes as well. Many of these fancy-dress waists were of silk, grenadine, and other transparent fabrics, and lavishly decorated with lace and ribbon.

During the nineties, skirts attained a voluminous breadth, reaching in many instances seven to nine yards. Circular skirts divided honors with those cut gored, but whether circular or gored they must fall in great flute-like folds. (*D*, *E*, Plate XXVIII; Fig. 50.) To secure the correct fall of these great tubular folds, the skirts were lined with canvas, or with a heavy unpliable material called *fibre chamois*.

The sleeves again kept pace with the skirt, and reached the most extravagant dimensions. These too were partly lined with *fibre chamois* to make them sufficiently bouffant. Width of shoulder was the last decree of that ever youthful old lady, Dame Fashion, and to emphasize this width, berthas and fichus of various designs, laces, and ribbons were added to the shoulders. (Fig. 50, a, b, c.)

Fashion had set her seal upon all these little accessories of dress, and yokes, collars, fichus, and berthas were in

great variety. These were kept in readiness and were often adjusted to an otherwise plain bodice, giving it that necessary touch to bring it within the realm of the fashionable.



Fig. 50. Fashions of the '90's

To the very turn of the century, skirts continued to be of great width. Toward '97 the new distinctive note in the dress was the sleeve. In contrast with the sleeve of preceding years, it became close-fitting, with a large puff or cap at the top. (Fig. 50, d and f.)

Width of shoulder was still desired, consequently ruffles of lace, ribbon, and other material edged the yoke and extended over the top of the sleeves, which were often wrinkled *mousquetaire*. With these sleeves all collars were worn high, closely encircling the throat, and frequently edged with a frill of deep lace or plaiting which stood high at the back.

The new materials at the end of the century were various. There were æolion, a mixture of silk and wool, Pompadour sateens, jaconet, satin stripes, India prints, Pompadour foulards, striped grenadines, and Italian silk, Turkish, Japanese, Indian, and Persian stuffs, embroidered in silk and glistening colors. Vandyke red, lotus-blue, and an undecided blue-green called Venetian heliotrope were among the fashionable hues. Well on toward the end of

the century costumes continued to be made of combined materials and colors.

Both hats and bonnets were worn, made in smooth straw and coming down close on the forehead. All head-gear was profusely trimmed with feathers and flowers. Golden poppies, tulips, magnolias, bachelor's buttons, and roses of every shade graced the covering of milady's bonnet.

A decided change in the arrangement of the hair marks these last years. The coiffure becomes more elaborate, and steadily grows to larger proportions until one almost wonders whether the extravagance of the eighteenth century threatens to overtake us. The Jubilee (1897) revived many of the early Victorian styles, and is said to be responsible for the new arrangement of the hair. It is now drawn up loosely over large cushions, that reach across the brow from ear to ear and secured at the back with pins and combs. To give a light and waving appearance the hair was often curled with hot irons or by means of a curling fluid. With this mass of waved hair raised over the huge cushions, milady came forth *à la Pompadour*. She who possessed a wealth of hair found herself highly favored, while she whose locks were scant took refuge in the "acquired."

The nineteenth century is a wonderful period in many ways. It is proudly marked as an age of science and progress. Many and rapid were the developments in every sphere, and so complete was the change in mental attitude and outlook upon life, that the nineteenth century seems a world apart from all preceding time. The growing conception of the appropriate in dress has completely changed modern costume. The new ideas regarding physical education, the opening of the business world, and professional life to women, the love of travel, and the complexity of modern living, have all played a part in revolutionizing the dress of both men and women. Woman has now taken her place in all the world's activities, and her dress is adapted to the life she leads. At the end of the century,

the trend is marked by a simplicity of elegance and good taste, the gratifying outcome of the refining process through which ideas of dress have passed during this epoch-making nineteenth century.





## CHAPTER XII

### AMERICAN COSTUME

(1900)

IF "VARIETY is the spice of life" we must admit that the world of today is well seasoned. Never has costume been so varied and fashions so ephemeral as in the opening years of the twentieth century. Though only a few years of the century have passed, so numerous have been the modes introducing wide variations in costume, and so immediate their adoption, that only one conclusion may be drawn—Dame Fashion still rules the world of dress. Indeed, so potent is her word that even the most conservative must submit in a measure to her decrees. Her sway is so universal that to be out of the fashion is to be out of the world!

Oh, mighty fine it is to be the slave  
Of fashion! Mighty fine it is to brave  
Old Common Sense, that antiquated snob,  
Mix in gay crowds, and mingle with the mob,  
Whom love of show and love of pleasure, too,  
Lead where they can be rather viewed than view!

Yes, to live thus, in some sea-beaten spot  
Is truly charming while the weather's hot,  
And while—kind friends, excuse this truthful song—  
Sport is the judgment and the purse is long.

—PARKE BENJAMINE—A humorous satirical poem read before  
a fashionable audience in Newport in 1852.

It is true that her scepter's sway is not so haughtily autocratic as in previous years. No, indeed, she is tact itself, and now deftly subordinates her soaring instincts to the feminine needs of her court. For woman has asserted herself, and the intolerable, the uncomfortable, and the grotesque are looked upon askance.

Fashions often overlap from century to century, the opening years of the new era frequently clinging to the preceding mode. So at the beginning of the century the

dominant types of the previous years still survived. The full skirt grew more clinging, the upper part fitting the figure snugly, and then flaring out into a bell-like arrangement at the lower edge. These skirts were known as the "serpentine" or "morning-glory" skirts. (A, Plate XXIX.) The fitted upper portion was often held back by elastic straps, and frequently the lower edge of the skirt became a rippled circular flounce. It was at this time that the "dip" became fashionable. The belt of the skirt was cut slightly lower in the front and the downward tendency was shown in the girdle and in the fall of the skirt. Jackets, blouses, and sleeves were all very snug in fit; indeed the figures of the period resemble the ungraceful and unlovely hour-glass type. (A, Plate XXIX.)

By 1904 skirts cut *en forme* may be said to have disappeared from the horizon of good style. At this period the skirts began to grow wider from the waist down, falling in an easy graceful sweep over the hips, forming broad undulations about the feet. (B, D, Plate XXIX.) The flowing line was the last word of fashion. Many of the skirts were as much as six or seven yards around the lower edge. With the flowing skirts, waists became fuller and more easy in fit with long shoulder effects. All trimming aimed to give breadth and slope to the shoulders. Horizontal designs rather than vertical, and epaulettes added to the shoulders, were all employed to secure this distinctive breadth. (B, Plate XXIX.)

---

COLOR NOTATIONS—PLATE XXIX

- A—Skirt, basque, Y R  $\frac{5}{8}$ . Blouse and collar, white. Hat, Y R  $\frac{7}{8}$ ; trimming, R  $\frac{5}{8}$ , R  $\frac{3}{4}$ . Parasol, R  $\frac{3}{4}$ .  
 B—Gown, R  $\frac{5}{8}$ ; guimpe and lace in sleeves, Y  $\frac{5}{8}$ ; ribbon, black. Hat, G Y  $\frac{5}{8}$ ; trimming, R  $\frac{3}{4}$ , R  $\frac{5}{8}$ , G Y  $\frac{5}{8}$ ; ribbon, black.  
 C—Coat, trousers, P B  $\frac{3}{4}$ , N 5. Skirt and collar, white. Tie, N 8, P B  $\frac{3}{8}$ .  
 D—Gown, Y  $\frac{5}{8}$ ; girdle and trim, G Y  $\frac{5}{8}$ ; guimpe, Y  $\frac{5}{8}$ ; embroidery, Y  $\frac{5}{8}$ , G Y  $\frac{5}{8}$ , R  $\frac{5}{8}$ . Hat, G Y  $\frac{5}{8}$ , plumes, G Y  $\frac{5}{8}$ . Gloves, white.  
 E—Jacket, skirt, Y  $\frac{5}{8}$ ; stripe, black. Blouse and cravat, white. Hat, Y  $\frac{5}{8}$ ; plume and ribbon, black. Gloves, shoes, hose, white.  
 F—Jacket, skirt, P B  $\frac{3}{8}$ . Blouse, cuff and collar, white. Tie, P B  $\frac{3}{8}$ , N 8. Hat, Y R  $\frac{7}{8}$ ; ribbon, P B  $\frac{3}{8}$ ; flowers, Y R  $\frac{5}{8}$ , Y  $\frac{5}{8}$ , G Y  $\frac{5}{8}$ . Purse, N 8, P B  $\frac{3}{8}$ .



A                      B                      C                      D                      E                      F

PLATE XXIX—AMERICAN COSTUME—1902-1915

- A—1902—The “serpentine,” or “morning-glory,” skirt. Jackets, blouses and sleeves were all very close in fit.
- B—1907—The distinctive breadth of shoulder is attained by horizontal trimmings, epaulettes and bretelles. The lace yoke, or quimpe, was indispensable.
- C—1915—The street and business suit. The coat is short, comfortably loose and double-breasted.
- D—1908—A costume with overdress. Large hats and a generous arrangement of the hair accompanied this period of the flowing line.
- E—1910—The tailored suit. The skirt was known as the “hobble-skirt.” Cravats of lace and fine materials were worn.
- F—1907—The tailored suit, showing the tight-waisted coat and full gored skirt. Waists were of linen and silk.

No matter how simple or how elaborate one's wardrobe, the *trotteur*, or walking-skirt was indispensable. The shirt-waist had proved itself of such value that its complement, the short skirt, was to be found in every woman's wardrobe. The walking-skirts were always finished in tailored effects and usually of serge, cheviot, or tweed.



Fig. 51. Shirt-waist suit

The natural outcome of the shirt-waist and the short skirt was the shirt-waist suit. (Fig. 51.) No longer were the light waists and the dark skirts the mode; the fashionable women of the period had their shirt-waist costumes of silk, mohair, and other light-weight materials made *en suite*, and a most comfortable, charming fashion it was.

The women of today owe much to the innovation the shirt-waist has made in their manner of dress. Its general comfort is evident and its loose lines have been adapted to the more elaborate blouses of chiffon, lace, and other delicate materials. The strictly tailored suit, coat and skirt, continued to hold its undisputed sway and it was not until 1914 that the almost rigid effects were somewhat softened by the vogue for the semi-tailored. During 1906 and 1907 the plaited skirt was the popular one for the tailored suit, and the jackets, all of close fit, were either short or three-quarter as milady preferred. (F, Plate XXIX.)

In 1907 the French influence was especially seen in the tone and beauty of the colorings offered. Taupes, lovely smoky tones, purples, yellows, browns, and peacock were the hues particularly sought and with these were combined trimmings of hand embroidery, beaded design, and fringe.

This was the day of high and close-fitting collars and guimpes. (Plate XXIX.) The linen collar was invariably worn with the shirt-waist, but with the more elaborate attire



guimpes of finest laces gave the daintiest touch to the costume.

The hats of these early days of the century were set well up on the head and were often raised by means of a bandeau. Plumes had a triumphal career, and the barbaric use of birds and wings was given second place. This use of birds and paradise feathers was temporarily discarded because of the satire directed against it; and it was the fond hope of many that this style would never again be approved by fashion's decree. However, a few years later it peeped above the horizon of fashion for a brief period in the guise of "chanteleer." (Fig. 52.)

Again it is an instance of the stage setting the mode, for it was the popular and unique drama *Chantecler* that set the barnyard fowl upon the heads of dainty woman. Women audaciously wore chanteleer perched upon their pretty heads, the tail feathers drooping at the back, and the head erect ready to announce his presence.

We are amused today over *la Belle Poule* and the *pouf au sentiment* of Marie Antoinette, but can these be more ridiculous than the poultry head-gear of our enlightened women of the twentieth century?

No longer can it be said that one type of hat is the fashion, for hats are as various as the occasions for wearing them. The curves and graceful lines of the Gainsborough effects were especially adapted to the long clinging diaphanous gowns. The Gainsborough is a large picturesque type of hat that sat tilted upon the head. It has become associated with the name of the artist Gainsborough, because he painted the portraits of famous women of his day, wearing this very becoming large hat.



Fig. 52. Chanteleer

Just the airiest, fairiest, slip of a thing,  
With a Gainsborough hat, like a butterfly's wing  
Tilted up at one side with the jauntiest air,  
And a knot of red roses sown under there  
Where the shadows are lost in her hair.

Then a cameo face, carven in on a ground  
Of that shadowy hair where the roses are wound.

—JAMES WHITCOMB RILEY, *Love Lyrics*.

The small toque simply trimmed was indispensable with the tailored costume or shirt-waist suit. Further, sports and outdoor life had created head-gear appropriate to its own world. The broad brimmed sailor was a general favorite for the warmer part of the year, and later it was replaced by soft white and light colored felts in various styles.

The following year (1908) the emphasis fell most decidedly upon the tunic or drapery, a Greek idea which was sought in both evening gowns and day toilettes. (*D*, Plate XXIX.) The most pronounced features of these draperies were the overskirts, which offered many possibilities for trimmings, for they were invariably bordered in one way or another. With these flowing robes, a taste for large hats and a most generous arrangement of the hair was indulged in. Crowns were high and trimmings were high. This tendency toward height gave the final touch to the costume inclining toward the Empire or Directory. The long curve from the tip of the hat to the lowermost edge of the flowing skirt produced that pleasing and picturesque effect which made perfect the *tout ensemble*.

Toward 1910 we find another revolution imminent in the matter of dress. The change began to be visible in Paris toward the latter half of 1908 when the question, "to be or not to be," was fiercely debated by the *couturières* and the public. The birth of a new fashion often wavers long between oblivion and the vogue, and it was not until the matter had been definitely settled that the new mode reached America.

The most pronounced innovation was the skirt which had shrunken to almost unbelievably small proportions. It became flat and narrow, ignoring the hips and keeping the lines of the figure as straight as possible. The silhouette had completely changed, skirts were not only narrower and high-waisted, but shoulders were narrower, and sleeves were narrower, in fact the styles of the Directory, the Consulate and the Empire were again becoming established. (*E*, Plate XXIX.) Not only were the skirts narrow, but they reached such exaggerated scantiness that many of them measured only from thirty-two inches to a yard and a half at the lower edge. In fact they were as narrow as they possibly could be and the wearer be able to walk. The hobbling, toddling gait of the geisha was fashionable because it could not be otherwise. This gives some color to the theory that the narrow skirt descended upon us from the Japanese.

Never since the time of the Louis' had fashion been so assailed as was this close-fitting skirt. It was ridiculed as the "hobble-skirt," the "halter-skirt" and the "sheath."

Hobble, hobble, little skirt,  
How I wonder what thou wert.  
Perchance, maybe a papa's pant  
Now for him a trifle scant.

—From a set of parodies issued by the Carol Press, Boston.

Pulpit and press alike heaped ridicule and abuse upon the mode. And yet, Fashion will do as Fashion always has done, the more she is assailed, the more she asserts herself. Consequently the hobble-skirt continued, became even more scant, until it was impossible even to hobble; then my fair lady shocked the pulpit and press still further by slashing the binding of the lower edge. Sometimes the slash was at the sides, sometimes every seam was left open to knee depth and sometimes only the front and back were slashed. These openings were often filled with a narrow plaited panel of silk, cloth, or chiffon. However, this was not always the choice of the feminine world, for many adopted the

bright colored silk petticoat and the more daring ventured the satin trousers of the Turkish harem.

No wonder the world stood aghast! No wonder bills were introduced into the state legislatures aiming to correct and regulate woman's dress!

But not so ruthlessly is Dame Fashion's world invaded. In the fate of one such bill introduced into the Virginia legislature we may read the fate of all—"It is a shame," said delegate W. M. M. of Richmond today, commenting on the defeat of his bill in the Virginia legislature regulating woman's dress, "I introduced the measure in all seriousness and I insist that it was worthy of better consideration than it received at the hands of the house, which killed it with an overwhelming vote."

With the narrow skirt came the collarless blouse with the open flowing sleeve. This sleeve resembled that worn by the peasants of Roumania and Bulgaria. These simple blouses were of soft clinging materials which emphasized the fine lines of the shoulder and the arm.

With this scant and narrow silhouette there is only one possibility for hats—they were high and set well down over the head. (*E*, Plate XXIX.) The coiffure was very elaborate, and again those not favored with abundant hair took refuge in the "acquired." One of the charming arrangements of the period was the heavy braid twined round the head in peasant fashion.

The narrow skirt continued to be played upon in varying ways, as if Fashion were toying with the old in the effort to

---

#### COLOR NOTATION—PLATE XXX

- A*—Costume, Y  $\frac{1}{2}$ ; trimming, B  $\frac{1}{4}$ . Collar, white; tie, B  $\frac{1}{4}$ . Hat, Y  $\frac{1}{4}$ ; trimming, N 7, B  $\frac{1}{4}$ . Gloves, Y  $\frac{1}{2}$ . Shoes, Y  $\frac{1}{2}$ . Parasol, N 6, B  $\frac{1}{4}$ .  
*B*—Costume, G Y  $\frac{1}{2}$ . Collar, Y  $\frac{1}{2}$ . Girdle, G Y  $\frac{1}{2}$ . Hose, shoes, hat, black. Jewels, gold, R  $\frac{1}{4}$ .  
*C*—Costume, R  $\frac{1}{2}$ . Frill inside collar, R  $\frac{1}{4}$ . Hat, Y  $\frac{1}{2}$ ; trimming, G Y  $\frac{1}{2}$ , P  $\frac{1}{4}$ . Gloves, white. Hose, N 8. Shoes, black.  
*D*—Costume, Y  $\frac{1}{2}$ ; trimming, B  $\frac{1}{4}$ ; lace, silver. Gloves, white. Hose, Y  $\frac{1}{2}$ . Shoes, bronze. Headband, Y  $\frac{1}{2}$ , Y  $\frac{1}{4}$ , R  $\frac{1}{2}$ ; feathers, Y  $\frac{1}{2}$ , Y  $\frac{1}{2}$ .  
*E*—Coat, trousers, shoes, black. Shirt, vest, collar, tie, white.  
*F*—Costume, G Y  $\frac{1}{2}$ ; dot, N 6. Sash, G Y  $\frac{1}{2}$ . Fan, black N 5, R  $\frac{1}{2}$ , G Y  $\frac{1}{2}$ , Boutonnière, R  $\frac{1}{2}$ , B G  $\frac{1}{2}$ .





A B C D E F

PLATE XXX—AMERICAN COSTUME—1913-1916

- A*—1916—The short, full skirt succeeded the long, close-fitting skirt of the earlier period. With the short skirt much care and attention was given to footwear.
- B*—1913—This lady of fashion wears the new basque dress. The overdress is now added to the "hobble skirt."
- C*—1914—Fullness is now at the top rather than at the lower edge of the skirt. The extreme lower edge is left open.
- D*—1914—The peg-top silhouette in evening gown. The evening head-dress is typical of the time.
- E*—1915—The dress suit of a gentleman of the period. The short waist-line and well-opened fronts still continue.
- F*—1916—A costume showing the short bouffant skirt.

evolve the new. Shortly tunics were added to the narrow skirt, (*B*, Plate XXX.) They were usually of chiffon, crepe, or net and inclined toward much fullness. Frequently they were banded at the lower edge thus preventing the tendency to fall away from the figure, and again, they were allowed to fall and fly unconfined. (Fig. 53.) Beads and bead trimming were used in profusion upon both skirts and blouses. The bands which confined the tunic were often of beaded design, beautiful in color harmony. The simple blouses were also artistically ornamented with beaded patterns.



Fig. 53. Dress of 1912, showing basque and tunic.

Toward 1914 the narrow skirt still lingered, though the silhouette gradually changed. Instead of the straight figure, the "drooping boneless pose" took its place before the footlights of fashion.

Gradually more fullness was creeping into the skirt, but at the top rather than at the lower edge, thus giving every hint of the atrocious bustle of the eighties. (Fig. 54.) The new figure, narrow at the foot and full at the hips, was termed the "peg-top silhouette." (Fig. 55.) Often the fullness of these skirts was laid in plaits around the hips or arranged in gathers. The extreme lower edge was left open at the front that it might slip up over the instep in walking. (*C*, *D*, Plate XXX.) This simple plaiting about the hips of these skirts merged gradually into huge puffings, ruffles, and draperies, giving the panier effect. In fact, caution in the use of drapery was thrown to the winds and the queen of fashion was simply wrapped up in material.

With the evasive waistline and the flow of drapery the fitting of a costume was not a matter of accuracy as in former years, but became a matter of artistry in the subtle

harmonies of line and color. Materials were usually supple and clinging, revealing the graceful lines of the figure and suggesting the Orient. Charmeuse, messaline, chiffons,



Fig. 54. Revival of the styles of '83

silk mulls, silk poplins, moire, gaberdine, embroidered and printed crepes, crepe meteor, and other charming stuffs in sufficient variety to please the most fastidious were offered. In evening dresses trains were worn narrowed to a point, a veritable *queue de serpent*. (D, Plate XXX.)

After a period of drooping blouses with the vague indeterminate waistline the fashion world awoke to find itself in the most unexpected attire—the new basque dress. It was indeed the old basque of the thirties but so tempered with the modern feeling for comfort and ease, and so charming in line that it immediately became the vogue. Slenderness was still the distinctive note, for the favorite skirt to be worn with the basque was narrow, decidedly narrow, with the full tunic overdress. The new basque did away with the blouse effect at the waist and dropped the waistline to the hip. It subtly suggested the curves of the figure without accentuating them and kept the long line from the shoulder to the hip unbroken. (Fig. 53.)

At this time, a reminder of the war in the Balkans was seen in the Balkan blouse with its belt girding the hips. (Fig. 56.) The bright colors of Bulgarian peasant art were also seen in the vivid hues of the period's trimming.



Fig. 55. The peg-top silhouette

Though women's fashions were as inconstant as the will-o-the-wisp, there continued to be little change in men's dress. Still the Prince Albert, or frock, and the cutaway, which have passed through varying phases of popularity for almost two hundred years, continued to be first choice. Dark browns as usual were favored; also, black, blue, gray, and the black and white mixtures. During 1915 odd waistcoats again appeared. These, however, had only a short season and were seen chiefly in dark silk or in white washable stuffs made double-breasted with a roll collar. The efforts to change the style of evening tailcoat proved unsuccessful, and the short waistline and well-opened fronts still continued. (*E*, Plate XXX.)

There is an old adage to the effect that the longest road has its turn. So it is with the way of fashion. Three years is said to be the lifetime of any particular mode, but the narrow skirt in either tailored or draped effects had survived for twice that period, and toward 1915 a welcome change appeared in the skirts flaring a little at the lower edge. By the end of 1915 the new mode was at its height—the full skirt and the well-defined waistline with the faintest suggestion of crinoline. (*A*, *F*, Plate XXX.)

The modes of 1916 plainly point to the fact that there is nothing absolutely new in a style. The conventions of dress have developed year by year, all the possibilities of costume have found expression and now nothing remains but to adapt the old to the conditions of today and thus relate it to the life and society of the present.



The fashions of 1916 take us decidedly back to the basque and crinoline of 1870, the period of the French Louis', with little suggestions of the Directory period, especially as seen in the hats. Skirts were full, and their width emphasized by horizontal trimmings and panier drapery. They had also become short. (Fig. 57.) Crinoline was imminent and already the new frocks had two hoops of whalebone between the hip and knee to make them sufficiently bouffant.

With the very short skirts a new emphasis was placed upon the footwear. Boots were of various colors, gray, tan, pearl, blue, and bronze; indeed the all-black shoe seemed relegated to the past. Boot tops were made quite high, just meeting the edge of the short skirt.

Hats also go back to the time of the French Louis' when ribbons were much in evidence. Not only were there wide brimmed hats, trimmed with ribbon, lace and flowers, which point to the Louis Seize period, but the Watteau of the time of Louis Quatorze and the Directory came in for its share of popularity. Much in evidence was the cockade of the French Revolutionary period. This was seen in ribbon and feathers and was evidently indicative of the times. (Fig. 58.)

Four years of the Great War made their inevitable demands upon the fashion world. Women must adapt themselves to a wartime schedule. Clothes must be economical. The great problem in the feminine world lay in selecting the clothes which might reflect in their dignity and simplicity the seriousness of the time. With the strict conservation of wool; silks, satins, crepes, and chiffons became the mode. Lines were simple, colors subdued and unobtrusive. The quiet and subdued tones were not a matter of choice



Fig. 56. The Balkan blouse

but of necessity. The dye situation in the dye markets of the world had become acute and a shortage of dyestuffs with which to color materials threatened. These quiet colorings were called "sympathetic hues," suggesting the mental tone of the world under the stress of war.



Fig. 57. Styles of 1916

The first season of the Textile Color Card of America resembles in tone if not in name the French color cards. A blue with a violet cast is called "heron"; gray, with a suggestion of taupe is "dusk"; a beautiful leaf-green, "tyme"; and a shade between fawn and brown is "gazelle." "Spring green" is the tone of the first new leaves; "mist," a tint of gray; and "blossom," pink with a violet tinge.

It was during the war period that the strictly one-piece dress became the favorite. For morning war work a one-piece frock (*C*, Plate XXXI) of satin, cloth, or wool jersey was selected. The attractiveness of these war-time dresses grew out of their simplicity of line and the lack of trimming. The coat-suit and the one-piece frock, slightly trimmed, were the "all-occasion" costumes of war time. (*A*, *B*, Plate XXXI.)

The many avenues of service open to women during the war gave rise to an entirely new departure in clothes. The woman skilled in driving her own car offered her service to the Motor Corps or the Ambulance Service. She of business experience found her place in the ranks of the Naval Yeoman Reserves. Many women skilled in domestic science entered the canteen kitchens, while others took their places in the Red Cross Service. In all these departments

of service, regulation uniforms were authorized by the United States government. (Plate XXXII.) The material of outdoor uniforms was strong durable stuff—serge and whipcord, often leather trimmed. Leather coats with removable fleece linings were often worn over the uniform. The Red Cross nurse, in her service at home, wore a uniform of fine white cloth; overseas, a gray chambre took



Fig. 58. Hats of 1916

its place. Coifs of red or blue according to her duty added the note of color to the costume. (Fig. 59.)

With the signing of the armistice in November 1918, the world looked for a return to normalcy in dress as well as in affairs. But with an upheaval so gigantic, adjustment lay only in the hand of time. A sudden transformation in fashion is unknown to history. The transition from the style of Louis XVI to that of the Directory is the most rapid recorded and that was born through a Reign of Terror.

As the aftermath of the French Revolution brought forth the *incroyables* and *merveilleuses*, so now new and strange fancies appeared. It is said that the incredibly short and scant skirt of 1920-1921 was the direct expression of the unsettled condition of the world. All women, irrespective of age, height or width donned the scant skirt reaching just below the knee. (E, Plate XXXI.) The women of sixty, fifty, and twenty were wearing, with an effort at equal grace, the abbreviated costume, formerly restricted to the growing girl of ten or twelve years. Notwithstanding the warning of skillful designers—"a woman should gauge the length of her skirt by her physique, not

by Parisian styles"—the short skirt continued. Along with the short skirt came the unbridled use of cosmetics. The "vanity-case" with its powder, rouge, and lip-stick enjoyed a reign rivaling that under the French queen, Marie Antoinette. Then followed bobbed hair, and the "flapper" made her bow over the footlights of fashion. "Flapper" was the popular term applied to her who followed the dictates of fashion to the limit. Then again history, true to type, repeated itself. Our makers of law rose in their official dignity and denounced these follies of fashion. Again laws were threatened regulating the dress of women. But, as in the past, the mode continues until woman herself decrees the new.

The war, the automobile, and the world of sport have all contributed to the costume of post-war days. All periods of dress have furnished ideas for the post-war fashions. Directory, Louis Seize, Moyen Age, and Oriental influences elbow one another. The Directory was suggested in the short scant skirt and in the knee-length, perfectly straight, close coat. The Moyen Age ideas were in the long panels front and back, with the side fullness attached at the hipline. (*B*, Plate XXXI.) The Oriental influence was seen in the excessively scant skirt with slashed sides, in its color and embroideries. With these varied influences of the past was the distinctly modern note contributed by the American sport world. Knitted woollens, sweaters, scarves, gloves,

---

COLOR NOTATION—PLATE XXXI

- A*—Tailored suit, P  $\frac{3}{8}$ , P  $\frac{5}{8}$ ; collar, black. Hat, P  $\frac{3}{8}$ , Y  $\frac{5}{8}$ . Hose, N 4. Shoes, black. Handbag, Y  $\frac{5}{8}$ , Y  $\frac{1}{8}$ .
- B*—Costume, B  $\frac{4}{8}$ ; trimming, B  $\frac{3}{8}$ . Hat, B  $\frac{3}{8}$ ; trimming, Y  $\frac{5}{8}$ , Y  $\frac{1}{8}$ , B  $\frac{3}{8}$ . Shoes, black, Y  $\frac{5}{8}$ . Hose, Y  $\frac{5}{8}$ .
- C*—Costume, B  $\frac{3}{8}$ . Hat, B  $\frac{3}{8}$ , Y R  $\frac{5}{8}$ , Y R  $\frac{1}{8}$ . Collar, Y  $\frac{5}{8}$ . Hose, N 5. Shoes, black. Handbag, Y  $\frac{1}{8}$ .
- D*—Skirt, B  $\frac{4}{8}$ . Overdress, Y  $\frac{1}{8}$ ; trimming, Y  $\frac{5}{8}$ , B  $\frac{4}{8}$ . Sash, B  $\frac{4}{8}$ . Hose, Y  $\frac{1}{8}$ . Shoes, black, Y  $\frac{1}{8}$ . Parasol, P  $\frac{4}{8}$ , G Y  $\frac{7}{8}$ , G Y  $\frac{1}{8}$ , R  $\frac{5}{8}$ , R  $\frac{1}{8}$ , B G  $\frac{5}{8}$ , Y  $\frac{5}{8}$ .
- E*—Costume, P B  $\frac{1}{8}$ ; trimming, Y R  $\frac{7}{8}$ . Blouse, white. Hat, B  $\frac{5}{8}$ ; trimming, black. Hose, Y R  $\frac{1}{2}$ . Shoes, black.
- F*—Cape, B  $\frac{3}{8}$ , B  $\frac{3}{8}$ , B  $\frac{1}{4}$ , black. Dress, B  $\frac{1}{8}$ , B  $\frac{5}{8}$ . Hat, Y R  $\frac{5}{8}$ , Y R  $\frac{1}{8}$ . Hose, N 6. Shoes, black.





A B C D E F

PLATE XXXI—AMERICAN COSTUME—1917-1921

- A*—1917—The tailored suit which has proven itself an all-occasion dress for women. The attractiveness of this costume lies in its simplicity of line and lack of ornamentation.
- B*—1918—A simple afternoon dress of the war-time period. This was usually of silk or satin crepe.
- C*—1918—The one-piece frock which rose to popularity during the World War.
- D*—1919—An afternoon dress carrying out the one-piece idea in the tunic. At this period all dresses were short.
- E*—1921—A woman wearing the short and scant skirt of the period.
- F*—1921—A costume showing the influence of the military idea upon dress in the large full cape and the Napoleonic hat.

and hose were the smart adjuncts of the sport toilette. (Fig. 60.)

The element of athletics in the life of the American woman has had much to do with her education and taste in matters of dress. Comfortable shoes and easy walking-skirts, and trousers, if need be, are outward expressions of women's ideals and indicate much in the character of the times. (Fig. 61.) The contrast between feminine apparel in 1848 and 1920 is a precise counterpart of the contrast between feminine thinking in that time and this. Says *Equal Rights*:

The hoop-skirt, the small waist and the general impracticability of the clothes worn at the first Seneca convention interpret far more graphically than words can phrase the position of women seventy-five years ago. The artificial helplessness, the wretched discomfort, the denial of nature, all are emblazoned in sartorial terms. The absolute dependence of woman upon man was blazoned forth in her clothes . . . . The frailty and incompetence inherent in an eighteen-inch waist and a hoop-skirt stimulated the male ego to an unconscionable extent. It was not difficult to feel superior to that. Probably there is no more wholesome encouraging symptom of the times than is to be found in woman's clothes. They indicate that women are no longer doomed to live on sex, that men are no longer such impossible egoists as they were, and they predict the girls of the future will enter life booted and spurred for the fray as they never have been before.

#### COLOR NOTATION—PLATE XXXII

- A—Overcoat, cap and skirt (whipecord), N 4, white; buttons, gunmetal; shoes, black.
- B—Overcoat, N 4; cap, N 4. Shoes, black; puttees, black. Gloves, N 4.
- C—Uniform, B  $\frac{1}{2}$ ; buttons, brass. Hat, B  $\frac{1}{2}$ ; band, black. Shirt, white. Shoes, black; hose, black. Gloves, N 6.
- D—Uniform and cap (whipecord), N 4, white; buttons, metal; belt, black. Shirt, white; tie, black.
- E—Overcoat and cap (whipecord), N 4, white. Insignia, cross, R  $\frac{1}{4}$ ; field, white. Shoes and puttees, black. Gloves, N 4.
- F—Uniform and cap (whipecord), N 4, white; buttons, metal; gloves, N 4; shirt, white; tie, N 4.

Note:—"At the beginning of the war much originality existed in the matter of uniforms. . . . However, as quickly as possible the subject was taken under advisement with the result that all uniforms worn by Red Cross workers were standardized."

From Red Cross National Headquarters,  
Washington, D. C.



A B C D E F

PLATE XXXII—AMERICAN COSTUME—1917-1918

- A*—The regulation overcoat worn by American women in foreign service during the war was made of durable stuffs, serge and whipcord, and leather trimmed.
- B*—A leather coat with removable fleece lining was a popular coat worn in both foreign and domestic service.
- C*—The uniform worn by the Naval Yeoman Reserves. This was the practical business suit for American women in yeoman service.
- D*—Foreign service uniform, American Red Cross. The black leather belt was worn only by commissioned officers.
- E, F*—The regulation overcoat and uniform worn in the American Red Cross (Motor Corps) in domestic service.

By the close of 1920 women's dress had become as varied as the world itself. No longer does she wait for the coming of the Parisian doll to announce the new mode from Paris, or borrow a much-prized fashion-sheet from her neighbor

to glean the coming styles. Not she of the twentieth century! Months ahead the buyers and designers of the big shops of North and South America, England and the continental countries have invaded Paris and brought back the word. This is broadcasted through innumerable magazines, fashion books, style shows, and the "movie." These buyers and designers, advance agents of style, come into Paris during the weeks of early spring and late summer. Their interest centers around the salons of the unrivaled French creators, Poiret, Callot, Paquin, Cheruit, Lanvin, Worth, Redfern and others.



Fig. 59. Red Cross uniforms

Though a few of the names long cherished as French are not French at all, these creators have risen to fame under the stimulating influence of the French capital. Paris is the inspiration! But why Paris? The answer is unmistakable. It is found in the French national character. Here is a people who have behind them traditions of color, traditions of design, traditions of artistic feeling. A people with a refined sense of form and color, who from time immemorial have given attention and thought to the adornment of the person. In Paris culture and society life developed earlier than in any other city, and fashion is essentially a product of social life. Under the French kings, the women of the court enjoyed a position and power which made them patronesses of fashion, and an inspiration to creative endeavor. With this



heritage of background who will say that this is not the stimulus which every artist finds in this historic beauty-loving city?

Long has been the hope for American fashions, and strong has been the agitation for a world's fashion in America—a fashion center where ideas of dress especially adapted to American women may be fostered and developed. Since the war the idea of a greater Americanism has taken a profound hold upon the mind of the people. Not only does a greater Americanism



Fig. 60. Sport suit

center around the legislative problems of the country, but it also enters into the commercial life. In industry the new note is "American Art for American Industry." This has led as never before to a greater emphasis upon the term "Industrial Art." The efforts now being made by designers and manufacturers to use American designs and American materials make apparent the common interest of these two powerful agencies in producing strictly American types. Our de-




Fig. 61. Riding clothes of 1924  
(Redrawn, courtesy Marshall Field & Company)

signers have always gone to France, not only for the fashion but for the design of fabrics as well. Our silks, our velvets, and our woolen goods have been designed by the Parisian schools. A change seems imminent. In 1916 the first American design contest<sup>1</sup> for women's wear was held at the Art Alliance of America in New York City and promoted by the paper called *Women's Wear*. During the same year, the first instance of a manufacturer calling upon American artists for designs was that of the Albert Blum Contest.<sup>1</sup> This was a contest for hand-decorated fabrics. This manufacturer put his emphasis upon *designs created in America*. Many of the designs submitted were inspired by the study of primitive American design including Mexico and Central and South America. The museums and galleries of America have entered heartily into this movement for the development of American design. Through these institutions a co-operation of artist and manufacturer is being fostered. The artist tells the expert in industry the effective use of form, line, and color, while the textile expert tells the artist whether the designs can be carried out by the machine, and whether the colors can be obtained. Others are lecturing upon costume design and the effects of the various lines, colors, and proportions upon the figure. Experiments in dyeing have been conducted and specimens of dyestuffs and textiles, native and foreign, have been shown. In 1917, the Metropolitan Museum of New York City, recognizing textile design as part of our national art, opened a new textile gallery. In this gallery embroideries, hand-decorated fabrics, and eighteenth-century garments are displayed.

<sup>1</sup>*Journal of Home Economics*, May, 1918.

#### COLOR NOTATION—PLATE XXXIII

- A—Tunic, Y  $\frac{1}{2}$ ; collar, belt, black and white. Cap, Y  $\frac{1}{2}$ , G Y  $\frac{1}{2}$ . Mantle, G Y  $\frac{1}{2}$ , G Y  $\frac{1}{2}$ . Shoes, N 4.  
 B—Skirt, white, N 7. Blouse, white. Tie, Y  $\frac{1}{4}$ , G  $\frac{1}{4}$ . Vest, G  $\frac{1}{4}$ . Sailor, Y  $\frac{1}{4}$ ; band, G  $\frac{1}{4}$ . Shoes, white.  
 C—Skirt, white. Sweater, black. Hat, black, white. Shoes, white.  
 D—Coat, trousers, Y  $\frac{1}{4}$ . Hat, Y  $\frac{1}{4}$ ; band, Y  $\frac{1}{4}$ . Boots, black.  
 E—Skirt, white, G Y  $\frac{1}{2}$ . Coat, G Y  $\frac{1}{2}$ , dot and trim, G Y  $\frac{1}{2}$ . Hat, black, G Y  $\frac{1}{2}$ . Shoes, white.



A B C D E

PLATE XXXIII—AMERICAN COSTUME—1900-1920

*A*—The popular bathing suit of the day. These are carried out in various and gay colors. The caps are rubber, harmonizing in color with the costume. The large cape adds the finishing touch to the mode.

*B*—A sport frock showing the comfortable shoes, walking skirt, sleeveless vest of gay color and sailor hat of rough straw.

*C, E*—Types of sport costume.

*D*—Riding togs of the twentieth century.

*B, C, E*—Redrawn, courtesy Marshall Field & Company.

The co-operation of art and industry is recognized in the organization known as the Fashion Art League, representing the dressmakers of America. The Dress and Skirt Designers' Association is another commercial organization which is emphasizing American designs. At a recent gathering of the association forty-nine model skirts were shown. The designs for these had been made in America, the cloth manufactured in America, and the skirts made in America. Formerly this association had always advertised Parisian models. Now their advertisement reads: "American designed, American manufactured, American made."

The educational institutions of the country have taken hold of this matter of clothes. Not only is the making of clothes an accredited course in the schools, but the æsthetic side—the line, the color, the beautiful in the dress of the past—is becoming more and more a vital part of the educational curriculum.

With all this impulse toward the beautiful in dress, it would not be surprising should American women, in time to come, create as well as wear beautiful clothes, though the art is not easily wrested from the hand of Paris. The French designer has supplied the world from an age-old heritage of artistic feeling, and he will doubtless maintain his supremacy until some other people, some other time, from a garnered heritage of the same age-old æsthetic instincts can, with the intuitive facility of Paris, divine the beautiful in the realm of dress.





## BIBLIOGRAPHY

- Boutet de Monvel—*Joan of Arc*.  
15th century costume, illustrated.
- Challamel, Augustin—*History of Fashion in France*.  
20 colored plates.
- Calthrop, D. C.—*English Costume*.  
72 colored plates, numerous woodcuts.
- Earle, Alice Morse—*Two Centuries of Costume in America*.  
*Costume of Colonial Times*.
- Hill, Georgiana—*History of English Dress*.
- Hope, Thomas—*Costumes of the Ancients*.  
321 plates.
- Hughes, Talbot—*Dress Design*.  
Illustrated.
- Kretschmer and Rohrbach—*Costumes of All Nations*.  
104 colored plates.
- Norris, Herbert—*Costume and Fashion*.  
Illustrated.
- Planché, J. R.—*Cyclopedia of Costume*.  
Illustrated; Vol. I, dictionary; Vol. II, general history of costume in Europe.
- Quicherat, J.—*Historie de Costume en France*.  
481 woodcuts of costume.
- Raciné, A.—*Le Costume Historique*.  
500 plates of practically every period and country.
- Robida, A.—“*Yester-year*.” *Ten Centuries of Toilette*.  
20 colored plates and numerous woodcuts showing costume from Middle Ages to 1880.
- Zur Geschichte der Kostüme*.  
119 colored plates showing costume from 4th to 19th centuries.

## INDEX

References are to pages. Page numbers in italic type refer to illustrations.

- Æsthetic Movement in London, 205  
 Aigrette, 45, 119, 175  
 Albert Blum Contest, 234  
 America as fashion center, 233  
*Amônières sarrasinoises*, 83, 89  
*Amusse*, 87  
 Ankle-boots, 189  
 Ankle-rings, 25, 34  
 Apotygmata, 48, 49  
 Appliqué, 86, 103, 179  
 Apron, 165, 167, 172; Egyptian, 23, 23, 25  
 Armlets, 25, 34  
 Armor, 88, 89  
 Art and industry, co-operation of, 236  
 Artisans, 84, 90  
 Arts and crafts movement of Middle Ages, 117, 136  
 Asp, the royal, 24, 25, 30  
  
*Baignolette*, 141, 147  
 Bags, 87, 148  
 Basque, 225; boned, 203, 204  
 Basque-dress, 221, 222, 223  
 Basquine, 109  
 Beads, 22, 35, 222  
 Beard: Asiatic, 41; Egyptian, 29, 30, 30; Greek, 57; "Imperial," 124, 125; Middle Ages, 81; Persian, 44, 45, 45  
 Belt, 22, 44, 87, 90  
 Bills, regulating dress, 220  
*Bliand*, 88, 89  
 Blouse, 206, 214, 220, 222; Balkan, 224, 225  
 Bodice, 116, 133, 153, 176, 182; boned, 109, 120, 126, 127, 143, 177; pointed, 106, 172, 180  
 Body, ornamentation, 19; painting, 17  
 Bolero, 189  
 Bonnets, 141, 197, 199, 204, 211; calash, 178; Shaker, 189  
 Books, fashion, 208, 232; *Godey's Lady's Book*, 192, 193; *Harper's Bazaar*, 192; *Peterson's Magazine*, 192; *Union Magazine*, 192  
 Boots, 31, 40, 63, 106, 108, 123, 225; great-topped, 123, 125, 138; half, Asiatic, 40, 41, Greek, 63; high, 122, 159  
 Boston, a center of fashion, 175  
 Bracelets, 34, 45, 64, 77, 82, 84, 157  
 Breeches, 113, 122, 123, 127, 139, 164, 183  
 Bretelles, 190, 191, 201, 215  
 Brooch, 48, 56, 79  
 Buckles, 141, 148, 168, 183  
 Buckram, 176  
 Bustle, 108, 200, 201, 203, 205, 222  
 Bustle-skirt, 202  
 Butterick, Ebenezer and Ellen, 207; pattern, 207  
 Buttons, 99, 100, 116, 117, 128, 139, 163, 165  
  
 Calash, 178, 178  
 Cambries, 196  
 Camlet, 82, 136, 174  
 Canezou, 195, 196  
 Caps, 110, 112, 148, 174, 179; Charlotte Corday, 156, 157; cylindrical, 45, 45; Mary Stuart, 113, 115, 116; Phrygian, 39, 41, 42, 42, 43, 79  
 Capes, 127, 135, 184, 197, 229

- Capillamentum, 75  
 Caul, 57, 75  
 Cavalier, 168  
 Chains, 110  
 Chain stitch, 103; stitching, 117  
*Chaperon*, 87  
 Chemise, 99, 118  
 Chignon, 182, 202, 203  
 Chinband, 83, 93  
 Chiton, 48, 49, 52, 53, 58; Doric, 48, 49, 51; double-girded, 49, 49, 51; Ionic, 50, 50, 52, 52, 53; knitted, 52  
 Chlamys, 56  
 Chopines, 128, 129  
 Clasps, 38, 43, 50, 54, 55, 79  
 Clays, use of colored, 18  
 Cloak, 124, 157, 163, 165, 193  
 Coat, 127, 135, 163, 168, 183; cut-away, 183, 185, 224; full-skirted, 139, 141, 176, 177, 191; Prince Albert, 224  
 Cockade, 139, 156, 182, 225  
 Coiffure:  
   American, Colonial, 166, 176, 178; 1813, 189; 1830, 190; '60's, 198; '70's, 199, 202; '90's, 211; 1921, 228  
   Carlovingian, 86  
   French, middle 17th century, 134, 135; late 18th century, 148-151; following Revolution, 157, 158  
   Gallo-Roman, 79  
   Grecian, 51, 55, 57  
   late 12th century, 92, 92  
   Merovingian, 84  
   Roman, 71, 74, 75  
 Coifs, 227  
 Collar, 22, 128, 131; flat, 127, 135; high, 188, 191, 209, 210, 215, 216  
 Color:  
   American, Dutch Colonial, 166; Pilgrim and Puritan, 163; Quaker, 172; during Great War, 225  
   Asiatic, 45  
   combined in costume, 96, 99, 204, 209  
   in early Christian design, 85  
   Color:  
     Egyptian, 28, 32, 33  
     French, 16th century, 109, 121; 17th century, 129, 138; 18th century, 152  
     Grecian, 61, 62  
     Merovingian, 84  
     Roman, 70, 72  
   Comb, 36, 190  
   Constantine, influence of court of, 84  
   Cordelières, 110, 113, 115  
   Corset, 126, 147; ancient form of, 62, 79; adopted by men, 113, 119; crusade against, 206; steel, 120, 120  
   Cosmetics, 77, 82, 117, 148, 228; disappearance of, 156  
   Costume, *à la constitution*, 155, 156; Garibaldi, 208  
   Cotillon (underskirt), 118, 140  
   Cotta, 94  
   Cottahardie, 94  
   Cotton, 26, 80, 95, 154, 205  
   Couching stitch, 103  
   Craftsman, 90, 91, 104  
   Cravat, 127, 136, 139, 141, 156, 158, 168, 177, 188  
   Crinoline, 108, 194, 195, 197, 225  
   Criticisms, of Massillon, 148  
   Crochet, 103  
   Cross stitch, 103  
   Crusaders, influence of, 83, 88, 89  
   Cuffs, 109, 135  
  
   Décolleté, extreme, 98  
   Decoration, body, 17  
   Design:  
     Byzantine, 84  
     Christian symbols in, 84, 85  
     Development of American, 233, 234  
     Egyptian, 33  
     French, 16th and 17th centuries, 136, 137; 18th century, 152  
     Greek, 60, 61  
     Heraldic, 96, 103  
     Roman, 74  
   Designer, French, 236

- Diadem, 57, 86  
 Dip, 214  
 Diploïdion, 51, 54  
 Directory, 148, 155, 160, 183, 225  
 Divided skirt, 206  
 Dolls, fashion, 104, 174, 232  
 Dolman, 204  
 Dorians, 49  
 Doublet, 83, 99, 101, 108, 115, 119,  
     122, 127, 163, 165, 168; busked,  
     113, 119  
 Drapery, 23, 68, 218, 222  
 Dress:  
     Amazon, 39, 43, 44  
     Capetian, 81, 83  
     Carlovingian, 81, 86  
     Colonial, 176; in New York, 175;  
         in Philadelphia, 176; in south-  
         ern colonies, 168; sources of in-  
         formation on, 163  
     craftsman, 91  
     Dacian, 45  
     Directory, 155, 160  
     during French Revolution, 154,  
         155  
     Dutch women in New Amsterdam,  
         166, 167  
     Egyptian, characteristic early, 21,  
         22, 22; later, 25, 26  
     Empire, 159, 160, 184, 185, 219  
     first problems in, 19  
     following American Revolution,  
         184, 185, 186  
     following French Revolution, 156,  
         157, 158, 159, 160  
     following Great War, 228  
     influences revolutionizing, 211  
     Medes, 45  
     Merovingian, 81, 82  
     modern, 20  
     mourning, Greek, 55, 62; Middle  
         Ages, 87, 88  
     Parthians, 45  
     Persian, 44, 45  
     Phrygian, 41, 42  
     Pilgrim and Puritan, 162, 166,  
         167  
     protective, 19  
     Quaker, 167, 171, 172  
     Dress:  
         Republicans, of America, 183, 184  
         sport, 212, 230, 233, 235  
         Syrians, 45  
     Dress and Skirt Designers' Associa-  
         tion, 236  
     Dress Reform Movement, 205  
     Du Barry, Mme., 142  
     Dyeing, 40, 95, 234  
     Dye markets, 226  
     Dyes, 26, 33, 40, 58, 205, 226  
     Ear-rings, 34, 44, 64, 77, 82, 119  
     Edicts, against the mode, 95, 109,  
         114, 117, 132; of Richelieu, 131  
     Embroidering, art of, 40, 87, 88, 96,  
         118  
     Embroidery, 42, 45, 56, 58, 73, 84,  
         86, 91, 103, 116, 129, 164, 176,  
         216, 234  
     Epaulettes, 214, 215  
     *Equal Rights*, quotation from, 230  
     Escoffion, 97, 102  
     Exhibition, Historical, of Costume  
         of France, 208  
     Face-painting, 63, 77  
     *Falbalas*, 140, 179  
     "Fall," 164, 165  
     "Falling whisk," 174  
     Fans, 34, 36, 64, 65, 80, 105, 119,  
         125, 126, 143, 149, 177, 185  
     Farthingale, 108, 111, 113, 115, 120,  
         124, 131, 140, 142, 144  
     Fashion, and architecture, 104; Art  
         League, 236; books, 192, 193,  
         208, 232; dolls, 104, 174, 232;  
         English, adopted in France,  
         143, 154, 156; "indecorous," 126;  
         of concealing the hair, 86, 87  
     Feathers, 124, 148, 162, 172, 200  
     *Fers*, 116  
     *Fibre chamois*, 209  
     Fichu, 153, 155, 180, 183  
     Fitted garment, 93, 94, 97  
     Flapper, 228  
     Flax, 21, 53  
     Flounces, 192  
     *Fontange*, the, 125, 134, 140



- Frankish women, characteristics of, 82
- Fringe, 26, 28, 40, 54, 72, 106, 131, 205, 216
- Furs, 63, 109, 110, 136, 175, 184
- Garters, 168
- Girdle, 23, 49, 52, 54, 72, 79, 84, 86, 95, 98, 120, 129, 214
- Gloves, 93, 105, 119, 129, 157, 175, 228
- Godey, Louis Antoine, 192
- Godey's Lady's Book*, 192, 193
- Gorget*, 93
- Gown, 128, 153, 165; *cambric*, 147; trailing, 104, 105
- Grecian bend, 202
- Guilds, 90, 126
- Guimpe, 88, 216, 217
- Hair, 57, 74, 118, 134, 157, 172, 184, 211; false, 29, 45, 63, 75, 80, 119, 121; fashionable color in, 105; *pompadour*, 178, 211; powdered, 176
- Hair-dresser, 134
- Hair-dressing, beginning of, 92
- Hairpin, 36, 64
- Handkerchief, 80, 157, 175, 181, 182
- Harper's Bazaar*, 192
- Hats, 57, 58, 116, 124, 157, 164, 165, 183, 184, 211, 217, 218, 225; beaver, 164, 165, 197; *Chanticleer*, 217, 217; *Gainsborough*, 217, 218; *Lavinia*, 189; modern, 153; *Troutbeck*, 189
- Head-dress:
- Asiatic, 39, 41, 42, 43, 45
- Egyptian, 25, 27, 29, 30, 31
- French, 16th century, 110, 111; 17th century, 125, 134, 135; 18th century, 148, 149, 149, 150, 150, 151, 160; *la Belle Poule*, 149, 149; *Fontange*, 125, 134, 140; *pouf au sentiment*, 150, 150
- Grecian, 51, 55, 57
- Head-dress:
- Middle Age, 97, 100, 102, 104, 105
- Roman, 71, 74, 75
- Headstrap, 93
- Heels, 152, 166; high, 129, 148, 153; low, 153; red, 176
- Helmet, 43, 59, 69, 90
- Hennin, 97, 102, 107
- Heraldry, 90
- Himation, 48, 51, 53, 54, 55, 58, 62, 67
- Hood, 31, 84, 86, 87, 101, 116, 147, 165, 172, 173
- Hooks and eyes, 165
- Hoop, 108, 140, 141, 142, 144, 171, 177, 196, 197, 198, 198
- Horsehair, 200
- Hose, 106, 175, 230; trunk-hose, 83, 99, 101, 108, 119
- Houppelande, 98
- House-shoe, 80
- Howe, Jr., Elias, 194
- Incroyables*, 158, 159, 227
- Industries, in France, 131
- Ionians, 49
- Isabelle of Bavaria, 98, 102, 104, 120
- Jacket, 19, 56, 97, 143, 154, 184, 205, 206, 214, 215, 216
- Jaeger Company, 205
- Jardin des Plantes, 133
- Jerkin, 163
- Jerseys, 204, 226
- Jewelry, 34, 64, 74, 77, 82, 128, 156, 199; *à la constitution*, 156
- Jouy prints, 147
- Kerchief, 93, 172
- Kneebuckles, 183
- Knight, 88, 90
- Knitting, 53
- Kohl, 35
- Kohl-pot, 35, 36
- Kolpos, 48, 49, 52
- Lace, 105, 110, 116, 118, 119, 128, 133, 136, 139, 162, 164, 173, 174, 176, 200; gold, 131, 132; importation of, 128

- Lacing, 93, 94  
 Lace-making, in France, 133  
 Laws, regulating dress, 164, 228  
 Linen, 26, 28, 40, 53, 68, 80, 87, 93,  
     106, 165, 166, 169, 172, 173, 174  
 Linsey-woolsey, 166  
 Livia, 73  
 London, as fashion center, 156  
  
 Macaroni roll, 178  
 Maintenon, Mme., 134, 139, 142,  
     147, 172  
*Mancherons*, 115, 116  
*Mantilla*, 26, 147  
 Mantle, 20, 26, 39, 40, 41, 42, 44,  
     54, 72, 81, 82, 83, 84, 87, 94,  
     95, 125, 157, 193  
 Marguerite of Valois, 120, 123  
 Marie Antoinette, 217, 228  
 Mask, 130; *loup*, 116, 121, 138  
 Massillon, criticisms of, 148  
 Materials:  
     in American dress, '30's, 193;  
     '80's, 204; '90's, 210; 1914, 223  
     Asiatic, 38, 44  
     Colonial, 163, 164, 165, 176, 179  
     combined in costume, 201, 204  
     Egyptian, 21, 26, 28  
     French, 16th century, 109; 17th  
     century, 128, 138; 18th century,  
     154  
     Grecian, 53  
     Middle Age, 80, 82, 95  
     Roman, 68  
 Medici, Catharine de', 112, 114,  
     117, 120  
 Merveilleuses, 156, 157, 158, 159,  
     184, 227  
 Middle class, 90  
 Mirrors, 36, 75, 80, 130  
 Mitre, 45, 45, 57  
 Mittens, 93, 194  
 Mitts, 175, 191  
 Muff-dog, 130  
 Muffs, 112, 130, 131, 141, 167,  
     185, 193; in costume of men,  
     127, 136, 170  
 Necklace, 19, 33, 44, 64, 82, 84, 105,  
     110, 116, 119, 148, 175  
 Needlework, 89, 114  
 Net, 57, 75, 92, 92, 198  
  
 Ornament:  
     Byzantine, 85, 85; Egyptian, 33,  
     34; Gothic, 91; Greek, 60, 60,  
     61; influence of the East in,  
     103; primitive, 19; Renaissance,  
     136, 137; Roman, 74, 74  
  
 Paint, 45, 64, 77, 117, 119, 148  
 Palla, 70, 71, 72, 79  
 Palliolium, 71, 72  
 Panier, 108, 139, 141, 142, 143, 144,  
     176, 222; *à coudes*, 144, 145;  
     *à guêridon*, 144; war against,  
     145, 146  
 Pantalets, 185, 186, 187  
 Pantaloon, 38, 39, 41, 43, 44, 46,  
     187  
 Parasol, 51, 80, 191, 194, 198, 201,  
     223, 229  
 Paris, as fashion center, 232; influ-  
     ences in establishing, 131, 132  
 Passementerie, 204, 205  
 Patch, 18, 77, 130, 148, 170, 171  
 Patch-box, 130, 171  
 Pattens, 99, 100, 110, 129  
 Pattern, 18, 32, 74, 118; dress, 207  
 Peg-top silhouette, 221, 222, 224  
 Pelerine, 135  
 Pelisse, 184, 188, 193  
 Penn, William, 171, 173  
 Peplos, 48, 48  
 Perfume, 35, 77, 80, 119  
 Periwig, 132, 169, 170, 172, 177  
*Perruquiers*, 139  
 Puke, 132, 170  
 Petasos, 58, 59  
 Petasus, 75  
*Peterson's Magazine*, 192  
 Petticoat, 124, 165, 166, 173, 179,  
     180, 181, 192, 195, 220; quilted,  
     177, 179  
 Pileus, 75  
 Pilgrims, 161  
 "Playne band," 164, 165, 167  
 Plumes, 151, 182, 217  
 Pockets, 119, 157

- Points, 99, 127  
 Poke-bonnet, 159, 172, 185, 189, 191  
 Polonaise, 204; looped, 203, 205  
 Pomades, 117  
 Pompadour, Mme., 142, 149; coiffure, 178, 211; silk, 142  
 Powder, 77, 119, 148; disappearance of, 156  
 Prints, 154; Jouy, 147  
 Pshent, 30  
 Puritans, 162  
 Purse, 89, 157  
 Pyxis, 64, 65
- Quaker, 171
- Redingote, 193  
 Reticule, 148, 157, 159  
 Revers, 190  
 Rhingraves, 123, 125, 138  
 Ribbon, 123, 128, 133, 134, 139, 148, 153, 162, 209, 210, 225  
 Riding costume, 206, 207, 233  
 Rings, 34, 44, 45, 77, 82, 84, 105, 119  
 Rosaries, 98, 110  
 Ruffs, 111, 112, 113, 114, 115, 116, 119, 120, 121, 127, 128, 131
- Sacque, silk, 199; *watteau*, 141, 177, 179  
 Samare, 166, 167  
 Sandals: Asiatic, 40; Egyptian, 31, 32; French, 18th century, 158; Greek, 62, 63; Roman, 75, 76, 80  
 Sash, 23, 29, 154  
 Scarves, 80, 87, 147, 159, 185, 191, 228  
 Sewing machine, 194  
 Shakefold, 108  
 Shawl, 26, 54, 158, 160, 184, 194; cashmere, 149, 194; Paisley, 160  
 Shend'ot, 24  
 Shirt, 26  
 Shirt-waist, 209; suit, 216, 216  
 Shoe polish, 189
- Shoes:  
 American, Colonial, 163, 166, 173, 176; early 19th century, 189; '60's, 198; 1916, 225; 1920, 230  
 Asiatic, 40, 45  
 Egyptian, 31  
 French, 16th century, 108, 110, 113; 17th century, 129; 18th century, 148, 152, 153, 153; 1800, 158  
 Grecian, 63  
 Middle Ages, 100, 106; *à la pou-laine*, 100, 101  
 Roman, 75, 76
- Silk, 53, 68, 70, 93, 95, 110, 122, 129, 132, 140, 142, 147, 153  
 Silk worm, introduced into France, 133; into Rome, 70  
 Silver, 42, 80, 105, 126, 131, 165  
 Singer, Isaac M., 194  
 Skirt, 20, 21, 22, 94, 98, 109, 112, 131, 132, 140, 144, 230; circular, 209; Egyptian, 22, 23, 23, 24, 27; gored, 199, 209, 210; hobble, 22, 215, 219; "morning glory," "serpentine," 214, 215; plaited, 215, 216; short, scant, 227, 229; *trotteur*, 216, 230  
 Sleeves, 26, 38, 45, 72, 88, 90, 93, 106, 108, 109, 112, 121, 128, 133, 139, 146, 186, 220; bishop, 196; false, 115, 116; leg-o-mutton, 110, 113, 190; *mousquetaire*, 210; puffed, 113, 115, 116, 120, 210; slashed, 110, 111, 164; '90's, 209, 210, 210  
 Slippers, 129, 186  
 Smock, 91  
 Sollerets, 106  
 Sorel, Agnes, 105, 120  
 Spenser, 185, 188  
 Spinning, 53, 73  
 Staël, Mme. de, 126  
 Stays, 126; ancient form of, 62  
 "Steinkirk," 136, 169  
 Stibium, 35, 36  
 Stockings, 106, 122, 129, 163, 164, 166

- Stola, 67, 70, 72, 79  
 Stripes, 142, 152, 181  
 Sudarium, 80  
 Sunshade, 51, 65  
 Surcoat, 83, 89, 92, 94; materials of, 95  
 Sweaters, 228  
 Swords, 124, 136
- Tapestry, 84, 85, 98, 102, 103; stitch, 103; weaving, 86  
 Tattoo, 18, 19  
 Textile Color Card of America, 226  
 Theristrion, 72  
 Tiara, 57  
 "Tied-back" time, 203, 204  
 Tilter, 202, 203  
 Tippet, 135, 193  
 Toga, 67, 69, 70  
 Toque, 111, 113, 116, 119, 183, 218  
 Trail, train, 125, 132, 133, 157, 192, 203  
 Transparents, 133  
 Trimmings, 152, 179; *falbalas*, 140; "ladders," 133; *pretintailles*, 140, 197  
 Trousers, 20, 123, 139, 187, 191, 197  
 Trunk-hose, 83, 101, 108, 113, 115, 119, 122  
 Tunic, 19, 20, 26, 38, 41, 42, 44, 48, 68, 70, 72, 79, 81, 86, 87, 90, 157, 218  
 Tussoire, 98
- Undergarments, 98  
 Uniforms, authorized by U. S. Government, 227; Red Cross (nurse), 227, 232; naval Yeoman Reserves, Motor Corps (A. R. C.), Foreign Service, 231; materials used in, 227  
*Union Magazine*, 192  
 Union-suit, 206
- Vanity-case, 228  
 Veils, 56, 62, 72, 80, 83, 87, 92, 94, 191  
 Vest, 38, 44, 155, 168, 185, 191
- Waist-belt, 19, 20  
 Waistcoat, 136, 156, 165, 167, 176, 177, 224  
 Waists, 19, 79, 94, 148, 189, 214  
 Walking-stick, 25, 31, 81, 87, 105, 158, 159  
 Watches, 154  
 Watteau, the, 146, 149, 179  
 Weaving, 20, 40, 53, 73, 88, 95, 166  
 Whalebone, 109, 144, 145, 225  
 Wigs, 44, 134, 139, 157; bob, 170; Campaign, 169, 170; "club," 139, 156; in colonies, 168, 169; Egyptian, 25, 28, 29; following French Revolution, 157; periwig and peruke, 169, 170; powdered, 121; Ramilie, 169, 170; Roman, 75; in sculptured portraits, 75  
 Wilson, Allen B., 194  
 Wimple, 86, 92, 97  
 Wool, 53, 68, 73, 107, 164, 205  
 Woolens, knitted, 228
- Zouave, 189





MAR 6 1950

FEB 10 '67

FEB 10 '67

MAR 2 '67

MAR 7 '67

MAR 13 '67

MAR 29 '67

115

(120)

✓

190


GT510  
.L4

Lutner L. Gobbel Library  
Lambuth College  
Jackson, Tennessee 38301

5559



LAMBETH UNIVERSITY



3 0866 1002 4401 0

850-ADR-058

